
xlwings - Make Excel Fly!

Release dev

Zoomer Analytics LLC

Oct 29, 2022

GETTING STARTED

1	Video course	1
2	Installation	3
2.1	Prerequisites	3
2.2	Installation	3
2.3	Add-in	4
2.4	Dependencies	4
2.5	How to activate xlwings PRO	4
2.6	Optional Dependencies	5
2.7	Update	5
2.8	Uninstall	5
3	Quickstart	7
3.1	1. Interacting with Excel from a Jupyter notebook	7
3.2	2. Scripting: Automate/interact with Excel from Python	7
3.3	3. Macros: Call Python from Excel	8
3.4	4. UDFs: User Defined Functions (Windows only)	9
4	Connect to a Book	11
4.1	Python to Excel	11
4.2	Excel to Python (RunPython)	12
4.3	User Defined Functions (UDFs)	12
5	Syntax Overview	13
5.1	Active Objects	13
5.2	Full qualification	14
5.3	App context manager	14
5.4	Range indexing/slicing	14
5.5	Range Shortcuts	15
5.6	Object Hierarchy	15
6	Data Structures Tutorial	17
6.1	Single Cells	17
6.2	Lists	18
6.3	Range expanding	19
6.4	NumPy arrays	19

6.5	Pandas DataFrames	20
6.6	Pandas Series	20
6.7	Chunking: Read/Write big DataFrames etc.	21
7	Add-in & Settings	23
7.1	Run main	23
7.2	Installation	24
7.3	User Settings	24
7.4	Making use of Environment Variables	25
7.5	User Config: Ribbon/Config File	25
7.6	Workbook Directory Config: Config file	26
7.7	Workbook Config: xlwings.conf Sheet	26
7.8	Alternative: Standalone VBA module	27
8	RunPython	29
8.1	xlwings add-in	29
8.2	Call Python with “RunPython”	29
8.3	Function Arguments and Return Values	30
9	User Defined Functions (UDFs)	31
9.1	One-time Excel preparations	31
9.2	Workbook preparation	31
9.3	A simple UDF	32
9.4	Array formulas: Get efficient	33
9.5	Array formulas with NumPy and Pandas	34
9.6	@xw.arg and @xw.ret decorators	34
9.7	Dynamic Array Formulas	35
9.8	Docstrings	37
9.9	The “caller” argument	37
9.10	The “vba” keyword	37
9.11	Macros	38
9.12	Call UDFs from VBA	38
9.13	Asynchronous UDFs	39
10	Matplotlib & Plotly Charts	41
10.1	Matplotlib	41
10.2	Plotly static charts	45
11	Jupyter Notebooks: Interact with Excel	47
11.1	The view function	47
11.2	The load function	48
12	Command Line Client (CLI)	49
13	Deployment	53
13.1	Zip files	53
13.2	RunFrozenPython	53
14	OneDrive and SharePoint	55

14.1	OneDrive (Personal)	55
14.2	OneDrive for Business	56
14.3	SharePoint (Online and On-Premises)	56
14.4	Implementation Details & Limitations	57
15	Troubleshooting	59
15.1	Issue: dll not found	59
15.2	Issue: Files that are saved on OneDrive or SharePoint cause an error to pop up	59
16	Converters and Options	61
16.1	Default Converter	62
16.2	Built-in Converters	66
16.3	Custom Converter	70
17	Debugging	73
17.1	RunPython	74
17.2	UDF debug server	74
18	Extensions	77
18.1	In-Excel SQL	77
19	Custom Add-ins	79
19.1	Quickstart	79
19.2	Changing the Ribbon menu	81
19.3	Importing UDFs	81
19.4	Configuration	81
19.5	Installation	81
19.6	Renaming your add-in	82
19.7	Deployment	82
20	Threading and Multiprocessing	83
20.1	Threading	83
20.2	Multiprocessing	84
21	Missing Features	87
21.1	Example: Workaround to use VBA's Range.WrapText	87
22	xlwings with other Office Apps	89
22.1	How To	89
22.2	Config	90
23	Overview PRO	91
23.1	PRO Features	91
23.2	License Key Activation	92
24	1-click installer PRO	93
24.1	Step 1: One-Click Installer	93
24.2	Step 2: Release Command (CLI)	96
24.3	Updating a Release	97

24.4	Embedded Code Explained	98
25	Permissioning PRO	101
25.1	Prerequisites	101
25.2	Configuration	102
25.3	GET request	102
25.4	POST request	103
25.5	Implementation Details & Limitations	104
26	Excel File Reader PRO	105
26.1	Reading a specific range	105
26.2	Reading an entire sheet	106
26.3	Converters: DataFrames etc.	106
26.4	Named Ranges	106
26.5	Dynamic Ranges	107
26.6	Cell errors	107
26.7	Limitations	107
27	xlwings Reports PRO	109
27.1	Quickstart	110
27.2	DataFrames	112
27.3	Excel Tables	120
27.4	Excel Charts	121
27.5	Images	126
27.6	Matplotlib and Plotly Plots	127
27.7	Text	128
27.8	Date and Time	130
27.9	Number Format	131
27.10	Frames: Multi-column Layout	131
27.11	PDF Layout	132
28	Markdown Formatting PRO	135
29	xlwings Server PRO	139
29.1	Why is this useful?	139
29.2	Prerequisites	140
29.3	Introduction	141
29.4	Local Development with Desktop Excel	141
29.5	Cloud-based development with Gitpod	142
29.6	Local Development with Google Sheets or Excel on the web	144
29.7	Configuration	147
29.8	Production Deployment	150
29.9	Triggers	150
29.10	Limitations	151
29.11	Roadmap	151
30	What's New	153
30.1	v0.28.4 (Oct 29, 2022)	153
30.2	v0.28.3 (Oct 21, 2022)	153

30.3	v0.28.2 (Oct 17, 2022)	153
30.4	v0.28.1 (Oct 10, 2022)	154
30.5	v0.28.0 (Oct 4, 2022)	155
30.6	v0.27.15 (Sep 16, 2022)	155
30.7	v0.27.14 (Aug 26, 2022)	155
30.8	v0.27.13 (Aug 22, 2022)	156
30.9	v0.27.12 (Aug 8, 2022)	156
30.10	v0.27.11 (Jul 6, 2022)	156
30.11	v0.27.10 (Jun 8, 2022)	156
30.12	v0.27.9 (Jun 4, 2022)	157
30.13	v0.27.8 (May 22, 2022)	157
30.14	v0.27.7 (May 1, 2022)	157
30.15	v0.27.6 (Apr 11, 2022)	157
30.16	v0.27.5 (Apr 1, 2022)	158
30.17	v0.27.4 (Mar 29, 2022)	158
30.18	v0.27.3 (Mar 18, 2022)	158
30.19	v0.27.2 (Mar 11, 2022)	158
30.20	v0.27.0 and v0.27.1 (Mar 8, 2022)	159
30.21	v0.26.3 (Feb 19, 2022)	159
30.22	v0.26.2 (Feb 10, 2022)	159
30.23	v0.26.0 and v0.26.1 (Feb 1, 2022)	160
30.24	v0.25.3 (Dec 16, 2021)	160
30.25	v0.25.2 (Dec 3, 2021)	160
30.26	v0.25.1 (Nov 21, 2021)	160
30.27	v0.25.0 (Oct 27, 2021)	161
30.28	v0.24.9 (Aug 26, 2021)	161
30.29	v0.24.8 (Aug 25, 2021)	161
30.30	v0.24.7 (Aug 5, 2021)	162
30.31	v0.24.6 (Jul 31, 2021)	162
30.32	v0.24.5 (Jul 27, 2021)	162
30.33	v0.24.4 (Jul 26, 2021)	162
30.34	v0.24.3 (Jul 15, 2021)	163
30.35	v0.24.2 (Jul 6, 2021)	164
30.36	v0.24.1 (Jun 27, 2021)	164
30.37	v0.24.0 (Jun 25, 2021)	164
30.38	v0.23.4 (Jun 15, 2021)	165
30.39	v0.23.3 (May 17, 2021)	165
30.40	v0.23.2 (May 7, 2021)	165
30.41	v0.23.1 (Apr 19, 2021)	166
30.42	v0.23.0 (Mar 5, 2021)	166
30.43	v0.22.3 (Mar 3, 2021)	167
30.44	v0.22.2 (Feb 8, 2021)	168
30.45	v0.22.1 (Feb 4, 2021)	168
30.46	v0.22.0 (Jan 29, 2021)	168
30.47	Older Releases	168

31	License	213
31.1	xlwings (Open Source)	213

31.2	xlwings PRO	213
32	Open Source Licenses	215
32.1	pywin32 (Windows only)	215
32.2	psutil (macOS only)	217
32.3	Appscript (macOS only)	217
32.4	Mistune	218
32.5	VBA-Dictionary	219
32.6	VBA-Web	219
33	Python API	221
33.1	Top-level functions	221
33.2	Object model	222
33.3	UDF decorators	271
33.4	Reports	273
34	REST API	275
34.1	Quickstart	275
34.2	Run the server	277
34.3	Indexing	277
34.4	Range Options	277
34.5	Endpoint overview	277
34.6	Endpoint details	278
	Index	307

VIDEO COURSE

Those who prefer a didactically structured video course over this documentation should have a look at our video course:

<https://training.xlwings.org/p/xlwings>

It's also a great way to support the ongoing development of xlwings :)

INSTALLATION

2.1 Prerequisites

- xlwings (Open Source) requires an **installation of Excel** and therefore only works on **Windows** and **macOS**. Note that macOS currently does not support UDFs.
- **xlwings PRO offers additional features:**
 - *File Reader* (new in v0.28.0): Runs additionally on Linux and doesn't require an installation of Excel.
 - *xlwings Server* (new in v0.26.0). Runs additionally on Linux and doesn't require a local installation of Python. Works with Desktop Excel on Windows and macOS as well as with Excel on the web and Google Sheets.
- xlwings requires at least Python 3.7.

Here are previous versions of xlwings that support older versions of Python:

- Python 3.6: 0.25.3
- Python 3.5: 0.19.5
- Python 2.7: 0.16.6

2.2 Installation

xlwings comes pre-installed with

- [Anaconda](#) (Windows and macOS)
- [WinPython](#) (Windows only) Make sure **not** to take the dot version as this only contains Python.

If you are new to Python or have trouble installing xlwings, one of these distributions is highly recommended. Otherwise, you can also install it with pip:

```
pip install xlwings
```

or conda:

```
conda install xlwings
```

Note that the official conda package might be a few releases behind. You can, however, use the `conda-forge` channel (replace `install` with `update` if `xlwings` is already installed):

```
conda install -c conda-forge xlwings
```

2.3 Add-in

To install the add-in, run the following command:

```
xlwings addin install
```

To automate Excel from Python, you don't need an add-in. Also, you can use a single file VBA module (*standalone workbook*) instead of the add-in. For more details, see [Add-in & Settings](#).

Note: The add-in needs to be the same version as the Python package. Make sure to run `xlwings add install` again after upgrading the `xlwings` package.

Note: When you are on macOS and are using the VBA standalone module instead of the add-in, you need to run `$ xlwings runpython install` once.

2.4 Dependencies

For automating Excel, you'll need the following dependencies:

- **Windows:** `pywin32`
- **Mac:** `psutil`, `appscript`

The dependencies are automatically installed via `conda` or `pip`. If you would like to install `xlwings` without dependencies, you can run `pip install xlwings --no-deps`.

2.5 How to activate xlwings PRO

See *xlwings PRO*.

2.6 Optional Dependencies

- NumPy
- pandas
- Matplotlib
- Pillow
- Jinja2 (for xlwings.pro.reports)
- requests (for permissioning)

These packages are not required but highly recommended as they play very nicely with xlwings. They are all pre-installed with Anaconda. With pip, you can install xlwings with all optional dependencies as follows:

```
pip install "xlwings[all]"
```

2.7 Update

To update to the latest xlwings version, run the following in a command prompt:

```
pip install --upgrade xlwings
```

or:

```
conda update -c conda-forge xlwings
```

Make sure to keep your version of the Excel add-in in sync with your Python package by running the following (make sure to close Excel first):

```
xlwings addin install
```

2.8 Uninstall

To uninstall xlwings completely, first uninstall the add-in, then uninstall the xlwings package using the same method (pip or conda) that you used for installing it:

```
xlwings addin remove
```

Then

```
pip uninstall xlwings
```

or:

```
conda remove xlwings
```

Finally, manually remove the `.xlwings` directory in your home folder if it exists.

QUICKSTART

This guide assumes you have `xlwings` already installed. If that's not the case, head over to [Installation](#).

3.1 1. Interacting with Excel from a Jupyter notebook

If you're just interested in getting a pandas DataFrame in and out of your Jupyter notebook, you can use the view and load functions, see *Jupyter Notebooks: Interact with Excel*.

3.2 2. Scripting: Automate/interact with Excel from Python

Establish a connection to a workbook:

```
>>> import xlwings as xw
>>> wb = xw.Book() # this will open a new workbook
>>> wb = xw.Book('FileName.xlsx') # connect to a file that is open or in the
↳current working directory
>>> wb = xw.Book(r'C:\path\to\file.xlsx') # on Windows: use raw strings to
↳escape backslashes
```

If you have the same file open in two instances of Excel, you need to fully qualify it and include the app instance. You will find your app instance key (the PID) via `xw.apps.keys()`:

```
>>> xw.apps[10559].books['FileName.xlsx']
```

Instantiate a sheet object:

```
>>> sheet = wb.sheets['Sheet1']
```

Reading/writing values to/from ranges is as easy as:

```
>>> sheet['A1'].value = 'Foo 1'
>>> sheet['A1'].value
'Foo 1'
```

There are many **convenience features** available, e.g. Range expanding:

```
>>> sheet['A1'].value = [['Foo 1', 'Foo 2', 'Foo 3'], [10.0, 20.0, 30.0]]
>>> sheet['A1'].expand().value
[['Foo 1', 'Foo 2', 'Foo 3'], [10.0, 20.0, 30.0]]
```

Powerful converters handle most data types of interest, including Numpy arrays and Pandas DataFrames in both directions:

```
>>> import pandas as pd
>>> df = pd.DataFrame([[1,2], [3,4]], columns=['a', 'b'])
>>> sheet['A1'].value = df
>>> sheet['A1'].options(pd.DataFrame, expand='table').value
      a    b
0.0  1.0  2.0
1.0  3.0  4.0
```

Matplotlib figures can be shown as pictures in Excel:

```
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.plot([1, 2, 3, 4, 5])
[<matplotlib.lines.Line2D at 0x1071706a0>]
>>> sheet.pictures.add(fig, name='MyPlot', update=True)
<Picture 'MyPlot' in <Sheet [Workbook4]Sheet1>>
```

3.3 3. Macros: Call Python from Excel

You can call Python functions either by clicking the Run button (new in v0.16) in the add-in or from VBA using the `RunPython` function:

The Run button expects a function called `main` in a Python module with the same name as your workbook. The great thing about that approach is that you don't need your workbooks to be macro-enabled, you can save it as `xlsx`.

If you want to call any Python function no matter in what module it lives or what name it has, use `RunPython`:

```
Sub HelloWorld()
    RunPython "import hello; hello.world()"
End Sub
```

Note: Per default, `RunPython` expects `hello.py` in the same directory as the Excel file with the same name, **but you can change both of these things**: if your Python file is in a different folder, add that folder to the `PYTHONPATH` in the config. If the file has a different name, change the `RunPython` command accordingly.

Refer to the calling Excel book by using `xw.Book.caller()`:


```
# hello.py
import numpy as np
import xlwings as xw

def world():
    wb = xw.Book.caller()
    wb.sheets[0]['A1'].value = 'Hello World!'
```

To make this run, you'll need to have the xlwings add-in installed or have the workbooks setup in the standalone mode. The easiest way to get everything set up is to use the xlwings command line client from either a command prompt on Windows or a terminal on Mac: `xlwings quickstart myproject`.

For details about the addin, see [Add-in & Settings](#).

3.4 4. UDFs: User Defined Functions (Windows only)

Writing a UDF in Python is as easy as:

```
import xlwings as xw

@xw.func
def hello(name):
    return f'Hello {name}'
```

Converters can be used with UDFs, too. Again a Pandas DataFrame example:

```
import xlwings as xw
import pandas as pd

@xw.func
@xw.arg('x', pd.DataFrame)
def correl2(x):
    # x arrives as DataFrame
    return x.corr()
```

Import this function into Excel by clicking the import button of the xlwings add-in: for a step-by-step tutorial, see [User Defined Functions \(UDFs\)](#).

CONNECT TO A BOOK

4.1 Python to Excel

The easiest way to connect to a book is offered by `xw.Book`: it looks for the book in all app instances and returns an error, should the same book be open in multiple instances. To connect to a book in the active app instance, use `xw.books` and to refer to a specific app, use:

```
>>> app = xw.App() # or something like xw.apps[10559] for existing apps, get
↳ the available PIDs via xw.apps.keys()
>>> app.books['Book1']
```

Note that you usually should use `App` as a context manager as this will make sure that the Excel instance is closed and cleaned up again properly:

```
with xw.App() as app:
    book = app.books['Book1']
```

	<code>xw.Book</code>	<code>xw.books</code>
New book	<code>xw.Book()</code>	<code>xw.books.add()</code>
Unsaved book	<code>xw.Book('Book1')</code>	<code>xw.books['Book1']</code>
Book by (full)name	<code>xw.Book(r'C:/path/to/file.xlsx')</code>	<code>xw.books.open(r'C:/path/to/file.xlsx')</code>

Note: When specifying file paths on Windows, you should either use raw strings by putting an `r` in front of the string or use double back-slashes like so: `C:\\path\\to\\file.xlsx`.

4.2 Excel to Python (RunPython)

To reference the calling book when using `RunPython` in VBA, use `xw.Book.caller()`, see *Call Python with “RunPython”*. Check out the section about *Debugging* to see how you can call a script from both sides, Python and Excel, without the need to constantly change between `xw.Book.caller()` and one of the methods explained above.

4.3 User Defined Functions (UDFs)

Unlike `RunPython`, UDFs don't need a call to `xw.Book.caller()`, see *User Defined Functions (UDFs)*. You'll usually use the `caller` argument which returns the xlwings range object from where you call the function.

SYNTAX OVERVIEW

The xlwings object model is very similar to the one used by VBA.

All code samples below depend on the following import:

```
>>> import xlwings as xw
```

5.1 Active Objects

```
# Active app (i.e. Excel instance)
>>> app = xw.apps.active

# Active book
>>> wb = xw.books.active # in active app
>>> wb = app.books.active # in specific app

# Active sheet
>>> sheet = xw.sheets.active # in active book
>>> sheet = wb.sheets.active # in specific book
```

A Range can be instantiated with A1 notation, a tuple of Excel's 1-based indices, or a named range:

```
import xlwings as xw
sheet1 = xw.Book("MyBook.xlsx").sheets[0]

sheet1.range("A1")
sheet1.range("A1:C3")
sheet1.range((1,1))
sheet1.range((1,1), (3,3))
sheet1.range("NamedRange")

# Or using index/slice notation
sheet1["A1"]
sheet1["A1:C3"]
sheet1[0, 0]
```

(continues on next page)

(continued from previous page)

```
sheet1[0:4, 0:4]  
sheet1["NamedRange"]
```

5.2 Full qualification

Round brackets follow Excel's behavior (i.e. 1-based indexing), while square brackets use Python's 0-based indexing/slicing. As an example, the following expressions all reference the same range:

```
xw.apps[763].books[0].sheets[0].range('A1')  
xw.apps(10559).books(1).sheets(1).range('A1')  
xw.apps[763].books['Book1'].sheets['Sheet1'].range('A1')  
xw.apps(10559).books('Book1').sheets('Sheet1').range('A1')
```

Note that the apps keys are different for you as they are the process IDs (PID). You can get the list of your PIDs via `xw.apps.keys()`.

5.3 App context manager

If you want to open a new Excel instance via `App()`, you usually should use `App` as a context manager as this will make sure that the Excel instance is closed and cleaned up again properly:

```
with xw.App() as app:  
    book = app.books['Book1']
```

5.4 Range indexing/slicing

Range objects support indexing and slicing, a few examples:

```
>>> myrange = xw.Book().sheets[0].range('A1:D5')  
>>> myrange[0, 0]  
<Range [Workbook1]Sheet1!$A$1>  
>>> myrange[1]  
<Range [Workbook1]Sheet1!$B$1>  
>>> myrange[:, 3:]  
<Range [Workbook1]Sheet1!$D$1:$D$5>  
>>> myrange[1:3, 1:3]  
<Range [Workbook1]Sheet1!$B$2:$C$3>
```

5.5 Range Shortcuts

Sheet objects offer a shortcut for range objects by using index/slice notation on the sheet object. This evaluates to either `sheet.range` or `sheet.cells` depending on whether you pass a string or indices/slices:

```
>>> sheet = xw.Book().sheets['Sheet1']
>>> sheet['A1']
<Range [Book1]Sheet1!$A$1>
>>> sheet['A1:B5']
<Range [Book1]Sheet1!$A$1:$B$5>
>>> sheet[0, 1]
<Range [Book1]Sheet1!$B$1>
>>> sheet[:10, :10]
<Range [Book1]Sheet1!$A$1:$J$10>
```

5.6 Object Hierarchy

The following shows an example of the object hierarchy, i.e. how to get from an app to a range object and all the way back:

```
>>> myrange = xw.apps[10559].books[0].sheets[0].range('A1')
>>> myrange.sheet.book.app
<Excel App 10559>
```


DATA STRUCTURES TUTORIAL

This tutorial gives you a quick introduction to the most common use cases and default behaviour of xlwings when reading and writing values. For an in-depth documentation of how to control the behavior using the `options` method, have a look at *Converters and Options*.

All code samples below depend on the following import:

```
>>> import xlwings as xw
```

6.1 Single Cells

Single cells are by default returned either as float, unicode, None or datetime objects, depending on whether the cell contains a number, a string, is empty or represents a date:

```
>>> import datetime as dt
>>> sheet = xw.Book().sheets[0]
>>> sheet['A1'].value = 1
>>> sheet['A1'].value
1.0
>>> sheet['A2'].value = 'Hello'
>>> sheet['A2'].value
'Hello'
>>> sheet['A3'].value is None
True
>>> sheet['A4'].value = dt.datetime(2000, 1, 1)
>>> sheet['A4'].value
datetime.datetime(2000, 1, 1, 0, 0)
```

6.2 Lists

- 1d lists: Ranges that represent rows or columns in Excel are returned as simple lists, which means that once they are in Python, you've lost the information about the orientation. If that is an issue, the next point shows you how to preserve this info:

```
>>> sheet = xw.Book().sheets[0]
>>> sheet['A1'].value = [[1],[2],[3],[4],[5]] # Column orientation (nested
↪list)
>>> sheet['A1:A5'].value
[1.0, 2.0, 3.0, 4.0, 5.0]
>>> sheet['A1'].value = [1, 2, 3, 4, 5]
>>> sheet['A1:E1'].value
[1.0, 2.0, 3.0, 4.0, 5.0]
```

To force a single cell to arrive as list, use:

```
>>> sheet['A1'].options(ndim=1).value
[1.0]
```

Note: To write a list in column orientation to Excel, use `transpose`: `sheet.range('A1').options(transpose=True).value = [1,2,3,4]`

- 2d lists: If the row or column orientation has to be preserved, set `ndim` in the Range options. This will return the Ranges as nested lists ("2d lists"):

```
>>> sheet['A1:A5'].options(ndim=2).value
[[1.0], [2.0], [3.0], [4.0], [5.0]]
>>> sheet['A1:E1'].options(ndim=2).value
[[1.0, 2.0, 3.0, 4.0, 5.0]]
```

- 2 dimensional Ranges are automatically returned as nested lists. When assigning (nested) lists to a Range in Excel, it's enough to just specify the top left cell as target address. This sample also makes use of index notation to read the values back into Python:

```
>>> sheet['A10'].value = [['Foo 1', 'Foo 2', 'Foo 3'], [10, 20, 30]]
>>> sheet.range((10,1),(11,3)).value
[['Foo 1', 'Foo 2', 'Foo 3'], [10.0, 20.0, 30.0]]
```

Note: Try to minimize the number of interactions with Excel. It is always more efficient to do `sheet.range('A1').value = [[1,2],[3,4]]` than `sheet.range('A1').value = [1, 2]` and `sheet.range('A2').value = [3, 4]`.

6.3 Range expanding

You can get the dimensions of Excel Ranges dynamically through either the method `expand` or through the `expand` keyword in the `options` method. While `expand` gives back an expanded Range object, `options` are only evaluated when accessing the values of a Range. The difference is best explained with an example:

```
>>> sheet = xw.Book().sheets[0]
>>> sheet['A1'].value = [[1,2], [3,4]]
>>> range1 = sheet['A1'].expand('table') # or just .expand()
>>> range2 = sheet['A1'].options(expand='table')
>>> range1.value
[[1.0, 2.0], [3.0, 4.0]]
>>> range2.value
[[1.0, 2.0], [3.0, 4.0]]
>>> sheet['A3'].value = [5, 6]
>>> range1.value
[[1.0, 2.0], [3.0, 4.0]]
>>> range2.value
[[1.0, 2.0], [3.0, 4.0], [5.0, 6.0]]
```

'table' expands to 'down' and 'right', the other available options which can be used for column or row only expansion, respectively.

Note: Using `expand()` together with a named Range as top left cell gives you a flexible setup in Excel: You can move around the table and change its size without having to adjust your code, e.g. by using something like `sheet.range('NamedRange').expand().value`.

6.4 NumPy arrays

NumPy arrays work similar to nested lists. However, empty cells are represented by `nan` instead of `None`. If you want to read in a Range as array, set `convert=np.array` in the `options` method:

```
>>> import numpy as np
>>> sheet = xw.Book().sheets[0]
>>> sheet['A1'].value = np.eye(3)
>>> sheet['A1'].options(np.array, expand='table').value
array([[ 1.,  0.,  0.],
       [ 0.,  1.,  0.],
       [ 0.,  0.,  1.]])
```

6.5 Pandas DataFrames

```
>>> sheet = xw.Book().sheets[0]
>>> df = pd.DataFrame([[1.1, 2.2], [3.3, None]], columns=['one', 'two'])
>>> df
   one  two
0  1.1  2.2
1  3.3  NaN
>>> sheet['A1'].value = df
>>> sheet['A1:C3'].options(pd.DataFrame).value
   one  two
0  1.1  2.2
1  3.3  NaN
# options: work for reading and writing
>>> sheet['A5'].options(index=False).value = df
>>> sheet['A9'].options(index=False, header=False).value = df
```

6.6 Pandas Series

```
>>> import pandas as pd
>>> import numpy as np
>>> sheet = xw.Book().sheets[0]
>>> s = pd.Series([1.1, 3.3, 5., np.nan, 6., 8.], name='myseries')
>>> s
0    1.1
1    3.3
2    5.0
3    NaN
4    6.0
5    8.0
Name: myseries, dtype: float64
>>> sheet['A1'].value = s
>>> sheet['A1:B7'].options(pd.Series).value
0    1.1
1    3.3
2    5.0
3    NaN
4    6.0
5    8.0
Name: myseries, dtype: float64
```

Note: You only need to specify the top left cell when writing a list, a NumPy array or a Pandas DataFrame to Excel, e.g.: `sheet['A1'].value = np.eye(10)`

6.7 Chunking: Read/Write big DataFrames etc.

When you read and write from or to big ranges, you may have to chunk them or you will hit a timeout or a memory error. The ideal chunksize will depend on your system and size of the array, so you will have to try out a few different chunksizes to find one that works well:

```
import pandas as pd
import numpy as np
sheet = xw.Book().sheets[0]
data = np.arange(75_000 * 20).reshape(75_000, 20)
df = pd.DataFrame(data=data)
sheet['A1'].options(chunksize=10_000).value = df
```

And the same for reading:

```
# As DataFrame
df = sheet['A1'].expand().options(pd.DataFrame, chunksize=10_000).value
# As list of list
df = sheet['A1'].expand().options(chunksize=10_000).value
```


ADD-IN & SETTINGS



The xlwings add-in is the preferred way to be able to use the `Run main` button, `RunPython` or UDFs. Note that you don't need an add-in if you just want to manipulate Excel by running a Python script.

Note: The ribbon of the add-in is compatible with Excel ≥ 2007 on Windows and ≥ 2016 on macOS. On macOS, all UDF related functionality is not available.

Note: The add-in is password protected with the password `xlwings`. For debugging or to add new extensions, you need to unprotect it. Alternatively, you can also install the add-in via `xlwings addin install --unprotected`.

7.1 Run main

New in version 0.16.0.


The `Run main` button is the easiest way to run your Python code: It runs a function called `main` in a Python module that has the same name as your workbook. This allows you to save your workbook as `xlsx` without enabling macros. The `xlwings quickstart` command will create a workbook that will automatically work with the `Run` button.

7.2 Installation

To install the add-in, use the command line client:

```
xlwings addin install
```

Technically, this copies the add-in from Python's installation directory to Excel's XLSTART folder. Then, to use RunPython or UDFs in a workbook, you need to set a reference to xlwings in the VBA editor, see screenshot (Windows: Tools > References..., Mac: it's on the lower left corner of the VBA editor). Note that when you create a workbook via `xlwings quickstart`, the reference should already be set.



7.3 User Settings

When you install the add-in for the first time, it will get auto-configured and therefore, a `quickstart` project should work out of the box. For fine-tuning, here are the available settings:

- **Interpreter:** This is the path to the Python interpreter. This works also with virtual or conda envs on Mac. If you use conda envs on Windows, then leave this empty and use `Conda Path` and `Conda Env` below instead. Examples: `"C:\Python39\pythonw.exe"` or `"/usr/local/bin/python3.9"`. Note that in the settings, this is stored as `Interpreter_Win` or `Interpreter_Mac`, respectively, see below!
- **PYTHONPATH:** If the source file of your code is not found, add the path to its directory here.
- **Conda Path:** If you are on Windows and use Anaconda or Miniconda, then type here the path to your installation, e.g. `C:\Users\Username\Miniconda3` or `%USERPROFILE%\Anaconda`. NOTE that you need at least conda 4.6! You also need to set `Conda Env`, see next point.

- **Conda Env:** If you are on Windows and use Anaconda or Miniconda, type here the name of your conda env, e.g. `base` for the base installation or `myenv` for a conda env with the name `myenv`.
- **UDF Modules:** Names of Python modules (without `.py` extension) from which the UDFs are being imported. Separate multiple modules by “;”. Example: `UDF_MODULES = "common_udfs;myproject"`
The default imports a file in the same directory as the Excel spreadsheet with the same name but ending in `.py`.
- **Debug UDFs:** Check this box if you want to run the xlwings COM server manually for debugging, see [Debugging](#).
- **RunPython: Use UDF Server:** Uses the same COM Server for RunPython as for UDFs. This will be faster, as the interpreter doesn’t shut down after each call.
- **Restart UDF Server:** This restarts the UDF Server/Python interpreter.
- **Show Console:** Check the box in the ribbon or set the config to `TRUE` if you want the command prompt to pop up. This currently only works on Windows.
- **ADD_WORKBOOK_TO_PYTHONPATH:** Uncheck this box to not automatically add the directory of your workbook to the `PYTHONPATH`. This can be helpful if you experience issues with OneDrive/SharePoint: uncheck this box and provide the path where your source file is manually via the `PYTHONPATH` setting.

7.3.1 Anaconda/Miniconda

If you use Anaconda or Miniconda on Windows, you will need to set your `Conda Path` and `Conda Env` settings, as you will otherwise get errors when using NumPy etc. In return, leave `Interpreter` empty.

7.4 Making use of Environment Variables

With environment variables, you can set dynamic paths e.g. to your interpreter or `PYTHONPATH`:

- On Windows, you can use all environment variables like so: `%USERPROFILE%\Anaconda`.
- On macOS, the following special variables are supported: `$HOME`, `$APPLICATIONS`, `$DOCUMENTS`, `$DESKTOP`.

7.5 User Config: Ribbon/Config File

The settings in the xlwings Ribbon are stored in a config file that can also be manipulated externally. The location is

- Windows: `.xlwings\xlwings.conf` in your home folder, that is usually `C:\Users\<username>`
- macOS: `~/Library/Containers/com.microsoft.Excel/Data/xlwings.conf`

The format is as follows (currently the keys are required to be all caps) - note the OS specific Interpreter settings!

```
"INTERPRETER_WIN", "C:\\path\\to\\python.exe"
"INTERPRETER_MAC", "/path/to/python"
"PYTHONPATH", ""
"ADD_WORKBOOK_TO_PYTHONPATH", ""
"CONDA_PATH", ""
"CONDA_ENV", ""
"UDF_MODULES", ""
"DEBUG_UDFS", ""
"USE_UDF_SERVER", ""
"SHOW_CONSOLE", ""
"ONEDRIVE_CONSUMER_WIN", ""
"ONEDRIVE_CONSUMER_MAC", ""
"ONEDRIVE_COMMERCIAL_WIN", ""
"ONEDRIVE_COMMERCIAL_MAC", ""
"SHAREPOINT_WIN", ""
"SHAREPOINT_MAC", ""
```

Note: The ONEDRIVE_WIN/_MAC setting has to be edited directly in the file, there is currently no possibility to edit it via the ribbon. Usually, it is only required if you are either on macOS or if your environment variables on Windows are not correctly set or if you have a private and corporate location and don't want to go with the default one. ONEDRIVE_WIN/_MAC has to point to the root folder of your local OneDrive folder.

7.6 Workbook Directory Config: Config file

The global settings of the Ribbon/Config file can be overridden for one or more workbooks by creating a `xlwings.conf` file in the workbook's directory.

Note: Workbook directory config files are not supported if your workbook is stored on SharePoint or OneDrive.

7.7 Workbook Config: xlwings.conf Sheet

Workbook specific settings will override global (Ribbon) and workbook directory config files: Workbook specific settings are set by listing the config key/value pairs in a sheet with the name `xlwings.conf`. When you create a new project with `xlwings quickstart`, it'll already have such a sheet but you need to rename it to `xlwings.conf` to make it active.

	A	B
1	Interpreter	pythonw
2	PYTHONPATH	
3	UDF Modules	
4	Debug UDFs	FALSE
5	Log File	
6	Use UDF Server	FALSE
-		

7.8 Alternative: Standalone VBA module

Sometimes, it might be useful to run xlwings code without having to install an add-in first. To do so, you need to use the `standalone` option when creating a new project: `xlwings quickstart myproject --standalone`.

This will add the content of the add-in as a single VBA module so you don't need to set a reference to the add-in anymore. It will also include `Dictionary.cls` as this is required on macOS. It will still read in the settings from your `xlwings.conf` if you don't override them by using a sheet with the name `xlwings.conf`.

RUNPYTHON

8.1 xlwings add-in

To get access to `Run main` (new in v0.16) button or the `RunPython` VBA function, you'll need the `xlwings` addin (or VBA module), see *Add-in & Settings*.

For new projects, the easiest way to get started is by using the command line client with the `quickstart` command, see *Command Line Client (CLI)* for details:

```
$ xlwings quickstart myproject
```

8.2 Call Python with “RunPython”

In the VBA Editor (Alt-F11), write the code below into a VBA module. `xlwings quickstart` automatically adds a new module with a sample call. If you rather want to start from scratch, you can add a new module via `Insert > Module`.

```
Sub HelloWorld()  
    RunPython "import hello; hello.world()"   
End Sub
```

This calls the following code in `hello.py`:

```
# hello.py  
import numpy as np  
import xlwings as xw  
  
def world():  
    wb = xw.Book.caller()  
    wb.sheets[0]['A1'].value = 'Hello World!'
```

You can then attach `HelloWorld` to a button or run it directly in the VBA Editor by hitting F5.

Note: Place `xw.Book.caller()` within the function that is being called from Excel and not outside as global variable. Otherwise it prevents Excel from shutting down properly upon exiting and leaves you with

a zombie process when you use `Use UDF Server = True`.

8.3 Function Arguments and Return Values

While it's technically possible to include arguments in the function call within `RunPython`, it's not very convenient. Also, `RunPython` does not allow you to return values. To overcome these issues, use UDFs, see *User Defined Functions (UDFs)* - however, this is currently limited to Windows only.

USER DEFINED FUNCTIONS (UDFS)

This tutorial gets you quickly started on how to write User Defined Functions.

Note:

- UDFs are currently only available on Windows.
 - For details of how to control the behaviour of the arguments and return values, have a look at *Converters and Options*.
 - For a comprehensive overview of the available decorators and their options, check out the corresponding API docs: *UDF decorators*.
-

9.1 One-time Excel preparations

- 1) Enable Trust access to the VBA project object model under File > Options > Trust Center > Trust Center Settings > Macro Settings. You only need to do this once. Also, this is only required for importing the functions, i.e. end users won't need to bother about this.
- 2) Install the add-in via command prompt: `xlwings addin install` (see *Add-in & Settings*).

9.2 Workbook preparation

The easiest way to start a new project is to run `xlwings quickstart myproject` on a command prompt (see *Command Line Client (CLI)*). This automatically adds the xlwings reference to the generated workbook.

9.3 A simple UDF

The default addin settings expect a Python source file in the way it is created by `quickstart`:

- in the same directory as the Excel file
- with the same name as the Excel file, but with a `.py` ending instead of `.xlsm`.

Alternatively, you can point to a specific module via **UDF Modules** in the xlwings ribbon.

Let's assume you have a Workbook `myproject.xlsm`, then you would write the following code in `myproject.py`:

```
import xlwings as xw

@xw.func
def double_sum(x, y):
    """Returns twice the sum of the two arguments"""
    return 2 * (x + y)
```

- Now click on **Import Python UDFs** in the xlwings tab to pick up the changes made to `myproject.py`.
- Enter the formula `=double_sum(1, 2)` into a cell and you will see the correct result:



- The docstring (in triple-quotes) will be shown as function description in Excel.

Note:

- You only need to re-import your functions if you change the function arguments or the function name.
 - Code changes in the actual functions are picked up automatically (i.e. at the next calculation of the formula, e.g. triggered by `Ctrl-Alt-F9`), but changes in imported modules are not. This is the very behaviour of how Python imports work. If you want to make sure everything is in a fresh state, click **Restart UDF Server**.
 - The `@xw.func` decorator is only used by xlwings when the function is being imported into Excel. It tells xlwings for which functions it should create a VBA wrapper function, otherwise it has no effect on how the functions behave in Python.
-

9.4 Array formulas: Get efficient

Calling one big array formula in Excel is much more efficient than calling many single-cell formulas, so it's generally a good idea to use them, especially if you hit performance problems.

You can pass an Excel Range as a function argument, as opposed to a single cell and it will show up in Python as list of lists.

For example, you can write the following function to add 1 to every cell in a Range:

```
@xw.func
def add_one(data):
    return [[cell + 1 for cell in row] for row in data]
```

To use this formula in Excel,

- Click on Import Python UDFs again
- Fill in the values in the range A1:B2
- Select the range D1:E2
- Type in the formula =add_one(A1:B2)
- Press Ctrl+Shift+Enter to create an array formula. If you did everything correctly, you'll see the formula surrounded by curly braces as in this screenshot:

	A	B	C	D	E	F	G	H	I	J
1	1	2		2	3					
2	3	4		4	5					
3										

9.4.1 Number of array dimensions: ndim

The above formula has the issue that it expects a “two dimensional” input, e.g. a nested list of the form `[[1, 2], [3, 4]]`. Therefore, if you would apply the formula to a single cell, you would get the following error: `TypeError: 'float' object is not iterable`.

To force Excel to always give you a two-dimensional array, no matter whether the argument is a single cell, a column/row or a two-dimensional Range, you can extend the above formula like this:

```
@xw.func
@xw.arg('data', ndim=2)
def add_one(data):
    return [[cell + 1 for cell in row] for row in data]
```

9.5 Array formulas with NumPy and Pandas

Often, you'll want to use NumPy arrays or Pandas DataFrames in your UDF, as this unlocks the full power of Python's ecosystem for scientific computing.

To define a formula for matrix multiplication using numpy arrays, you would define the following function:

```
import xlwings as xw
import numpy as np

@xw.func
@xw.arg('x', np.array, ndim=2)
@xw.arg('y', np.array, ndim=2)
def matrix_mult(x, y):
    return x @ y
```

Note: If you are not on Python >= 3.5 with NumPy >= 1.10, use `x.dot(y)` instead of `x @ y`.

A great example of how you can put Pandas at work is the creation of an array-based CORREL formula. Excel's version of CORREL only works on 2 datasets and is cumbersome to use if you want to quickly get the correlation matrix of a few time-series, for example. Pandas makes the creation of an array-based CORREL2 formula basically a one-liner:

```
import xlwings as xw
import pandas as pd

@xw.func
@xw.arg('x', pd.DataFrame, index=False, header=False)
@xw.ret(index=False, header=False)
def CORREL2(x):
    """Like CORREL, but as array formula for more than 2 data sets"""
    return x.corr()
```

9.6 @xw.arg and @xw.ret decorators

These decorators are to UDFs what the `options` method is to Range objects: they allow you to apply converters and their options to function arguments (`@xw.arg`) and to the return value (`@xw.ret`). For example, to convert the argument `x` into a pandas DataFrame and suppress the index when returning it, you would do the following:

```
@xw.func
@xw.arg('x', pd.DataFrame)
@xw.ret(index=False)
def myfunction(x):
```

(continues on next page)

(continued from previous page)

```
# x is a DataFrame, do something with it
return x
```

For further details see the *Converters and Options* documentation.

9.7 Dynamic Array Formulas

Note: If your version of Excel supports the new native dynamic arrays, then you don't have to do anything special, and you shouldn't use the `expand` decorator! To check if your version of Excel supports it, see if you have the `=UNIQUE()` formula available. Native dynamic arrays were introduced in Office 365 Insider Fast at the end of September 2018.

As seen above, to use Excel's array formulas, you need to specify their dimensions upfront by selecting the result array first, then entering the formula and finally hitting `Ctrl-Shift-Enter`. In practice, it often turns out to be a cumbersome process, especially when working with dynamic arrays such as time series data. Since v0.10, xlwings offers dynamic UDF expansion:

This is a simple example that demonstrates the syntax and effect of UDF expansion:

```
import numpy as np

@xw.func
@xw.ret(expand='table')
def dynamic_array(r, c):
    return np.random.randn(int(r), int(c))
```

Note:

- Expanding array formulas will overwrite cells without prompting
- Pre v0.15.0 doesn't allow to have volatile functions as arguments, e.g. you cannot use functions like `=TODAY()` as arguments. Starting with v0.15.0, you can use volatile functions as input, but the UDF will be called more than 1x.
- Dynamic Arrays have been refactored with v0.15.0 to be proper legacy arrays: To edit a dynamic array with xlwings `>= v0.15.0`, you need to hit `Ctrl-Shift-Enter` while in the top left cell. Note that you don't have to do that when you enter the formula for the first time.

File Home Insert Page Layout Formulas Data Review					
B4 ✕ ✓ <i>fx</i> =dynamic_array(B2,C2)					
	A	B	C	D	E
1		rows:	columns:		
2		5	2		
3					
4		2.01156647	-0.0985618		
5		-0.2152179	-0.7541961		
6		0.37168657	-0.1978662		
7		-1.0643897	1.37592295		
8		0.5272535	-0.0508628		
9					

File Home Insert Page Layout Formulas Data Review View xlwings							
B4 ✕ ✓ <i>fx</i> =dynamic_array(B2,C2)							
	A	B	C	D	E	F	
1		rows:	columns:				
2		2	5				
3							
4		-0.6788379	-1.0009999	-0.6342434	-0.9362773	1.02582914	
5		-2.1803953	0.18511092	0.3121721	0.20600051	0.3799863	
6							

9.8 Docstrings

The following sample shows how to include docstrings both for the function and for the arguments x and y that then show up in the function wizard in Excel:

```
import xlwings as xw

@xw.func
@xw.arg('x', doc='This is x.')
@xw.arg('y', doc='This is y.')
def double_sum(x, y):
    """Returns twice the sum of the two arguments"""
    return 2 * (x + y)
```

9.9 The “caller” argument

You often need to know which cell called the UDF. For this, xlwings offers the reserved argument caller which returns the calling cell as xlwings range object:

```
@xw.func
def get_caller_address(caller):
    # caller will not be exposed in Excel, so use it like so:
    # =get_caller_address()
    return caller.address
```

Note that caller will not be exposed in Excel but will be provided by xlwings behind the scenes.

9.10 The “vba” keyword

By using the vba keyword, you can get access to any Excel VBA object in the form of a pywin32 object. For example, if you wanted to pass the sheet object in the form of its CodeName, you can do it as follows:

```
@xw.func
@xw.arg('sheet1', vba='Sheet1')
def get_name(sheet1):
    # call this function in Excel with:
    # =get_name()
    return sheet1.Name
```

Note that vba arguments are not exposed in the UDF but automatically provided by xlwings.

9.11 Macros

On Windows, as an alternative to calling macros via *RunPython*, you can also use the `@xw.sub` decorator:

```
import xlwings as xw

@xw.sub
def my_macro():
    """Writes the name of the Workbook into Range("A1") of Sheet 1"""
    wb = xw.Book.caller()
    wb.sheets[0].range('A1').value = wb.name
```

After clicking on Import Python UDFs, you can then use this macro by executing it via `Alt + F8` or by binding it e.g. to a button. To do the latter, make sure you have the Developer tab selected under `File > Options > Customize Ribbon`. Then, under the Developer tab, you can insert a button via `Insert > Form Controls`. After drawing the button, you will be prompted to assign a macro to it and you can select `my_macro`.

9.12 Call UDFs from VBA

Imported functions can also be used from VBA. For example, for a function returning a 2d array:

```
Sub MySub()

Dim arr() As Variant
Dim i As Long, j As Long

    arr = my_imported_function(...)

    For j = LBound(arr, 2) To UBound(arr, 2)
        For i = LBound(arr, 1) To UBound(arr, 1)
            Debug.Print "(" & i & "," & j & ")", arr(i, j)
        Next i
    Next j

End Sub
```

9.13 Asynchronous UDFs

Note: This is an experimental feature

New in version v0.14.0.

xlwings offers an easy way to write asynchronous functions in Excel. Asynchronous functions return immediately with #N/A `waiting...`. While the function is waiting for its return value, you can use Excel to do other stuff and whenever the return value is available, the cell value will be updated.

The only available mode is currently `async_mode='threading'`, meaning that it's useful for I/O-bound tasks, for example when you fetch data from an API over the web.

You make a function asynchronous simply by giving it the respective argument in the function decorator. In this example, the time consuming I/O-bound task is simulated by using `time.sleep`:

```
import xlwings as xw
import time

@xw.func(async_mode='threading')
def myfunction(a):
    time.sleep(5)  # long running tasks
    return a
```

You can use this function like any other xlwings function, simply by putting `=myfunction("abcd")` into a cell (after you have imported the function, of course).

Note that xlwings doesn't use the native asynchronous functions that were introduced with Excel 2010, so xlwings asynchronous functions are supported with any version of Excel.

MATPLOTLIB & PLOTLY CHARTS

10.1 Matplotlib

Using `pictures.add()`, it is easy to paste a Matplotlib plot as picture in Excel.

10.1.1 Getting started

The easiest sample boils down to:

```
import matplotlib.pyplot as plt
import xlwings as xw

fig = plt.figure()
plt.plot([1, 2, 3])

sheet = xw.Book().sheets[0]
sheet.pictures.add(fig, name='MyPlot', update=True)
```

Note: If you set `update=True`, you can resize and position the plot on Excel: subsequent calls to `pictures.add()` with the same name ('MyPlot') will update the picture without changing its position or size.


10.1.2 Full integration with Excel

Calling the above code with `RunPython` and binding it e.g. to a button is straightforward and works cross-platform.

However, on Windows you can make things feel even more integrated by setting up a `UDF` along the following lines:

```
@xw.func
def myplot(n, caller):
    fig = plt.figure()
```

(continues on next page)



(continued from previous page)

```
plt.plot(range(int(n)))
caller.sheet.pictures.add(fig, name='MyPlot', update=True)
return 'Plotted with n={}'.format(n)
```

If you import this function and call it from cell B2, then the plot gets automatically updated when cell B1 changes:

10.1.3 Properties

Size, position and other properties can either be set as arguments within `pictures.add()`, or by manipulating the picture object that is returned, see `xlwings.Picture()`.

For example:

```
>>> sht = xw.Book().sheets[0]
>>> sht.pictures.add(fig, name='MyPlot', update=True,
                     left=sht.range('B5').left, top=sht.range('B5').top)
```

or:

```
>>> plot = sht.pictures.add(fig, name='MyPlot', update=True)
>>> plot.height /= 2
>>> plot.width /= 2
```



10.1.4 Getting a Matplotlib figure

Here are a few examples of how you get a matplotlib figure object:

- via PyPlot interface:

```
import matplotlib.pyplot as plt
fig = plt.figure()
plt.plot([1, 2, 3, 4, 5])
```

or:

```
import matplotlib.pyplot as plt
plt.plot([1, 2, 3, 4, 5])
fig = plt.gcf()
```

- via object oriented interface:

```
from matplotlib.figure import Figure
fig = Figure(figsize=(8, 6))
ax = fig.add_subplot(111)
ax.plot([1, 2, 3, 4, 5])
```

- via Pandas:

```
import pandas as pd
import numpy as np

df = pd.DataFrame(np.random.rand(10, 4), columns=['a', 'b', 'c', 'd'])
ax = df.plot(kind='bar')
fig = ax.get_figure()
```

Note: When working with Google Sheets, you can use a maximum of 1 million pixels per picture. Total pixels is a function of figure size and dpi: (width in inches * dpi) * (height in inches * dpi). For example, `fig = plt.figure(figsize=(6, 4))` with 200 dpi (default dpi when using `pictures.add()`) will result in $(6 * 200) * (4 * 200) = 960,000$ px. To change the dpi, provide `export_options`: `pictures.add(fig, export_options={"bbox_inches": "tight", "dpi": 300})`. Existing figure size can be checked via `fig.get_size_inches()`. pandas also accepts `figsize` like so: `ax = df.plot(figsize=(3, 3))`. Note that `"bbox_inches": "tight"` crops the image and therefore will reduce the number of pixels in a non-deterministic way. `export_options` will be passed to `figure.savefig()` when using Matplotlib and to `figure.write_image()` when using Plotly.

10.2 Plotly static charts

10.2.1 Prerequisites

In addition to plotly, you will need kaleido, psutil, and requests. The easiest way to get it is via pip:

```
$ pip install kaleido psutil requests
```

or conda:

```
$ conda install -c conda-forge python-kaleido psutil requests
```

See also: <https://plotly.com/python/static-image-export/>


10.2.2 How to use

It works the same as with Matplotlib, however, rendering a Plotly chart takes slightly longer. Here is a sample:

```
import xlwings as xw
import plotly.express as px

# Plotly chart
df = px.data.iris()
fig = px.scatter(df, x="sepal_width", y="sepal_length", color="species")

# Add it to Excel
wb = xw.Book()
wb.sheets[0].pictures.add(fig, name='IrisScatterPlot', update=True)
```



JUPYTER NOTEBOOKS: INTERACT WITH EXCEL

When you work with Jupyter notebooks, you may use Excel as an interactive data viewer or scratchpad from where you can load DataFrames. The two convenience functions `view` and `load` make this really easy.

Note: The `view` and `load` functions should exclusively be used for interactive work. If you write scripts, use the `xlwings` API as introduced under *Quickstart* and *Syntax Overview*.

11.1 The view function

The `view` function accepts pretty much any object of interest, whether that's a number, a string, a nested list or a NumPy array or a pandas DataFrame. By default, it writes the data into an Excel table in a new workbook. If you wanted to reuse the same workbook, provide a sheet object, e.g. `view(df, sheet=xw.sheets.active)`, for further options see `view`.



The screenshot shows a Jupyter Notebook titled "Untitled" with a Python 3 kernel. The interface is split into two main panes. The left pane displays an Excel spreadsheet with the following data:

index	one	two
0	0	5
1	1	6
2	2	7
3	3	8
4	4	9

The right pane shows the Jupyter code editor with the following code:

```
In [1]: import pandas as pd
        from xlwings import view

In [2]: df = pd.DataFrame(data={'one': [0, 1, 2, 3, 4],
                                'two': [5, 6, 7, 8, 9]})
        df

Out[2]:
```

	one	two
0	0	5
1	1	6
2	2	7
3	3	8
4	4	9

```
In [3]: view(df)
```

Changed in version 0.22.0: Earlier versions were not formatting the output as Excel table

11.2 The load function

To load in a range in an Excel sheet as pandas DataFrame, use the `load` function. If you only select one cell, it will auto-expand to cover the whole range. If, however, you select a specific range that is bigger than one cell, it will load in only the selected cells. If the data in Excel does not have an index or header, set them to `False` like this: `xw.load(index=False)`, see also [load](#).

The screenshot shows a Jupyter Notebook with two input cells and one output cell. The first input cell contains the code `from xlwings import load`. The second input cell contains the code `load()`. The output cell displays a pandas DataFrame with 6 columns: Date, Open, High, Low, Close, Adj Close, and Volume. The data is formatted as an Excel table with alternating light gray and white rows. The first row is the header, and the subsequent rows contain numerical data. The output is labeled 'Out[2]:'.

```
In [1]: from xlwings import load
```

```
In [2]: load()
```

```
Out[2]:
```

Date	Open	High	Low	Close	Adj Close	Volume
2020-01-27	161.149994	163.380005	160.199997	162.279999	160.578888	32078100.0
2020-01-28	163.779999	165.759995	163.070007	165.460007	163.725555	24899900.0
2020-01-29	167.839996	168.750000	165.690002	168.039993	166.278503	34754500.0
2020-01-30	174.050003	174.050003	170.789993	172.779999	170.968826	51597500.0
2020-01-31	172.210007	172.399994	169.580002	170.229996	168.445557	36142700.0
...
2021-01-21	224.699997	226.300003	222.419998	224.970001	224.970001	30749600.0
2021-01-22	227.080002	230.070007	225.800003	225.949997	225.949997	30172700.0
2021-01-25	229.119995	229.779999	224.220001	229.529999	229.529999	33152100.0
2021-01-26	231.860001	234.179993	230.080002	232.330002	232.330002	48699200.0
2021-01-27	238.000000	240.440002	230.740005	238.979996	238.979996	28153959.0

254 rows x 6 columns

New in version 0.22.0.

COMMAND LINE CLIENT (CLI)

xlwings comes with a command line client. On Windows, type the commands into a Command Prompt or Anaconda Prompt, on Mac, type them into a Terminal. To get an overview of all commands, simply type `xlwings` and hit Enter:

<code>addin</code>	Run <code>"xlwings addin install"</code> to install the Excel add-in (will be copied to the user's XLSTART folder). Instead of <code>"install"</code> you can also use <code>"update"</code> , <code>"remove"</code> or <code>"status"</code> . Note that this command may take a while. You can install your custom add-in by providing the name or path via the <code>--file/-f</code> flag, e.g. <code>"xlwings add-in install -f custom.xlam"</code> or copy all Excel files in a directory to the XLSTART folder by providing the path via the <code>--dir</code> flag." To install the add-in for every user globally, use the <code>--glob/-g</code> flag and run this command from an Elevated Command Prompt. (New in 0.6.0, the <code>--dir</code> flag was added in 0.24.8 and the <code>--glob</code> flag in 0.28.4)
<code>quickstart</code>	Run <code>"xlwings quickstart myproject"</code> to create a folder called <code>"myproject"</code> in the current directory with an Excel file and a Python file, ready to be used. Use the <code>"--standalone"</code> flag to embed all VBA code in the Excel file and make it work without the xlwings add-in. Use <code>"--fastapi"</code> for creating a project that uses a remote Python interpreter. Use <code>"--addin --ribbon"</code> to create a template for a custom ribbon addin. Leave away the <code>"--ribbon"</code> if you don't want a ribbon tab.
<code>runpython</code>	macOS only: run <code>"xlwings runpython install"</code> if you want to enable the RunPython calls without installing the add-in. This will create the following file: ~/Library/Application Scripts/com.microsoft.Excel/xlwings.applescript (new in 0.7.0)
<code>restapi</code>	Use <code>"xlwings restapi run"</code> to run the xlwings REST API via Flask dev server. Accepts <code>"--host"</code> and <code>"--port"</code> as

(continues on next page)

(continued from previous page)

	optional arguments.
license	xlwings PRO: Use "xlwings license update -k KEY" where "KEY" is your personal (trial) license key. This will update ~/.xlwings/xlwings.conf with the LICENSE_KEY entry. If you have a paid license, you can run "xlwings license deploy" to create a deploy key. This is not available for trial keys.
config	Run "xlwings config create" to create the user config file (~/.xlwings/xlwings.conf) which is where the settings from the Ribbon add-in are stored. It will configure the Python interpreter that you are running this command with. To reset your configuration, run this with the "--force" flag which will overwrite your current configuration. (New in 0.19.5)
code	Run "xlwings code embed" to embed all Python modules of the workbook's dir in your active Excel file. Use the "--file" flag to only import a single file by providing its path. Requires xlwings PRO. (Changed in 0.23.4)
permission	"xlwings permission cwd" prints a JSON string that can be used to permission the execution of all modules in the current working directory via GET request. "xlwings permission book" does the same for code that is embedded in the active workbook. (New in 0.23.4)
release	Run "xlwings release" to configure your active workbook to work with a one-click installer for easy deployment. Requires xlwings PRO. (New in 0.23.4)
copy	Run "xlwings copy os" to copy the xlwings Office Scripts module. Run "xlwings copy gs" to copy the xlwings Google Apps Script module. (New in 0.26.0)
vba	This functionality allows you to easily write VBA code in an external editor: run "xlwings vba edit" to update the VBA modules of the active workbook from their local exports everytime you hit save. If you run this the first time, the modules will be exported from Excel into your current working directory. To overwrite the local version of the modules with those from Excel, run "xlwings vba export". To overwrite the VBA modules in Excel with their local versions, run "xlwings vba import". The "--file/-f" flag allows you to specify a file path instead of using the active Workbook. Requires "Trust access to the VBA project

(continues on next page)

(continued from previous page)

object model" enabled. NOTE: Whenever you change something in the VBA editor (such as the layout of a form or the properties of a module), you have to run "xlwings vba export".

(New in 0.26.3, changed in 0.27.0)

DEPLOYMENT

13.1 Zip files

New in version 0.15.2.

To make it easier to distribute, you can zip up your Python code into a zip file. If you use UDFs, this will disable the automatic code reload, so this is a feature meant for distribution, not development. In practice, this means that when your code is inside a zip file, you'll have to click on re-import to get any changes.

If you name your zip file like your Excel file (but with .zip extension) and place it in the same folder as your Excel workbook, xlwings will automatically find it (similar to how it works with a single python file).

If you want to use a different directory, make sure to add it to the PYTHONPATH in your config (Ribbon or config file):

```
PYTHONPATH, "C:\path\to\myproject.zip"
```

13.2 RunFrozenPython

Changed in version 0.15.2.

You can use a freezer like PyInstaller, cx_Freeze, py2exe etc. to freeze your Python module into an executable so that the recipient doesn't have to install a full Python distribution.

Note:

- This does not work with UDFs.
 - Currently only available on Windows, but support for Mac should be easy to add.
 - You need at least 0.15.2 to support arguments whereas the syntax changed in 0.15.6
-

Use it as follows:

```
Sub MySample()  
    RunFrozenPython "C:\path\to\dist\myproject\myproject.exe", "arg1 arg2"  
End Sub
```


ONEDRIVE AND SHAREPOINT

Since v0.27.4, xlwings works with locally synced files on OneDrive, OneDrive for Business, and SharePoint. Some constellations will work out-of-the-box, while others require you to edit the configuration via the `xlwings.conf` file (see [User Config](#)) or the workbook's `xlwings.conf` sheet (see [Workbook Config](#)).

Note: This documentation is for OneDrive and SharePoint files that are synced to a local folder. This means that both, the Excel and Python file, need to show the green check mark in the File Explorer/Finder as status—a cloud icon will not work. If, in turn, you are looking for the documentation to run xlwings with Excel on the web, see [xlwings Server PRO](#).

An easy workaround if you run into issues is to:

- Disable the `ADD_WORKBOOK_TO_PYTHONPATH` setting (either via the checkbox on the Ribbon or via the settings in the `xlwings.conf` sheet).
- Add the directory of your Python source file to the `PYTHONPATH`—again, either via Ribbon or `xlwings.conf` sheet.

If you are using the PRO version, you could instead also embed your code to get around these issues.

For a bit more flexibility, follow the solutions below.

14.1 OneDrive (Personal)

Default setups work out-of-the-box on Windows and macOS. If you get an error message, add the following setting with the correct path to the local root directory of your OneDrive. If possible, make use of environment variables (as shown in the examples) so the configuration will work across different users with the same setup:

- **Windows** (Example):

ONEDRIVE_CONSUMER_WIN	%USERPROFILE%\OneDrive
-----------------------	------------------------

- **macOS** (Example):

ONEDRIVE_CONSUMER_MAC	\$HOME/OneDrive
-----------------------	-----------------

14.2 OneDrive for Business

- **Windows:** Default setups work out-of-the-box. If you get an error message, add the following setting with the correct path to the local root directory of your OneDrive for Business. If possible, make use of environment variables (as shown in the examples) so the configuration will work across different users with the same setup:

ONEDRIVE_COMMERCIAL_WIN	%USERPROFILE%\OneDrive - My Company LLC
-------------------------	---

- **macOS:** macOS *always* requires the following setting with the correct path to the local root directory of your OneDrive for Business. If possible, make use of environment variables (as shown in the examples) so the configuration will work across different users with the same setup:

ONEDRIVE_COMMERCIAL_MAC	\$HOME/OneDrive - My Company LLC
-------------------------	----------------------------------

14.3 SharePoint (Online and On-Premises)

On Windows, the location of the local root folder of SharePoint can *sometimes* be derived from the OneDrive environment variables. Most of the time though, you'll have to provide the following setting (on macOS this is a must):

- **Windows:**

SHAREPOINT_WIN	%USERPROFILE%\My Company LLC
----------------	------------------------------

- **macOS:**

SHAREPOINT_MAC	\$HOME/My Company LLC
----------------	-----------------------

14.4 Implementation Details & Limitations

A lot of the xlwings functionality depends on the workbook's `FullName` property (via VBA/COM) that returns the local path of the file unless it is saved on OneDrive, OneDrive for Business or SharePoint **with AutoSave enabled**. In this case, it returns a URL instead.

URLs for OneDrive and OneDrive for Business can be translated fairly straight forward to the local equivalent. You will need to know the root directory of the local drive though: on Windows, these are usually provided via environment variables for OneDrive. On macOS they don't exist, which is the reason why you need to provide the root directory for OneDrive. On Windows, the root directory for SharePoint can sometimes be derived from the env vars, too, but this is not guaranteed. On macOS, you'll need to provide it always anyway.

SharePoint, unfortunately, allows you to map the drives locally in any way you want and there's no way to reliably get the local path for these files. On Windows, xlwings first checks the registry for the mapping. If this doesn't work, xlwings checks if the local path is mapped by using the defaults and if the file can't be found, it checks all existing local files on SharePoint. If it finds one with the same name, it'll use this. If, however, it finds more than one with the same name, you will get an error message. In this case, you can either rename the file to something unique across all the locally synced SharePoint files or you can change the `SHAREPOINT_WIN/MAC` setting to not stop at the root folder but include additional folders. As an example, assume you have the following file structure on your local SharePoint:

```
My Company LLC/
├─ sitename1/
│   └─ myfile.xlsx
├─ sitename2 - Documents/
│   └─ myfile.xlsx
```

In this case, you could either rename one of the files, or you could add a path that goes beyond the root folder (preferably under the `xlwings.conf` sheet):

SHAREPOINT_WIN	%USERPROFILE%/My Company LLC/sitename2 - Documents
----------------	--

TROUBLESHOOTING

15.1 Issue: dll not found

Solution:

- 1) `xlwings32-<version>.dll` and `xlwings64-<version>.dll` are both in the same directory as your `python.exe`. If not, something went wrong with your installation. Reinstall it with `pip` or `conda`, see *Installation*.
- 2) Check your Interpreter in the add-in or config sheet. If it is empty, then you need to be able to open a windows command prompt and type `python` to start an interactive Python session. If you get the error '`python`' is not recognized as an internal or external command, operable program or batch file., then you have two options: Either add the path of where your `python.exe` lives to your Windows path (see <https://www.computerhope.com/issues/ch000549.htm>) or set the full path to your interpreter in the add-in or your config sheet, e.g. `C:\Users\MyUser\anaconda\pythonw.exe`

15.2 Issue: Files that are saved on OneDrive or SharePoint cause an error to pop up

Solution:

See the dedicated page about how to configure OneDrive and Sharepoint: *OneDrive and SharePoint*.

CONVERTERS AND OPTIONS

Introduced with v0.7.0, converters define how Excel ranges and their values are converted both during **reading** and **writing** operations. They also provide a consistent experience across **xlwings.Range** objects and **User Defined Functions** (UDFs).

Converters are explicitly set in the `options` method when manipulating `Range` objects or in the `@xw.arg` and `@xw.ret` decorators when using UDFs. If no converter is specified, the default converter is applied when reading. When writing, xlwings will automatically apply the correct converter (if available) according to the object's type that is being written to Excel. If no converter is found for that type, it falls back to the default converter.

All code samples below depend on the following import:

```
>>> import xlwings as xw
```

Syntax:

	Range objects	UDFs
read- ing	<code>myrange.options(convert=None, **kwargs).value</code>	<code>@arg('x', convert=None, **kwargs)</code>
writ- ing	<code>myrange.options(convert=None, **kwargs).value = myvalue</code>	<code>@ret(convert=None, **kwargs)</code>

Note: Keyword arguments (`kwargs`) may refer to the specific converter or the default converter. For example, to set the `numbers` option in the default converter and the `index` option in the `DataFrame` converter, you would write:

```
myrange.options(pd.DataFrame, index=False, numbers=int).value
```

16.1 Default Converter

If no options are set, the following conversions are performed:

- single cells are read in as floats in case the Excel cell holds a number, as unicode in case it holds text, as datetime if it contains a date and as None in case it is empty.
- columns/rows are read in as lists, e.g. [None, 1.0, 'a string']
- 2d cell ranges are read in as list of lists, e.g. [[None, 1.0, 'a string'], [None, 2.0, 'another string']]

The following options can be set:

- **ndim**

Force the value to have either 1 or 2 dimensions regardless of the shape of the range:

```
>>> import xlwings as xw
>>> sheet = xw.Book().sheets[0]
>>> sheet['A1'].value = [[1, 2], [3, 4]]
>>> sheet['A1'].value
1.0
>>> sheet['A1'].options(ndim=1).value
[1.0]
>>> sheet['A1'].options(ndim=2).value
[[1.0]]
>>> sheet['A1:A2'].value
[1.0 3.0]
>>> sheet['A1:A2'].options(ndim=2).value
[[1.0], [3.0]]
```

- **numbers**

By default cells with numbers are read as float, but you can change it to int:

```
>>> sheet['A1'].value = 1
>>> sheet['A1'].value
1.0
>>> sheet['A1'].options(numbers=int).value
1
```

Alternatively, you can specify any other function or type which takes a single float argument.

Using this on UDFs looks like this:

```
@xw.func
@xw.arg('x', numbers=int)
def myfunction(x):
    # all numbers in x arrive as int
    return x
```

Note: Excel always stores numbers internally as floats, which is the reason why the *int* converter rounds numbers first before turning them into integers. Otherwise it could happen that e.g. 5 might be returned as 4 in case it is represented as a floating point number that is slightly smaller than 5. Should you require Python's original *int* in your converter, use *raw int* instead.

- **dates**

By default cells with dates are read as `datetime.datetime`, but you can change it to `datetime.date`:

- Range:

```
>>> import datetime as dt
>>> sheet['A1'].options(dates=dt.date).value
```

- UDFs: `@xw.arg('x', dates=dt.date)`

Alternatively, you can specify any other function or type which takes the same keyword arguments as `datetime.datetime`, for example:

```
>>> my_date_handler = lambda year, month, day, **kwargs: "%04i-%02i-%02i" % (
    year, month, day)
>>> sheet['A1'].options(dates=my_date_handler).value
'2017-02-20'
```

- **empty**

Empty cells are converted per default into `None`, you can change this as follows:

- Range: `>>> sheet['A1'].options(empty='NA').value`
- UDFs: `@xw.arg('x', empty='NA')`

- **transpose**

This works for reading and writing and allows us to e.g. write a list in column orientation to Excel:

- Range: `sheet['A1'].options(transpose=True).value = [1, 2, 3]`
- UDFs:

```
@xw.arg('x', transpose=True)
@xw.ret(transpose=True)
def myfunction(x):
    # x will be returned unchanged as transposed both when reading and
    # writing
    return x
```

- **expand**

This works the same as the Range properties table, vertical and horizontal but is only evaluated when getting the values of a Range:

```
>>> import xlwings as xw
>>> sheet = xw.Book().sheets[0]
>>> sheet['A1'].value = [[1,2], [3,4]]
>>> range1 = sheet['A1'].expand()
>>> range2 = sheet['A1'].options(expand='table')
>>> range1.value
[[1.0, 2.0], [3.0, 4.0]]
>>> range2.value
[[1.0, 2.0], [3.0, 4.0]]
>>> sheet['A3'].value = [5, 6]
>>> range1.value
[[1.0, 2.0], [3.0, 4.0]]
>>> range2.value
[[1.0, 2.0], [3.0, 4.0], [5.0, 6.0]]
```

Note: The `expand` method is only available on Range objects as UDFs only allow to manipulate the calling cells.

- **chunksize**

When you read and write from or to big ranges, you may have to chunk them or you will hit a timeout or a memory error. The ideal `chunksize` will depend on your system and size of the array, so you will have to try out a few different chunksizes to find one that works well:

```
import pandas as pd
import numpy as np
sheet = xw.Book().sheets[0]
data = np.arange(75_000 * 20).reshape(75_000, 20)
df = pd.DataFrame(data=data)
sheet['A1'].options(chunksize=10_000).value = df
```

And the same for reading:

```
# As DataFrame
df = sheet['A1'].expand().options(pd.DataFrame, chunksize=10_000).value
# As list of list
df = sheet['A1'].expand().options(chunksize=10_000).value
```

- **err_to_str** (new in v0.28.0)

If `True`, will include cell errors such as `#N/A` as strings. By default, they will be converted to `None`.

- **formatter** (new in v0.28.1)

The `formatter` option accepts the name of a function. The function will be called after writing the values to Excel and allows you to easily style the range in a very flexible way. How it works is best shown with a little example:


```

import pandas as pd
import xlwings as xw

sheet = xw.Book().sheets[0]

def table(rng: xw.Range, df: pd.DataFrame):
    """This is the formatter function"""
    # Header
    rng[0, :].color = "#A9D08E"

    # Rows
    for ix, row in enumerate(rng.rows[1:]):
        if ix % 2 == 0:
            row.color = "#D0CECE" # Even rows

    # Columns
    for ix, col in enumerate(df.columns):
        if "two" in col:
            rng[1:, ix].number_format = "0.0%"

df = pd.DataFrame(data={"one": [1, 2, 3, 4], "two": [5, 6, 7, 8]})
sheet["A1"].options(formatter=table, index=False).value = df

```

Running this code will format the DataFrame like this:

	A	B
1	one	two
2	1	500.0%
3	2	600.0%
4	3	700.0%
5	4	800.0%

The formatter's signature is: `def myformatter(myrange, myvalues)` where `myrange` corresponds to the range where `myvalues` are written to. `myvalues` is simply what you assign to the `value` property in the last line of the example. Since we're using this with a `DataFrame`, it makes sense to name the argument accordingly and using type hints will help your editor with auto-completion. If you would use a nested list instead of a `DataFrame`, you would write something like this instead:

```

def table(rng: xw.Range, values: list[list]): # Python >= 3.9

```

For Python <= 3.8, you'll need to capitalize `List` and import it like so: `from typing import List`.

16.2 Built-in Converters

xlwings offers several built-in converters that perform type conversion to **dictionaries**, **NumPy arrays**, **Pandas Series** and **DataFrames**. These build on top of the default converter, so in most cases the options described above can be used in this context, too (unless they are meaningless, for example the `ndim` in the case of a dictionary).

It is also possible to write and register a custom converter for additional types, see below.

The samples below can be used with both `xlwings.Range` objects and UDFs even though only one version may be shown.

16.2.1 Dictionary converter

The dictionary converter turns two Excel columns into a dictionary. If the data is in row orientation, use `transpose`:

	A	B
1	a	1
2	b	2
3		
4	a	b
5	1	2

```
>>> sheet = xw.sheets.active
>>> sheet['A1:B2'].options(dict).value
{'a': 1.0, 'b': 2.0}
>>> sheet['A4:B5'].options(dict, transpose=True).value
{'a': 1.0, 'b': 2.0}
```

Note: instead of `dict`, you can also use `OrderedDict` from `collections`.

16.2.2 Numpy array converter

options: `dtype=None`, `copy=True`, `order=None`, `ndim=None`

The first 3 options behave the same as when using `np.array()` directly. Also, `ndim` works the same as shown above for lists (under default converter) and hence returns either numpy scalars, 1d arrays or 2d arrays.

Example:

```
>>> import numpy as np
>>> sheet = xw.Book().sheets[0]
>>> sheet['A1'].options(transpose=True).value = np.array([1, 2, 3])
>>> sheet['A1:A3'].options(np.array, ndim=2).value
array([[ 1.],
       [ 2.],
       [ 3.]])
```

16.2.3 Pandas Series converter

options: dtype=None, copy=False, index=1, header=True

The first 2 options behave the same as when using `pd.Series()` directly. `ndim` doesn't have an effect on Pandas series as they are always expected and returned in column orientation.

index: int or Boolean

When reading, it expects the number of index columns shown in Excel.

When writing, include or exclude the index by setting it to `True` or `False`.

header: Boolean

When reading, set it to `False` if Excel doesn't show either index or series names.

When writing, include or exclude the index and series names by setting it to `True` or `False`.

For `index` and `header`, `1` and `True` may be used interchangeably.

Example:

	A	B	C	D	E
1	date	series name		01/01/01	1
2	01/01/01	1		02/01/01	2
3	02/01/01	2		03/01/01	3
4	03/01/01	3		04/01/01	4
5	04/01/01	4		05/01/01	5
6	05/01/01	5		06/01/01	6
7	06/01/01	6			

```
>>> sheet = xw.Book().sheets[0]
>>> s = sheet['A1'].options(pd.Series, expand='table').value
>>> s
date
2001-01-01    1
2001-01-02    2
2001-01-03    3
2001-01-04    4
2001-01-05    5
2001-01-06    6
Name: series name, dtype: float64
```

16.2.4 Pandas DataFrame converter

options: dtype=None, copy=False, index=1, header=1

The first 2 options behave the same as when using `pd.DataFrame()` directly. `ndim` doesn't have an effect on Pandas DataFrames as they are automatically read in with `ndim=2`.

index: int or Boolean

When reading, it expects the number of index columns shown in Excel.

When writing, include or exclude the index by setting it to `True` or `False`.

header: int or Boolean

When reading, it expects the number of column headers shown in Excel.

When writing, include or exclude the index and series names by setting it to `True` or `False`.

For `index` and `header`, 1 and `True` may be used interchangeably.

Example:

B13		fx {=myfunction(A1:D5)}			
	A	B	C	D	
1		a	a	b	
2	ix	c	d	e	
3	10	1	2	3	
4	20	4	5	6	
5	30	7	8	9	
6					
7		a	a	b	
8		c	d	e	
9		1	2	3	
10		4	5	6	
11		7	8	9	
12					
13		a	a	b	
14		c	d	e	
15		1	2	3	
16		4	5	6	
17		7	8	9	
18					

```
>>> sheet = xw.Book().sheets[0]
>>> df = sheet['A1:D5'].options(pd.DataFrame, header=2).value
>>> df
```

(continues on next page)

(continued from previous page)

```

    a    b
    c  d  e
ix
10  1  2  3
20  4  5  6
30  7  8  9

# Writing back using the defaults:
>>> sheet['A1'].value = df

# Writing back and changing some of the options, e.g. getting rid of the index:
>>> sheet['B7'].options(index=False).value = df

```

The same sample for **UDF** (starting in cell A13 on screenshot) looks like this:

```

@xw.func
@xw.arg('x', pd.DataFrame, header=2)
@xw.ret(index=False)
def myfunction(x):
    # x is a DataFrame, do something with it
    return x

```

16.2.5 xw.Range and ‘raw’ converters

Technically speaking, these are “no-converters”.

- If you need access to the `xlwings.Range` object directly, you can do:

```

@xw.func
@xw.arg('x', 'range')
def myfunction(x):
    return x.formula

```

This returns `x` as `xlwings.Range` object, i.e. without applying any converters or options.

- The raw converter delivers the values unchanged from the underlying libraries (pywin32 on Windows and appscript on Mac), i.e. no sanitizing/cross-platform harmonizing of values are being made. This might be useful in a few cases for efficiency reasons. E.g:

```

>>> sheet['A1:B2'].value
[[1.0, 'text'], [datetime.datetime(2016, 2, 1, 0, 0), None]]

>>> sheet['A1:B2'].options('raw').value # or sheet['A1:B2'].raw_value
((1.0, 'text'), (pywintypes.datetime(2016, 2, 1, 0, 0, tzinfo=TimeZoneInfo(
↳ 'GMT Standard Time', True))), None))

```

16.3 Custom Converter

Here are the steps to implement your own converter:

- Inherit from `xlwings.conversion.Converter`
- Implement both a `read_value` and `write_value` method as static- or classmethod:
 - In `read_value`, `value` is what the base converter returns: hence, if no base has been specified it arrives in the format of the default converter.
 - In `write_value`, `value` is the original object being written to Excel. It must be returned in the format that the base converter expects. Again, if no base has been specified, this is the default converter.

The options dictionary will contain all keyword arguments specified in the options method, e.g. when calling `myrange.options(myoption='some value')` or as specified in the `@arg` and `@ret` decorator when using UDFs. Here is the basic structure:

```
from xlwings.conversion import Converter

class MyConverter(Converter):

    @staticmethod
    def read_value(value, options):
        myoption = options.get('myoption', default_value)
        return_value = value # Implement your conversion here
        return return_value

    @staticmethod
    def write_value(value, options):
        myoption = options.get('myoption', default_value)
        return_value = value # Implement your conversion here
        return return_value
```

- Optional: set a base converter (base expects a class name) to build on top of an existing converter, e.g. for the built-in ones: `DictConverter`, `NumpyArrayConverter`, `PandasDataFrameConverter`, `PandasSeriesConverter`
- Optional: register the converter: you can **(a)** register a type so that your converter becomes the default for this type during write operations and/or **(b)** you can register an alias that will allow you to explicitly call your converter by name instead of just by class name

The following examples should make it much easier to follow - it defines a `DataFrame` converter that extends the built-in `DataFrame` converter to add support for dropping nan's:

```
from xlwings.conversion import Converter, PandasDataFrameConverter

class DataFrameDropna(Converter):
```

(continues on next page)

(continued from previous page)

```

base = PandasDataFrameConverter

@staticmethod
def read_value(builtin_df, options):
    dropna = options.get('dropna', False) # set default to False
    if dropna:
        converted_df = builtin_df.dropna()
    else:
        converted_df = builtin_df
    # This will arrive in Python when using the DataFrameDropna converter.
    ↪for reading
    return converted_df

@staticmethod
def write_value(df, options):
    dropna = options.get('dropna', False)
    if dropna:
        converted_df = df.dropna()
    else:
        converted_df = df
    # This will be passed to the built-in PandasDataFrameConverter when.
    ↪writing
    return converted_df

```

Now let's see how the different converters can be applied:

```

# Fire up a Workbook and create a sample DataFrame
sheet = xw.Book().sheets[0]
df = pd.DataFrame([[1., 10.], [2., np.nan], [3., 30.]])

```

- Default converter for DataFrames:

```

# Write
sheet['A1'].value = df

# Read
sheet['A1:C4'].options(pd.DataFrame).value

```

- DataFrameDropna converter:

```

# Write
sheet['A7'].options(DataFrameDropna, dropna=True).value = df

# Read
sheet['A1:C4'].options(DataFrameDropna, dropna=True).value

```

- Register an alias (optional):

```
DataFrameDropna.register('df_dropna')

# Write
sheet['A12'].options('df_dropna', dropna=True).value = df

# Read
sheet['A1:C4'].options('df_dropna', dropna=True).value
```

- Register DataFrameDropna as default converter for DataFrames (optional):

```
DataFrameDropna.register(pd.DataFrame)

# Write
sheet['A13'].options(dropna=True).value = df

# Read
sheet['A1:C4'].options(pd.DataFrame, dropna=True).value
```

These samples all work the same with UDFs, e.g.:

```
@xw.func
@arg('x', DataFrameDropna, dropna=True)
@ret(DataFrameDropna, dropna=True)
def myfunction(x):
    # ...
    return x
```

Note: Python objects run through multiple stages of a transformation pipeline when they are being written to Excel. The same holds true in the other direction, when Excel/COM objects are being read into Python.

Pipelines are internally defined by `Accessor` classes. A `Converter` is just a special `Accessor` which converts to/from a particular type by adding an extra stage to the pipeline of the default `Accessor`. For example, the `PandasDataFrameConverter` defines how a list of lists (as delivered by the default `Accessor`) should be turned into a Pandas `DataFrame`.


The `Converter` class provides basic scaffolding to make the task of writing a new `Converter` easier. If you need more control you can subclass `Accessor` directly, but this part requires more work and is currently undocumented.

DEBUGGING

Since xlwings runs in every Python environment, you can use your preferred way of debugging.

- **RunPython:** When calling Python through RunPython, you can set a `mock_caller` to make it easy to switch back and forth between calling the function from Excel and Python.
- **UDFs:** For debugging User Defined Functions, xlwings offers a convenient debugging server

To begin with, Excel will show Python errors in a Message Box:



Note: On Mac, if the `import` of a module/package fails before `xlwings` is imported, the popup will not be shown and the StatusBar will not be reset. However, the error will still be logged in the log file (`/Users/<User>/Library/Containers/com.microsoft.Excel/Data/xlwings.log`).

17.1 RunPython

Consider the following sample code of your Python source code `my_module.py`:

```
# my_module.py
import os
import xlwings as xw

def my_macro():
    wb = xw.Book.caller()
    wb.sheets[0]['A1'].value = 1

if __name__ == '__main__':
    # Expects the Excel file next to this source file, adjust accordingly.
    xw.Book('myfile.xlsm').set_mock_caller()
    my_macro()
```

`my_macro()` can now easily be run from Python for debugging and from Excel via `RunPython` without having to change the source code:

```
Sub my_macro()
    RunPython "import my_module; my_module.my_macro()"
End Sub
```

17.2 UDF debug server


Windows only: To debug UDFs, just check the `Debug UDFs` in the *Add-in & Settings*, at the top of the xlwings VBA module. Then add the following lines at the end of your Python source file and run it. Depending on which IDE you use, you might need to run the code in “debug” mode (e.g. in case you’re using PyCharm or PyDev):

```
if __name__ == '__main__':
    xw.serve()
```

When you recalculate the Sheet (Ctrl-Alt-F9), the code will stop at breakpoints or output any print calls that you may have.

The following screenshot shows the code stopped at a breakpoint in the community version of PyCharm:

Note: When running the debug server from a command prompt, there is currently no gracious way to terminate it, but closing the command prompt will kill it.



EXTENSIONS

It's easy to extend the xlwings add-in with own code like UDFs or RunPython macros, so that they can be deployed without end users having to import or write the functions themselves. Just add another VBA module to the xlwings addin with the respective code.

UDF extensions can be used from every workbook without having to set a reference.

18.1 In-Excel SQL

The xlwings addin comes with a built-in extension that adds in-Excel SQL syntax (sqlite dialect):

```
=sql(SQL Statement, table a, table b, ...)
```

As this extension uses UDFs, it's only available on Windows right now.

A16		✕ ✓ <i>fx</i>		=sql(A14,A1:D11,G1:H8)				
	A	B	C	D	E	F	G	H
1	id	first_name	last_name	age			id	email
2	1	Mariam	Alt	12			1	Mariam@Alt
3	2	Shenita	Truelove	55			2	Shenita@Truelove
4	3	Evelyn	Braddy	30			3	Evelyn@Braddy
5	4	Shery	Sam	35			5	Rogello@Mote
6	5	Rogello	Mote	88			6	Solomon@Okamura
7	6	Solomon	Okamura	33			8	Latashia@Alire
8	7	Jessica	Buelow	10			9	Roselee@Tarwater
9	8	Latashia	Alire	19				
10	9	Roselee	Tarwater	28				
11	10	Kiera	Saulsbury	55				
12								
13								
14	SELECT a.id, a.first_name, a.last_name, b.email FROM a INNER JOIN b ON a.id = b.id							
15								
16	id	first_name	last_name	email				
17	1	Mariam	Alt	Mariam@Alt				
18	2	Shenita	Truelove	Shenita@Truelove				
19	3	Evelyn	Braddy	Evelyn@Braddy				
20	5	Rogello	Mote	Rogello@Mote				
21	6	Solomon	Okamura	Solomon@Okamura				
22	8	Latashia	Alire	Latashia@Alire				
23	9	Roselee	Tarwater	Roselee@Tarwater				

CUSTOM ADD-INS

New in version 0.22.0.

Custom add-ins work on Windows and macOS and are white-labeled xlwings add-ins that include all your `RunPython` functions and UDFs (as usual, UDFs work on Windows only). You can build add-ins with and without an Excel ribbon.

The useful thing about add-in is that UDFs and `RunPython` calls will be available in all workbooks right out of the box without having to add any references via the VBA editor's `Tools > References...` You can also work with standard `xlsx` files rather than `xlsm` files. This tutorial assumes you're familiar with how xlwings and its configuration works.

19.1 Quickstart

Start by running the following command on a command line (to create an add-in without a ribbon, you would leave away the `--ribbon` flag):

```
$ xlwings quickstart myproject --addin --ribbon
```

This will create the familiar quickstart folder with a Python file and an Excel file, but this time, the Excel file is in the `xlam` format.

- Double-click the Excel add-in to open it in Excel
- Add a new empty workbook (Ctrl+N on Windows or Command+N on macOS)



You should see a new ribbon tab called `MyAddin` like this:

The add-in and VBA project are currently always called `myaddin`, no matter what name you chose in the quickstart command. We'll see towards the end of this tutorial how we can change that, but for now we'll stick to it.

Compared to the xlwings add-in, the custom add-in offers an additional level of configuration: the configuration sheet of the add-in itself which is the easiest way to configure simple add-ins with a static configuration.

Let's open the VBA editor by clicking on Alt+F11 (Windows) or Option+F11 (macOS). In our project, select `ThisWorkbook`, then change the Property `IsAddin` from `True` to `False`, see the following screenshot:

This will make the sheet `_myaddin.conf` visible (again, we'll see how to change the name of `myaddin` at the end of this tutorial):



- Activate the sheet config by renaming it from `_myaddin.conf` to `myaddin.conf`
- Set your `Interpreter_Win/_Mac` or `Conda` settings (you may want to take them over from the `xlwings` settings for now)

Once done, switch back to the VBA editor, select `ThisWorkbook` again, and change `IsAddin` back to `True` before you save your add-in from the VBA editor. Switch back to Excel and click the `Run` button under the `My Addin` ribbon tab and if you've configured the Python interpreter correctly, it will print `Hello xlwings!` into cell `A1` of the active workbook.

19.2 Changing the Ribbon menu

To change the buttons and items in the ribbon menu or the Backstage View, download and install the [Office RibbonX Editor](#). While it is only available for Windows, the created ribbons will also work on macOS. Open your add-in with it so you can change the XML code that defines your buttons etc. You will find a good tutorial [here](#). The callback function for the demo `Run` button is in the `RibbonMyAddin` VBA module that you'll find in the VBA editor.

19.3 Importing UDFs

To import your UDFs into the custom add-in, run the `ImportPythonUDFstoAddin` Sub towards the end of the `xlwings` module (click into the Sub and hit `F5`). Remember, you only have to do this whenever you change the function name, argument or decorator, so your end users won't have to deal with this.

If you are only deploying UDFs via your add-in, you probably don't need a Ribbon menu and can leave away the `--ribbon` flag in the `quickstart` command.

19.4 Configuration

As mentioned before, configuration works the same as with `xlwings`, so you could have your users override the default configuration we did above by adding a `myaddin.conf` sheet on their workbook or you could use the `myaddin.conf` file in the user's home directory. For details see [Add-in & Settings](#).

19.5 Installation

If you want to permanently install your add-in, you can do so by using the `xlwings` CLI:

```
$ xlwings addin install --file C:\path\to\your\myproject.xlam
```

This, however, means that you will need to adjust the `PYTHONPATH` for it to find your Python code (or move your Python code to somewhere where Python looks for it—more about that below under deployment). The command will copy your add-in to the `XLSTART` folder, a special folder from where Excel will open all files everytime you start it.

19.6 Renaming your add-in

Admittedly, this part is a bit cumbersome for now. Let's assume, we would like to rename the addin from `MyAddin` to `Demo`:

- In the xlwings VBA module, change `Public Const PROJECT_NAME As String = "myaddin"` to `Public Const PROJECT_NAME As String = "demo"`. You'll find this line at the top, right after the `Declare` statements.
- If you rely on the `myaddin.conf` sheet for your configuration, rename it to `demo.conf`
- Right-click the VBA project, select `MyAddin Properties...` and rename the `Project Name` from `MyAddin` to `Demo`.
- If you use the ribbon, you want to rename the `RibbonMyAddin` VBA module to `RibbonDemo`. To do this, select the module in the VBA editor, then rename it in the `Properties` window. If you don't see the `Properties` window, hit `F4`.
- Open the add-in in the Office RibbonX Editor (see above) and replace all occurrences of `MyAddin` with `Demo` in the XML code.

And finally, you may want to rename your `myproject.xlam` file in the Windows explorer, but I assume you have already run the `quickstart` command with the correct name, so this won't be necessary.

19.7 Deployment

By far the easiest way to deploy your add-in to your end-users is to build an installer via the xlwings `PRO` offering. This will take care of everything and your end users literally just need to double-click the installer and they are all set (no existing Python installation required and no manual installation of the add-in or adjusting of settings required).

If you want it the free (but hard) way, you either need to build an installer yourself or you need your users to install Python and the add-in and take care of placing the Python code in the correct directory. This normally involves tweaking the following settings, for example in the `myaddin.conf` sheet:

- `Interpreter_Win/_Mac`: if your end-users have a working version of Python, you can use environment variables to dynamically resolve to the correct path. For example, if they have Anaconda installed in the default location, you could use the following configuration:

<pre>Conda Path: %USERPROFILE%\anaconda3 Conda Env: base Interpreter_Mac: \$HOME/opt/anaconda3/bin/python</pre>

- `PYTHONPATH`: since you can't have your Python source code in the `XLSTART` folder next to the add-in, you'll need to adjust the `PYTHONPATH` setting and add the folder to where the Python code will be. You could point this to a shared drive or again make use of environment variables so the users can place the file into a folder called `MyAddin` in their home directory, for example. However, you can also place your Python code where Python looks for it, for example by placing them in the `site-packages` directory of the Python distribution—an easy way to achieve this is to build a Python package that you can install via `pip`.

THREADING AND MULTIPROCESSING

New in version 0.13.0.

20.1 Threading

While xlwings is not technically thread safe, it's still easy to use it in threads as long as you have at least v0.13.0 and stick to a simple rule: Do not pass xlwings objects to threads. This rule isn't a requirement on macOS, but it's still recommended if you want your programs to be cross-platform.

Consider the following example that will **NOT** work:

```
import threading
from queue import Queue
import xlwings as xw

num_threads = 4

def write_to_workbook():
    while True:
        myrange = q.get()
        myrange.value = myrange.address
        print(myrange.address)
        q.task_done()

q = Queue()

for i in range(num_threads):
    t = threading.Thread(target=write_to_workbook)
    t.daemon = True
    t.start()

for cell in ['A1', 'A2', 'A3', 'A4', 'A5', 'A6', 'A7', 'A8', 'A9', 'A10']:
    # THIS DOESN'T WORK - passing xlwings objects to threads will fail!
```

(continues on next page)

(continued from previous page)

```
myrange = xw.Book('Book1.xlsx').sheets[0].range(cell)
q.put(myrange)

q.join()
```

To make it work, you simply have to fully qualify the cell reference in the thread instead of passing a Book object:

```
import threading
from queue import Queue
import xlwings as xw

num_threads = 4

def write_to_workbook():
    while True:
        cell_ = q.get()
        xw.Book('Book1.xlsx').sheets[0].range(cell_).value = cell_
        print(cell_)
        q.task_done()

q = Queue()

for i in range(num_threads):
    t = threading.Thread(target=write_to_workbook)
    t.daemon = True
    t.start()

for cell in ['A1', 'A2', 'A3', 'A4', 'A5', 'A6', 'A7', 'A8', 'A9', 'A10']:
    q.put(cell)

q.join()
```

20.2 Multiprocessing

Note: Multiprocessing is only supported on Windows!

The same rules apply to multiprocessing as for threading, here's a working example:

```
from multiprocessing import Pool
import xlwings as xw
```

(continues on next page)

(continued from previous page)

```
def write_to_workbook(cell):
    xw.Book('Book1.xlsx').sheets[0].range(cell).value = cell
    print(cell)

if __name__ == '__main__':
    with Pool(4) as p:
        p.map(write_to_workbook,
              ['A1', 'A2', 'A3', 'A4', 'A5', 'A6', 'A7', 'A8', 'A9', 'A10'])
```


MISSING FEATURES

If you're missing a feature in xlwings, do the following:

- 1) Most importantly, open an issue on [GitHub](#). Adding functionality should be user driven, so only if you tell us about what you're missing, it's eventually going to find its way into the library. By the way, we also appreciate pull requests!
- 2) Workaround: in essence, xlwings is just a smart wrapper around [pywin32](#) on Windows and [appscript](#) on Mac. You can access the underlying objects by calling the `api` property:

```
>>> sheet = xw.Book().sheets[0]
>>> sheet.api
# Windows (pywin32)
<win32com.gen_py.Microsoft Excel 16.0 Object Library._Worksheet instance at 0x2260624985352>
# macOS (appscript)
app(pid=2319).workbooks['Workbook1'].worksheets[1]
```

This works accordingly for the other objects like `sheet.range('A1').api` etc.

The underlying objects will offer you pretty much everything you can do with VBA, using the syntax of `pywin32` (which pretty much feels like VBA) and `appscript` (which doesn't feel like VBA). But apart from looking ugly, keep in mind that **it makes your code platform specific (!)**, i.e. even if you go for option 2), you should still follow option 1) and open an issue so the feature finds its way into the library (cross-platform and with a Pythonic syntax).

21.1 Example: Workaround to use VBA's `Range.WrapText`

```
# Windows
sheet['A1'].api.WrapText = True

# Mac
sheet['A1'].api.wrap_text.set(True)
```


XLWINGS WITH OTHER OFFICE APPS

xlwings can also be used to call Python functions from VBA within Office apps other than Excel (like Outlook, Access etc.).

Note: This is an experimental feature and may be removed in the future. Currently, this functionality is only available on Windows for UDFs. The RunPython functionality is currently not supported.

22.1 How To

- 1) As usual, write your Python function and import it into Excel (see *User Defined Functions (UDFs)*).
- 2) Press Alt-F11 to get into the VBA editor, then right-click on the xlwings_udfs VBA module and select **Export File...** Save the xlwings_udfs.bas file somewhere.
- 3) Switch into the other Office app, e.g. Microsoft Access and click again Alt-F11 to get into the VBA editor. Right-click on the VBA Project and **Import File...**, then select the file that you exported in the previous step. Once imported, replace the app name in the first line to the one that you are using, i.e. Microsoft Access or Microsoft Outlook etc. so that the first line then reads: `#Const App = "Microsoft Access"`
- 4) Now import the standalone xlwings VBA module (xlwings.bas). You can find it in your xlwings installation folder. To know where that is, do:

```
>>> import xlwings as xw
>>> xlwings.__path__
```

And finally do the same as in the previous step and replace the App name in the first line with the name of the corresponding app that you are using. You are now able to call the Python function from VBA.

22.2 Config

The other Office apps will use the same global config file as you are editing via the Excel ribbon add-in. When it makes sense, you'll be able to use the directory config file (e.g. you can put it next to your Access or Word file) or you can hardcode the path to the config file in the VBA standalone module, e.g. in the function `GetDirectoryConfigFilePath` (e.g. suggested when using Outlook that doesn't really have the same concept of files like the other Office apps). NOTE: For Office apps without file concept, you need to make sure that the `PYTHONPATH` points to the directory with the Python source file. For details on the different config options, see [Config](#).

OVERVIEW PRO

xlwings PRO is [source-available](#) and dual-licensed under one of the following licenses:

- [xlwings PRO License](#) (commercial use requires a [paid plan](#))
- [PolyForm Noncommercial License 1.0.0](#) (non-commercial use is free)

23.1 PRO Features

- *Ultra Fast File Reader*: Similar to `pandas.read_excel()` but 5-25 times faster and you can leverage the convenient xlwings syntax. Works without an Excel installation and therefore on all platforms including Linux.
- *xlwings Server*: With xlwings Server, you don't need to install Python locally anymore. Instead, run it as a web app on a server. Works with Desktop Excel on Windows and macOS and with Google Sheet and Excel on the web. Runs on all platforms, including Linux, WSL and Docker.
- *Embedded code*: Store your Python source code directly in Excel for easy deployment.
- *xlwings Reports*: A template-based reporting framework, allowing business users to change the layout of the report without having to touch the Python code.
- *Markdown Formatting*: Support for Markdown formatting of text in cells and shapes like e.g., text boxes.
- *Permissioning*: Control which users can run which Python modules via xlwings.

Paid plans come with additional services like:

- *1-click Installer*: Easily build your own Python installer including all dependencies—your end users don't need to know anything about Python
- [On-demand video course](#)
- Direct Support

Check out the [paid plans](#) for more details!

23.2 License Key Activation

To use xlwings PRO, you need to install a license key on a Terminal/Command Prompt like so:

```
xlwings license update -k YOUR_LICENSE_KEY
```

Make sure to replace `LICENSE_KEY` with your personal key (see below). This will store the license key in your `xlwings.conf` file (see *User Config: Ribbon/Config File* for where this is on your system). Instead of running this command, you can also store the license key as an environment variable with the name `XLWINGS_LICENSE_KEY`.

License Key for Commercial Purpose:

- To try xlwings PRO for free in a commercial context, request a trial license key: <https://www.xlwings.org/trial>
- To use xlwings PRO in a commercial context beyond the trial, you need to enroll in a paid plan (they include additional services like support and the ability to create one-click installers): <https://www.xlwings.org/pricing>

xlwings PRO licenses are developer licenses, are verified offline (i.e., no telemetry/license server involved) and allow royalty-free deployments to unlimited internal end-users and servers for a hassle-free management. External end-users are included with the business plan. Deployments use deploy keys that don't expire but instead are bound to a specific version of xlwings.

License Key for non-commercial Purpose:

- To use xlwings PRO for free in a non-commercial context, use the following license key: `noncommercial` (Note that you need at least xlwings 0.26.0).

1-CLICK INSTALLER PRO

xlwings PRO offers a simple way to deploy your xlwings tools to your end users without the usual hassle that's involved when installing and configuring Python and xlwings. End users don't need to know anything about Python as they only need to:

- Run an installer (one installer can power many different Excel workbooks)
- Use the Excel workbook as if it was a normal macro-enabled workbook

Advantages:

- **Zero-config:** The end user doesn't have to configure anything throughout the whole process.
- **No add-in required:** No installation of the xlwings add-in required.
- **Easy to update:** If you want to deploy an update of your Python code, it's often good enough to distribute a new version of your workbook.
- **No conflicts:** The installer doesn't touch any environment variables or registry keys and will therefore not conflict with any existing Python installations.
- **Deploy key:** The release command will add a deploy key as your LICENSE_KEY. A deploy key won't expire and end users won't need a paid subscription.

You as a developer need to create the one-click installer and run the `xlwings release` command on the workbook. Let's go through these two steps in detail!

There is a video walkthrough at: https://www.youtube.com/watch?v=yw36VT_n1qg

24.1 Step 1: One-Click Installer

As a subscriber of one of our [paid plans](#), you will get access to a private GitHub repository, where you can build your one-click installer:

- 1) Update your `requirements.txt` file with your dependencies: in your repository, start by clicking on the `requirements.txt` file. This will open the following screen where you can click on the pencil icon to edit the file (if you know your way around Git, you can also clone the repository and use your local commit/push workflow instead):

After you're done with your edits, click on the green `Commit changes` button.

```
2 lines (1 sloc) | 22 Bytes
1 xlwings[pro]==0.20.8
2
```


Note: If you are unsure about your dependencies, it's best to work locally with a virtual or Conda environment. In the virtual/Conda environment, only install packages that you need, then run: `pip list --format=freeze`.

2) On the right-hand side of the landing page, click on Releases:



No releases published
[Create a new release](#)

On the next screen, click on **Draft a new release** (note, the very first time, you will see a green button called **Create a new release** instead):



This will bring up the following screen, where you'll only have to fill in a **Tag version** (e.g., `1.0.0`), then click on the green button **Publish release**:

After 3-5 minutes (you can follow the progress under the **Actions** tab), you'll find the installer ready for download under **Releases** (ignore the `zip` and `tar.gz` files):


Note: The one-click installer is a normal Python installation that you can use with multiple Excel workbooks. Hence, you don't need to create a separate installer for each workbook as long as they all work with the same set of dependencies as defined by the `requirements.txt` file.

Releases

Tags

1.0.0

@

 Target: main ▼


Choose an existing tag, or create a new tag on publish


Release title

Write

Preview

Describe this release


Attach files by dragging & dropping, selecting or pasting them. 

 Attach binaries by dropping them here or selecting them.

☐ **This is a pre-release**
We'll point out that this release is identified as non-production ready.

Publish release

Save draft



Releases Tags

Draft a new release

Latest release

1.2.0
7321e85

Compare

1.2.0
fzumstein released this 3 days ago

added more deps

Assets 4

installer.sh	1.67 KB
xlwings-runtime-1.2.0-x64.exe	83.1 MB
Source code (zip)	
Source code (tar.gz)	

24.2 Step 2: Release Command (CLI)

The release command is part of the xlwings CLI (command-line client) and will prepare your Excel file to work with the one-click installer generated in the previous step. Before anything else:

- Make sure that you have enabled Trust access to the VBA project object model under File > Options > Trust Center > Trust Center Settings > Macro Settings. You only need to do this once and since this is a developer setting, your end users won't need to bother about this. This setting is needed so that xlwings can update the Excel file with the correct version of the VBA code.
- Run the installer from the previous step. This will not interfere with your existing Python installation as it won't touch your environment variables or registry. Instead, it will only write to the following folder: %LOCALAPPDATA%\<installer-name>.
- Make sure that your local version of xlwings corresponds to the version of xlwings in the requirements.txt from the installer. The easiest way to double-check this is to run `pip freeze` on a Command Prompt or Anaconda Prompt. If your local version of xlwings differs, install the same version as the installer uses via: `pip install xlwings==<version from installer>`.

To work with the release command, you should have your workbook in the xlsx format and all the Python modules in the same folder:

```
myworkbook.xlsx
mymodule_one.py
mymodule_two.py
...
```

You currently can't organize your code in directories, but you can easily import `mymodule_two` from `mymodule_one`.

Make sure that your Excel workbook is the active workbook, then run the following command on a Command/Anaconda Prompt:

xlwings release

If this is the first time you are running this command, you will be asked a few questions. If you are shown a [Y/n], you can hit Enter to accept the default as expressed by the capitalized letter:

- **Name of your one-click installer?** *Type in the name of your one-click installer. If you want to use a different Python distribution (e.g., Anaconda), you can leave this empty (but you will need to update the xlwings.conf sheet with the Conda settings once the release command has been run).*
- **Embed your Python code?** [Y/n] *This will copy the Python code into the sheets of the Excel file. It will respect all Python files that are in the same folder as the Excel workbook.*
- **Hide the config sheet?** [Y/n] *This will hide the xlwings.conf sheet.*
- **Hide the sheets with the embedded Python code?** [Y/n] *If you embed your Python code, this will hide all sheets with a .py ending.*
- **Allow your tool to run without the xlwings add-in?** [Y/n] *This will remove the VBA reference to xlwings and copy in the xlwings VBA modules so that the end users don't need to have the xlwings add-in installed. Note that in this case, you will need to have your RunPython calls bound to a button as you can't use the Ribbon's Run main button anymore.*

Whatever answers you pick, you can always change them later by editing the xlwings.conf sheet or by deleting the xlwings.conf sheet and re-running the xlwings release command. If you go with the defaults, you only need to provide your end users with the one-click installer and the Excel workbook, no external Python files are required.

24.3 Updating a Release

To edit your Python code, it's easiest to work with external Python files and not with embedded code. To stop xlwings from using the embedded code, simply delete all sheets with a .py ending and the workbook will again use the external Python modules. Once you are done editing the files, simply run the xlwings release command again, which will embed the updated code. If you haven't done any changes to your dependencies (i.e., you haven't upgraded a package or introduced a new one), you only need to redeploy your Excel workbook to have the end users get the update.

If you did make changes to the requirements.txt and release a new one-click installer, you will need to have the users install the new version of the installer first.

Note: Every time you change the xlwings version in requirements.txt of your one-click installer, make sure to upgrade your local xlwings installatino to the same version and run xlwings release again!


24.4 Embedded Code Explained

When you run the `xlwings release` command, your code will be embedded automatically (except if you switch this behavior off). You can, however, also embed code directly: on a command line, run the following command:

```
xlwings code embed
```

This will import all Python files from the current directory and paste them into Excel sheets of the currently active workbook. Now, you can use `RunPython` as usual: `RunPython "import mymodule;mymodule.myfunction()"`.

Note that you can have multiple Excel sheets and import them like normal Python files. Consider this example:




You can call the `main` function from VBA like so:

```
Sub RandomNumbers()
    RunPython "import random_numbers;random_numbers.main()"
End Sub
```

Note:

- UDFs modules don't have to be added to the UDF Modules explicitly when using embedded code. However, in contrast to how it works with external files, you currently need to re-import the functions when you change them.



- While you can hide your sheets with your code, they will be written to a temporary directory in clear text.

PERMISSIONING PRO

xlwings allows you to control which Python modules are allowed to run from Excel. In order to use this functionality, you need to run your own web server. You can choose between an HTTP POST and a GET request for the permissioning:

- **GET:** This is the simpler option as you only need to host a static JSON file that you can generate via the xlwings CLI. You can use any web server that is capable of serving static files (e.g., nginx) or use a free external service like GitHub pages. However, every permission change requires you to update the JSON file on the server.
- **POST:** This option relies on the web server to validate the incoming payload of the POST request. While this requires custom logic on your end, you are able to connect it with any internal system (such as a database or LDAP server) to dynamically decide whether a user should be able to run a specific Python module through xlwings.

Before looking at both of these options in more detail, let's go through the prerequisites and configuration.

Note: This feature does not stop users from running arbitrary Python code through Python directly. Rather, think of it as a mechanism to prevent accidental execution of Python code from Excel via xlwings.

25.1 Prerequisites

- This functionality requires every end user to have the `requests` library installed. You can install them via `pip`:

```
pip install requests
```

or via Conda:

```
conda install requests
```

- You need to have a `LICENSE_KEY` in the form of a [trial key](#), a paid license key or a deploy key.

25.2 Configuration

While xlwings offers various ways to configure your workbook (see [Configuration](#)), it will only respect the permissioning settings in the config file in the user's home folder (on Windows, this is %USERPROFILE%\xlwings\xlwings.conf):

- To prevent end users from overwriting xlwings.conf, you'll need to make sure that the file is owned by the Administrator while giving end users read-only permissions.
- Add the following settings while replacing the PERMISSION_CHECK_URL and PERMISSION_CHECK_METHOD (POST or GET) with the appropriate value for your case. PERMISSION_CHECK_AUTHORIZATION is an optional setting that allows you to send a token with POST requests via the Authorization header:

```
"LICENSE_KEY", "YOUR_LICENSE_OR_DEPLOY_KEY"
"PERMISSION_CHECK_ENABLED", "True"
"PERMISSION_CHECK_URL", "https://myurl.com"
"PERMISSION_CHECK_METHOD", "POST"
"PERMISSION_CHECK_AUTHORIZATION", "your_token"
```

25.3 GET request

You can generate the static JSON file by using the xlwings CLI:

- Print the JSON string for all Python modules in a certain folder:

```
cd myfolder
xlwings permission cwd
```

- Print the JSON string for all embedded modules of the active workbook:

```
xlwings permission book
```

Both commands will print a JSON string similar to this one:

```
{
  "modules": [
    {
      "file_name": "myfile.py",
      "sha256": "cea259922207049a734c88930b5c09109deb6b55f692fd0832f4e57052d85896
→",
      "machine_names": [
        "DESKTOP-QQ27RP3"
      ]
    },
    {
      "file_name": "myfile2.py",
```

(continues on next page)

(continued from previous page)

```

    "sha256": "355200bb9ae00fcec1d7b660e7dd95fb3dbf246a9db397a6daa2471458a8e6cb",
    "machine_names": [
        "DESKTOP-QQ27RP3"
    ]
}
]
}

```

All you need to do at this point is:

- Add additional machines names e.g., "machine_names": ["DESKTOP-QQ27RP3", "DESKTOP-XY12AS2"]. Alternatively, you can use the "*" wildcard if you want to allow the module to be used on all end user's computers. In case of the wildcard, it will still make sure that the file's content hasn't been changed by looking at its sha256 hash. xlwings uses `import socket; socket.gethostname()` as the machine name.
- Make this JSON file accessible via your web server and update the settings in the `xlwings.conf` file accordingly (see above).

25.4 POST request

If you work with POST requests, xlwings will post a payload similar to the following:

```

{
  "machine_name": "DESKTOP-QQ27RP3",
  "modules": [
    {
      "file_name": "myfile.py",
      "sha256":
        ↪ "cea259922207049a734c88930b5c09109deb6b55f692fd0832f4e57052d85896"
    },
    {
      "file_name": "myfile2.py",
      "sha256":
        ↪ "355200bb9ae00fcec1d7b660e7dd95fb3dbf246a9db397a6daa2471458a8e6cb"
    }
  ]
}

```

It is now up to you to validate this request and:

- Return the HTTP status code 200 ("success") if the user is allowed to run the code of these modules
- Return the HTTP status code 403 ("forbidden") if the user is not allowed to run the code of these modules

Note that xlwings only checks for HTTP status code 200, so any other status code will fail.

25.5 Implementation Details & Limitations

- Currently, RunPython and user-defined functions (UDFs) are supported. RunFrozenPython is not supported.
- Permissions checks are only done when the Python module is run via Excel/xlwings, it has no effect on Python code that is run from Python directly.
- RunPython won't allow you to run code that uses the `from x import y` syntax. Use `import x;x.y` instead.
- The answer of the permissioning server is cached for the duration of the Python session. For UDFs, this means until the functions are re-imported or the **Restart UDF Server** button is clicked or until Excel is restarted. The same is true if you run RunPython with the **Use UDF Server** option. By default, however, RunPython starts a new Python session every time, so it will contact the server whenever you call RunPython.
- Only top-level modules are checked, i.e. modules that are imported as UDFs or run via RunPython call. Any modules that are imported as dependencies of these modules are not checked.
- RunPython with external Python source files depends on logic in the VBA part of xlwings. UDFs and RunPython calls that use embedded code will only rely on Python to perform the permissioning check.

EXCEL FILE READER PRO

This feature requires at least v0.28.0.

xlwings PRO comes with an ultra fast Excel file reader. Compared with `pandas.read_excel()`, you should be able to see speedups anywhere between 5 to 25 times when reading a single sheet. The exact speed will depend on your content, file format, and Python version. The following Excel file formats are supported:

- `xlsx / xlsxm / xlam`
- `xlsb`
- `xls`

Other advantages include:

- Support for named ranges
- Support for dynamic ranges via `myrange.expand()` or `myrange.options(expand="table")`, respectively.
- Support for converters so you can read in ranges not just as pandas DataFrames, but also as NumPy arrays, lists, scalar values, dictionaries, etc.
- You can read out cell errors like `#DIV/0!` or `#N/A` as strings instead of converting them all into NaN

Unlike the classic (“interactive”) use of xlwings that requires Excel to be installed, reading a file doesn’t depend on an installation of Excel and therefore works everywhere where Python runs. However, reading directly from a file requires the workbook to be saved before xlwings is able to pick up any changes.

26.1 Reading a specific range

To open a file in read mode, provide the `mode="r"` argument: `xw.Book("myfile.xlsx", mode="r")`. You usually want to use `Book` as a context manager so that the file is automatically closed and resources cleaned up once the code leaves the body of the `with` statement:

```
import xlwings as xw

with xw.Book("myfile.xlsx", mode="r") as book:
    sheet1 = book.sheets[0]
    data = sheet1["A1:B2"].value
```

If you don't use the `with` statement, make sure to close the book manually via `book.close()`.

26.2 Reading an entire sheet

To read an entire sheet, use the `cells` property:

```
with xw.Book("myfile.xlsx", mode="r") as book:
    sheet1 = book.sheets[0]
    data = sheet1.cells.value
```

26.3 Converters: DataFrames etc.

You can use the usual converters, for example to read in a range as a DataFrame:

```
with xw.Book("myfile.xlsx", mode="r") as book:
    sheet1 = book.sheets[0]
    df = sheet1["A1:B2"].options("df").value
    # As usual, you can also provide more options
    df = sheet1["A1:B2"].options("df", index=False).value
```

For more details, see *Converters and Options*.

26.4 Named Ranges

Named ranges can be accessed like so:

```
with xw.Book("myfile.xlsx", mode="r") as book:
    sheet1 = book.sheets[0]
    data = sheet1["myname"].value # get values
    address = sheet1["myname"].address # get address
```

Alternatively, you can also access them via the *Names* collection:

```
with xw.Book("myfile.xlsx", mode="r") as book:
    for name in book.names:
        print(name.refers_to_range.value)
```

26.5 Dynamic Ranges

You can make use of the usual range expansion to read in a range of dynamic size:

```
with xw.Book("myfile.xlsx", mode="r") as book:
    sheet1 = book.sheets[0]
    data = sheet1["A1"].expand().value
```

26.6 Cell errors

While xlwings reads in cell errors such as #N/A as None by default, you may want to read them in as strings if you're specifically looking for these by using the `err_to_str` option:

```
with xw.Book("myfile.xlsx", mode="r") as book:
    sheet1 = book.sheets[0]
    data = sheet1["A1:B2"].option(err_to_str=True).value
```

26.7 Limitations

- The reader is currently only available via `pip install xlwings`. Installation via conda is not yet supported, but you can still use pip to install xlwings into a Conda environment!
- Date cells: Excel cells with a Date/Time are currently only converted to a `datetime` object in Python for `xlsx` file formats. For `xlsb` format, pandas has the same restriction though (it uses `pyxlsb` under the hood).
- Dynamic ranges: `myrange.expand()` is currently inefficient, so will slow down the reading considerably if the dynamic range is big.
- Named ranges: Named ranges with sheet scope are currently not shown with their proper name: E.g. `mybook.names[0].name` will show the name `mylocalname` instead of including the sheet name like so `Sheet1!mylocalname`. Along the same lines, the `names` property can only be accessed via `book` object, not via `sheet` object. Other defined names (formulas and constants) are currently not supported.
- Excel tables: Accessing data via table names isn't supported at the moment.
- Options: except for `err_to_str`, non-default options are currently inefficient and will slow down the read operation. This includes `dates`, `empty`, and `numbers`.
- Formulas: currently only the cell values are supported, but not the cell formulas.
- This is only a file reader, writing files is currently not supported.

XLWINGS REPORTS PRO

xlwings Reports is a solution for template-based Excel and PDF reporting, making the generation of pixel-perfect factsheets really simple. xlwings Reports allows business users without Python knowledge to create and maintain Excel templates without having to rely on a Python developer after the initial setup has been done: xlwings Reports separates the Python code (pre- and post-processing) from the Excel template (layout/formatting).

xlwings Reports supports all commonly required components:

- **Text:** Easily format your text via Markdown syntax.
- **Tables (dynamic):** Write pandas DataFrames to Excel cells and Excel tables and format them dynamically based on the number of rows.
- **Charts:** Use your favorite charting engine: Excel charts, Matplotlib, or Plotly.
- **Images:** You can include both raster (e.g., png) or vector (e.g., svg) graphics, including dynamically generated ones, e.g., QR codes or plots.
- **Multi-column Layout:** Split your content up into e.g. a classic two column layout by using Frames.
- **Single Template:** Generate reports in various languages, for various funds etc. based on a single template.
- **PDF Report:** Generate PDF reports automatically and “print” the reports on PDFs in your corporate layout for pixel-perfect results including headers, footers, backgrounds and borderless graphics.
- **Easy Pre-processing:** Since everything is based on Python, you can connect with literally any data source and clean it with pandas or some other library.
- **Easy Post-processing:** Again, with Python you’re just a few lines of code away from sending an email with the reports as attachment or uploading the reports to your web server, S3 bucket etc.

27.1 Quickstart

You can work on the sheet, book or app level:

- `mysheet.render_template(**data)`: replaces the placeholders in `mysheet`
- `mybook.render_template(**data)`: replaces the placeholders in all sheets of `mybook`
- `myapp.render_template(template, output, **data)`: convenience wrapper that copies a template book before replacing the placeholder with the values. Since this approach allows you to work with hidden Excel instances, it is the most commonly used method for production.

Let's go through a typical example: start by creating the following Python script `report.py`:

```
# report.py
from pathlib import Path

import pandas as pd
import xlwings as xw

# We'll place this file in the same directory as the Excel template
this_dir = Path(__file__).resolve().parent

data = dict(
    title='MyTitle',
    df=pd.DataFrame(data={'one': [1, 2], 'two': [3, 4]})
)

# Change visible=False to run this in a hidden Excel instance
with xw.App(visible=True) as app:
    book = app.render_template(this_dir / 'mytemplate.xlsx',
                              this_dir / 'myreport.xlsx',
                              **data)
    book.to_pdf(this_dir / 'myreport.pdf')
```

Then create the following Excel file called `mytemplate.xlsx`:

	A	B	C	D
1	{{ title }}			
2				
3	My DataFrame			
4	{{ df }}			
5				
6				

Run the Python script (or run the code from a Jupyter notebook):

```
python report.py
```

This will copy the template and create the following output by replacing the variables in double curly braces with the value from the Python variable:

	A	B
1	MyTitle	
2		
3	My DataFrame	
4	one	two
5	1	3
6	2	4
7		

If you like, you could also create a classic xlwings tool to call this script or you could design a GUI app by using a framework like PySimpleGUI and turn it into an executable by using a freezer (e.g., PyInstaller). This, however, is beyond the scope of this tutorial.

Note: By default, xlwings Reports overwrites existing values in templates if there is not enough free space for your variable. If you want your rows to dynamically shift according to the height of your array, use [Frames](#).

Note: Unlike xlwings, xlwings Reports never writes out the index of pandas DataFrames. If you need the index to appear in Excel, use `df.reset_index()`, see [DataFrames](#).

See also `render_templates` (API reference).

27.1.1 Render Books and Sheets

Sometimes, it's useful to render a single book or sheet instead of using the `myapp.render_template` method. This is a workbook stored as `Book1.xlsx`:

Running the following code:

```
import xlwings as xw

book = xw.Book('Book1.xlsx')
sheet = book.sheets['template'].copy(name='report')
```

(continues on next page)

	A	B	C
1	{{ title }}		
2			
3	{{ table }}		
4			
5			
6			
7			
8			

template +

(continued from previous page)

```
sheet.render_template(title='A Demo!', table=[[1, 2], [3, 4]])
book.to_pdf()
```

Copies the template sheet first and then fills it in:

	A	B	C
1	A Demo!		
2			
3	1	2	
4	3	4	
5			
6			
7			
8			

template report

See also the [mysheet.render_template \(API reference\)](#) and [mybook.render_template \(API reference\)](#).

New in version 0.22.0.

27.2 DataFrames


To write DataFrames in a consistent manner to Excel, xlwings Reports ignores the DataFrame indices. If you need to pass the index over to Excel, reset the index before passing in the DataFrame to `render_template`: `df.reset_index()`.

When working with pandas DataFrames, the report designer often needs to tweak the data. Thanks to filters, they can do the most common operations directly in the template without the need to write Python code. A filter is added to the placeholder in Excel by using the pipe character: `{{ myplaceholder | myfilter }}`. You can combine multiple filters by using multiple pipe characters: they are applied from left to right,

i.e. the result from the first filter will be the input for the next filter. Let's start with an example before listing each filter with its details:

```
import xlwings as xw
import pandas as pd

book = xw.Book('Book1.xlsx')
sheet = book.sheets['template'].copy(name='report')
df = pd.DataFrame({'one': [1, 2, 3], 'two': [4, 5, 6], 'three': [7, 8, 9]})
sheet.render_template(df=df)
```



	A	B	C	D
1	{{ df }}			
2				
3				
4				
5				
6				
7	{{ df noheader }}			
8				
9				
10				
11				
12				
13	{{ df sortdesc(1) columns(0, None, 1) }}			
14				
15				
16				
17				

	A	B	C	D
1	one	two	three	
2	1	4	7	
3	2	5	8	
4	3	6	9	
5				
6				
7	1	4	7	
8	2	5	8	
9	3	6	9	
10				
11				
12				
13	one		two	
14	3		6	
15	2		5	
16	1		4	
17				

27.2.1 DataFrames Filters

noheader

Hide the column headers

Example:

```
{{ df | noheader }}
```

header

Only return the header

Example:

```
{{ df | header }}
```

sortasc

Sort in ascending order (indices are zero-based)

Example: sort by second, then by first column:

```
{{ df | sortasc(1, 0) }}
```

sortdesc

Sort in descending order (indices are zero-based)

Example: sort by first, then by second column in descending order:

```
{{ df | sortdesc(0, 1) }}
```

columns

Select/reorder columns and insert empty columns (indices are zero-based)

See also: `colslice`

Example: introduce an empty column (`None`) as the second column and switch the order of the second and third column:

```
{{ df | columns(0, None, 2, 1) }}
```

Merged cells: you'll also have to introduce empty columns if you are using merged cells in your Excel template.

mul, div, sum, sub

Apply an arithmetic operation (multiply, divide, sum, subtract) on a column (indices are zero-based)

Syntax:

```
{{ df | operation(value, col_ix[, fill_value]) }}
```

`fill_value` is optional and determines whether empty cells are included in the operation or not. To include empty values and thus make it behave like in Excel, set it to `0`.

Example: multiply the first column by 100:

```
{{ df | mul(100, 0) }}
```

Example: multiply the first column by 100 and the second column by 2:

```
{{ df | mul(100, 0) | mul(2, 1) }}
```

Example: add 100 to the first column including empty cells:

```
{{ df | add(100, 0, 0) }}
```

maxrows

Maximum number of rows (currently, only `sum` is supported as aggregation function)

If your DataFrame has 12 rows and you use `maxrows(10, "Other")` as filter, you'll get a table that shows the first 9 rows as-is and sums up the remaining 3 rows under the label `Other`. If your data is unsorted, make sure to call `sortasc/sortdesc` first to make sure the correct rows are aggregated.

See also: `aggsmall`, `head`, `tail`, `rowslice`

Syntax:

```
{{ df | maxrows(number_rows, label[, label_col_ix]) }}
```

`label_col_ix` is optional: if left away, it will label the first column of the DataFrame (index is zero-based)

Examples:

```
{{ df | maxrows(10, "Other") }}
{{ df | sortasc(1) | maxrows(5, "Other") }}
{{ df | maxrows(10, "Other", 1) }}
```

aggsmall

Aggregate rows with values below a certain threshold (currently, only `sum` is supported as aggregation function)

If the values in the specified row are below the threshold values, they will be summed up in a single row.

See also: `maxrows`, `head`, `tail`, `rowslice`

Syntax:

```
{{ df | aggsmall(threshold, threshold_col_ix, label[, label_col_ix][, min_rows]) ↵
↵ }}
```

label_col_ix and min_rows are optional: if label_col_ix is left away, it will label the first column of the DataFrame (indices are zero-based). min_rows has the effect that it skips rows from aggregating if it otherwise the number of rows falls below min_rows. This prevents you from ending up with only one row called “Other” if you only have a few rows that are all below the threshold. NOTE that this parameter only makes sense if the data is sorted!

Examples:

```
{{ df | aggsmall(0.1, 2, "Other") }}  
{{ df | sortasc(1) | aggsmall(0.1, 2, "Other") }}  
{{ df | aggsmall(0.5, 1, "Other", 1) }}  
{{ df | aggsmall(0.5, 1, "Other", 1, 10) }}
```

head

Only show the top n rows

See also: maxrows, aggsmall, tail, rowslice

Example:

```
{{ df | head(3) }}
```

tail

Only show the bottom n rows

See also: maxrows, aggsmall, head, rowslice

Example:

```
{{ df | tail(5) }}
```

rowslice

Slice the rows

See also: maxrows, aggsmall, head, tail

Syntax:

```
{{ df | rowslice(start_index[, stop_index]) }}
```

stop_index is optional: if left away, it will stop at the end of the DataFrame

Example: Show rows 2 to 4 (indices are zero-based and interval is half-open, i.e. the start is including and the end is excluding):

```
{{ df | rowslice(2, 5) }}
```

Example: Show rows 2 to the end of the DataFrame:

```
{{ df | rowslice(2) }}
```

colslice

Slice the columns

See also: `columns`

Syntax:

```
{{ df | colslice(start_index[, stop_index]) }}
```

`stop_index` is optional: if left away, it will stop at the end of the DataFrame

Example: Show columns 2 to 4 (indices are zero-based and interval is half-open, i.e. the start is including and the end is excluding):

```
{{ df | colslice(2, 5) }}
```

Example: Show columns 2 to the end of the DataFrame:

```
{{ df | colslice(2) }}
```

vmerge

Merge cells vertically for adjacent cells with the same value — can be used to represent hierarchies

Note: The `vmerge` filter does not work in Excel tables, as Excel tables don't support merged cells!

Note that the screenshot uses 4 *Frames* and the text is centered/vertically aligned in the template.

Syntax (arguments are optional):

```
{{ df | vmerge(col_index1, col_index2, ...) }}
```

Example (default): Hierarchical mode across all columns — this is helpful if the number of columns is dynamic. In hierarchical mode, cells are merged vertically in the first column (indices are zero-based) and cells in the next columns are merged only within the merged cells of the previous column:

```
{{ df | vmerge }}
```

Example: Hierarchical mode across the specified columns only:

	A	B	C	D	E	F	G	H	I	J	K
1	{{ df }}		{{ df vmerge(0, 1) }}			{{ df vmerge(0) vmerge(1) }}			{{ df vmerge }}		
2											



	A	B	C	D	E	F	G	H	I	J	K
1	one	two	one	two	one	two	one	two	one	two	
2	a	a	a	a	a	a	a	a	a	a	
3	a	b		b		b		b		b	
4	b	a									
5	b	a	b	a		b	a		b	a	
6	b	a						a			
7	c	a	c	a		c			c	a	
8	d	a	d	a		d			d	a	
9	d	b		b			b			b	

```
{{ df | vmerge(0, 1) }}
```

Example: Independent mode: If you want to merge cells within columns independently of each other, use the filter multiple times. This sample merge cells vertically in the first two columns (indices are zero-based):

```
{{ df | vmerge(0) | vmerge(1) }}
```

formatter

The `formatter` filter accepts the name of a function. The function will be called after writing the values to Excel and allows you to easily style the range in a very flexible way:

```
{{ df | formatter("myformatter") }}
```

The formatter's signature is: `def myformatter(rng, df)` where `rng` corresponds to the range where the original DataFrame `df` is written to. Adding type hints (as shown in the example below) will help your editor with auto-completion.

Note: Within the reports framework, formatters need to be decorated with `xlwings.reports.formatter` (see example below)! This isn't necessary though when you use them as part of the standard xlwings API.

Let's run through the Quickstart example again, amended by a formatter.

Example:

```
from pathlib import Path
```

(continues on next page)

(continued from previous page)

```

import pandas as pd
import xlwings as xw
from xlwings.reports import formatter

# We'll place this file in the same directory as the Excel template
this_dir = Path(__file__).resolve().parent

@formatter
def table(rng: xw.Range, df: pd.DataFrame):
    """This is the formatter function"""
    # Header
    rng[0, :].color = "#A9D08E"

    # Rows
    for ix, row in enumerate(rng.rows[1:]):
        if ix % 2 == 0:
            row.color = "#D0CECE" # Even rows

    # Columns
    for ix, col in enumerate(df.columns):
        if 'two' in col:
            rng[1:, ix].number_format = '0.0%'

data = dict(
    title='MyTitle',
    df=pd.DataFrame(data={'one': [1, 2, 3, 4], 'two': [5, 6, 7, 8]})
)


# Change visible=False to run this in a hidden Excel instance
with xw.App(visible=True) as app:
    book = app.render_template(this_dir / 'mytemplate.xlsx',
                              this_dir / 'myreport.xlsx',
                              **data)

```

	A	B		A	B
1	{{ df formatter("table") }}			1	one two
2				2	1 500.0%
3				3	2 600.0%
4				4	3 700.0%
5				5	4 800.0%
6				6	

27.3 Excel Tables

Using Excel tables is the recommended way to format tables as the styling can be applied dynamically across columns and rows. You can also use themes and apply alternating colors to rows/columns. Go to **Insert > Table** and make sure that you activate **My table has headers** before clicking on OK. Add the placeholder as usual on the top-left of your Excel table (note that this example makes use of [Frames](#)):



The screenshot shows an Excel spreadsheet with columns A, B, and C, and rows 1 through 7. A table is defined in the range A1:C4. The table has a header row (A1) with the text 'Title'. The data rows are A2, A3, and A4. The cell A3 contains the placeholder text '{{ df }}'. A yellow rectangular frame is overlaid on the table, with its top-left corner at cell A1 and its bottom-right corner at cell C4. The frame contains the text '<frame>'. A red arrow points from the frame to the text '<frame>'. The cell A6 contains the text 'Some static text.'.

	A	B	C
1	Title		
2			
3	{{ df }}		
4			
5			
6	Some static text.		
7			

Running the following script:

```
import pandas as pd

nrows, ncols = 3, 3
df = pd.DataFrame(data=nrows * [ncols * ['test']],
                  columns=[f'col {i}' for i in range(ncols)])

with xw.App(visible=True) as app:
    book = app.render_template('template.xlsx', 'output.xlsx', df=df)
```

Will produce the following report:

Headers of Excel tables are relatively strict, e.g. you can't have multi-line headers or merged cells. To get around these limitations, uncheck the **Header Row** checkbox under **Table Design** and use the **noheader** filter (see [DataFrame filters](#)). This will allow you to design your own headers outside of the Excel Table.

Note:

- At the moment, you can only assign pandas DataFrames to tables
-

	A	B	C
1	Title		
2			
3	col 0	col 1	col 2
4	test	test	test
5	test	test	test
6	test	test	test
7			
8	Some static text.		

27.4 Excel Charts

To use Excel charts in your reports, follow this process:

1. Add some sample/dummy data to your Excel template:

F6			
	A	B	C
1		Q1	Q2
2	North	1	2
3	South	3	4
4			
5			

2. If your data source is dynamic, turn it into an Excel Table (Insert > Table). Make sure you do this *before* adding the chart in the next step.
3. Add your chart and style it:

	A	B	C	D
1	Column1 ▼	Q1 ▼	Q2 ▼	
2	North	1	2	
3	South	3	4	
4				
5				

4. Reduce the Excel table to a 2 x 2 range and add the placeholder in the top-left corner (in our example `{{ chart_data }}`). You can leave in some dummy data or clear the values of the Excel table:
5. Assuming your file is called `mytemplate.xlsx` and your sheet `template` like on the previous screenshot, you can run the following code:


```
import xlwings as xw
import pandas as pd


df = pd.DataFrame(data={'Q1': [1000, 2000, 3000],
                        'Q2': [4000, 5000, 6000],
                        'Q3': [7000, 8000, 9000]},
                  index=['North', 'South', 'West'])


book = xw.Book("mytemplate.xlsx")
sheet = book.sheets['template'].copy(name='report')
sheet.render_template(chart_data=df.reset_index())
```

This will produce the following report, with the chart source correctly adjusted:

Note: If you don't want the source data on your report, you can place it on a separate sheet. It's easiest if you add and design the chart on the separate sheet, before cutting the chart and pasting it on your report template. To prevent the data sheet from being printed when calling `to_pdf`, you can give it a name that starts with `#` and it will be ignored. NOTE that if you start your sheet name with `##`, it won't be printed but also not rendered!







27.5 Images

Images are inserted so that the cell with the placeholder will become the top-left corner of the image. For example, write the following placeholder into you desired cell: `{{ logo }}`, then run the following code:

```
import xlwings as xw
from xlwings.reports import Image

book = xw.Book('Book1.xlsx')
sheet = book.sheets['template'].copy(name='report')
sheet.render_template(logos=Image(r'C:\path\to\logo.png'))
```

Note: Image also accepts a `pathlib.Path` object instead of a string.

If you want to use vector-based graphics, you can use `svg` on Windows and `pdf` on macOS. You can control the appearance of your image by applying filters on your placeholder.

Available filters for Images:

- **width:** Set the width in pixels (height will be scaled proportionally).

Example:

```
{{ logo | width(200) }}
```

- **height:** Set the height in pixels (width will be scaled proportionally).

Example:

```
{{ logo | height(200) }}
```

- **width and height:** Setting both width and height will distort the proportions of the image!

Example:

```
{{ logo | height(200) | width(200) }}
```

- **scale:** Scale your image using a factor (height and width will be scaled proportionally).

Example:

```
{{ logo | scale(1.2) }}
```

- **top:** Top margin. Has the effect of moving the image down (positive pixel number) or up (negative pixel number), relative to the top border of the cell. This is very handy to fine-tune the position of graphics object.

See also: `left`

Example:

```
{{ logo | top(5) }}
```

- **left**: Left margin. Has the effect of moving the image right (positive pixel number) or left (negative pixel number), relative to the left border of the cell. This is very handy to fine-tune the position of graphics object.

See also: `top`

Example:

```
{{ logo | left(5) }}
```

27.6 Matplotlib and Plotly Plots

For a general introduction on how to handle Matplotlib and Plotly, see also: [Matplotlib](#). There, you'll also find the prerequisites to be able to export Plotly charts as pictures.

27.6.1 Matplotlib

Write the following placeholder in the cell where you want to paste the Matplotlib plot: `{{ lineplot }}`. Then run the following code to get your Matplotlib Figure object:

```
import matplotlib.pyplot as plt
import xlwings as xw

fig = plt.figure()
plt.plot([1, 2, 3])

book = xw.Book('Book1.xlsx')
sheet = book.sheets['template'].copy(name='report')
sheet.render_template(lineplot=fig)
```

27.6.2 Plotly

Plotly works practically the same:

```
import plotly.express as px
import xlwings as xw

fig = px.line(x=["a", "b", "c"], y=[1, 3, 2], title="A line plot")
book = xw.Book('Book1.xlsx')
sheet = book.sheets['template'].copy(name='report')
sheet.render_template(lineplot=fig)
```

To change the appearance of the Matplotlib or Plotly plot, you can use the same filters as with images. Additionally, you can use the following filter:

- **format**: allows to change the default image format from `png` to e.g., `vector`, which will export the plot as vector graphics (`svg` on Windows and `pdf` on macOS). As an example, to make the chart smaller and use the vector format, you would write the following placeholder:

```
{{ lineplot | scale(0.8) | format("vector") }}
```

27.7 Text

You can work with placeholders in text that lives in cells or shapes like text boxes. If you have more than just a few words, text boxes usually make more sense as they won't impact the row height no matter how you style them. Using the same grid formatting across worksheets is key to getting a consistent multi-page report.

27.7.1 Simple Text without Formatting

New in version 0.21.4.

You can use any shapes like rectangles or circles, not just text boxes:

```
with xw.App(visible=True) as app:
    app.render_template('template.xlsx', 'output.xlsx', temperature=12.3)
```

This code turns this template:

	A	B	C	D	E	F	G
1							
2							
3							
4							
5							
6							
7							

into this report:

	A	B	C	D	E	F	G
1							
2							
3							
4							
5							
6							
7							

While this works for simple text, you will lose the formatting if you have any. To prevent that, use a Markdown object, as explained in the next section.

If you will be printing on a *PDF Layout* with a dark background, you may need to change the font color to white. This has the nasty side effect that you won't see anything on the screen anymore. To solve that issue, use the `fontcolor` filter:

- **fontcolor:** Change the color of the whole (!) cell or shape. The primary purpose of this filter is to make white fonts visible in Excel. For most other colors, you can just change the color in Excel itself. Note that this filter changes the font of the whole cell or shape and only has an effect if there is just a single placeholder—if you need to manipulate single words, use Markdown instead, see below. Black and white can be used as word, otherwise use a hex notation of your desired color.

Example:

```
{{ mytitle | fontcolor("white") }}
{{ mytitle | fontcolor("#efefef") }}
```

27.7.2 Markdown Formatting

New in version 0.23.0.

You can format text in cells or shapes via Markdown syntax. Note that you can also use placeholders in the Markdown text that will take the values from the variables you supply via the `render_template` method:

```
import xlwings as xw
from xlwings.reports import Markdown

mytext = """\
# Title

Text bold and italic

* A first bullet
* A second bullet

# {{ second_title }}

This paragraph has a line break.
Another line.
"""

# The first sheet requires a shape as shown on the screenshot
sheet = xw.sheets.active
sheet.render_template(myplaceholder=Markdown(mytext),
                     second_title='Another Title')
```

This will render this template with the placeholder in a cell and a shape:

	A	B	C	D	E	F
	{{ myplaceholder }}	<div> {{ myplaceholder }} </div>				
1						
2						
3						

Like this (this uses the default formatting):

	A	B	C	D	E	F
	Title Text bold and <i>italic</i> <ul style="list-style-type: none"> • A first bullet • A second bullet Another Title This paragraph has a line break. 1 Another line. 2	<div> Title Text bold and <i>italic</i> <ul style="list-style-type: none"> • A first bullet • A second bullet Another Title This paragraph has a line break. Another line. </div>				

For more details about Markdown, especially about how to change the styling, see [Markdown](#).

27.8 Date and Time

If a placeholder corresponds to a Python `datetime` object, by default, Excel will format that cell as a date-formatted cell. This isn't always desired as the formatting depends on the user's regional settings. To prevent that, format the cell in the Text format or use a `TextBox` and use the `datetime` filter to format the date in the desired format. The `datetime` filter accepts the `strftime` syntax—for a good reference, see e.g., strftime.org.

To control the language of month and weekday names, you'll need to set the `locale` in your Python code. For example, for German, you would use the following:

```
import locale
locale.setlocale(locale.LC_ALL, 'de_DE')
```

Example: The default formatting is December 1, 2020:

```
{{ mydate | datetime }}
```

Example: To apply a specific formatting, provide the desired format as filter argument. For example, to get it in the 12/31/20 format:

```
{{ mydate | datetime("%m/%d/%y") }}
```

27.9 Number Format

The `format` filter allows you to format numbers by using the same mechanism as offered by Python's f-strings. For example, to format the placeholder `performance=0.13` as `13.0%`, you would do the following:

```
{{ performance | format(".1%") }}
```

This corresponds to the following f-string in Python: `f"{performance:0.1%}"`. To get an introduction to the formatting string syntax, have a look at the [Python String Format Cookbook](#).

27.10 Frames: Multi-column Layout

Frames are vertical containers in which content is being aligned according to their height. That is, within Frames:

- Variables do not overwrite existing cell values as they do without Frames.
- Formatting is applied dynamically, depending on the number of rows your object uses in Excel

To use Frames, insert a Note with the text `<frame>` into **row 1** of your Excel template wherever you want a new dynamic column to start. Frames go from one `<frame>` to the next `<frame>` or the right border of the used range.

How Frames behave is best demonstrated with an example: The following screenshot defines two frames. The first one goes from column A to column E and the second one goes from column F to column I, since this is the last column that is used.

	A	B	C	D	E	F	G	H	I
1	Table 1	<frame>				Table 3	<frame>		
2	{{ df1 }}					{{ df2 }}			
3									
4									
5	Table 2					Table 4			
6	{{ df2 }}					{{ df1 }}			
7									

You can define and format DataFrames by formatting

- one header and

- one data row

If you use the `noheader` filter for DataFrames, you can leave the header away and format a single data row. Alternatively, you could also use Excel Tables, as they can make formatting easier.

Running the following code:

```
import pandas as pd

df1 = pd.DataFrame([[1, 2, 3], [4, 5, 6], [7, 8, 9]])
df2 = pd.DataFrame([[1, 2, 3], [4, 5, 6], [7, 8, 9], [10, 11, 12], [13, 14, 15]])

data = dict(df1=df1.reset_index(), df2=df2.reset_index())

with xw.App(visible=True) as app:
    book = app.render_template('my_template.xlsx',
                              'my_report.xlsx',
                              **data)
```

will generate this report:

	A	B	C	D	E	F	G	H	I
1	Table 1					Table 3			
2		0	1	2			0	1	2
3	0	1	2	3		0	1	2	3
4	1	4	5	6		1	4	5	6
5	2	7	8	9		2	7	8	9
6						3	10	11	12
7	Table 2					4	13	14	15
8		0	1	2					
9	0	1	2	3		Table 4			
10	1	4	5	6			0	1	2
11	2	7	8	9		0	1	2	3
12	3	10	11	12		1	4	5	6
13	4	13	14	15		2	7	8	9

27.11 PDF Layout

Using the `layout` parameter in the `to_pdf()` command, you can “print” your Excel workbook on professionally designed PDFs for pixel-perfect reports in your corporate layout including headers, footers, backgrounds and borderless graphics:

```
import pandas as pd
```

(continues on next page)


(continued from previous page)

```
df = pd.DataFrame([[1, 2, 3], [4, 5, 6], [7, 8, 9]])

with xw.App(visible=True) as app:
    book = app.render_template('template.xlsx',
                              'report.xlsx',
                              month_year = 'May 21',
                              summary_text = '...')
    book.to_pdf('report.pdf', layout='monthly_layout.pdf')
```

Note that the layout PDF either needs to consist of a single page (will be used for each reporting page) or will need to have the same number of pages as the report (each report page will be printed on the corresponding layout page).

To create your layout PDF, you can use any program capable of exporting a file in PDF format such as PowerPoint or Word, but for the best results consider using a professional desktop publishing software such as Adobe InDesign.



MARKDOWN FORMATTING PRO

New in version 0.23.0.

Markdown offers an easy and intuitive way of styling text components in your cells and shapes. For an introduction to Markdown, see e.g., [Mastering Markdown](#).

Markdown support is in an early stage and currently only supports:

- First-level headings
- Bold (i.e., strong)
- Italic (i.e., emphasis)
- Unordered lists

It doesn't support nested objects yet such as 2nd-level headings, bold/italic within bullet points or nested bullet points.

Let's go through an example to see how everything works!

```
from xlwings.reports import Markdown, MarkdownStyle

mytext = """\
# Title

Text bold and italic

* A first bullet
* A second bullet

# Another Title

This paragraph has a line break.
Another line.
"""

sheet = xw.Book("Book1.xlsx").sheets[0]

# Range
```

(continues on next page)

(continued from previous page)


```

sheet['A1'].clear()
sheet['A1'].value = Markdown(mytext)

# Shape: The following expects a shape like a Rectangle on the sheet
sheet.shapes[0].text = ""
sheet.shapes[0].text = Markdown(mytext)

```

Running this code will give you this nicely formatted text:

	A	B	C	D	E	F
	Title					
	Text bold and <i>italic</i>					
	<ul style="list-style-type: none"> • A first bullet • A second bullet 					
	Another Title					
	This paragraph has a line break.					
1	Another line.					
2						

But why not make things a tad more stylish? By providing a MarkdownStyle object, you can define your style. Let's change the previous example like this:

```

from xlwings.reports import Markdown, MarkdownStyle

mytext = """\
# Title

Text bold and italic

* A first bullet
* A second bullet

# Another Title

This paragraph has a line break.
Another line.
"""\

sheet = xw.Book("Book1.xlsx").sheets[0]

# Styling
style = MarkdownStyle()

```

(continues on next page)

(continued from previous page)

```

style.h1.font.color = (255, 0, 0)
style.h1.font.size = 14
style.h1.font.name = 'Comic Sans MS' # No, that's not a font recommendation...
style.h1.blank_lines_after = 0
style.unordered_list.bullet_character = '\N{heavy black heart}' # Emojis are ↪ fun!

# Range
sheet['A1'].clear()
sheet['A1'].value = Markdown(mytext, style) # <= provide your style object here

# Shape: The following expects a shape like a Rectangle on the sheet
sheet.shapes[0].text = ""
sheet.shapes[0].text = Markdown(mytext, style)

```

Here is the output of this:

	A	B	C	D	E	F
	Title Text bold and <i>italic</i> ♥ A first bullet ♥ A second bullet Another Title This paragraph has a line break. 1 Another line. 2	Title Text bold and <i>italic</i> ♥ A first bullet ♥ A second bullet Another Title This paragraph has a line break. Another line.				

You can override all properties, i.e., you can change the emphasis from italic to a red font or anything else you want:

```

>>> style.strong.bold = False
>>> style.strong.color = (255, 0, 0)
>>> style.strong
strong.color: (255, 0, 0)

```

Markdown objects can also be used with template-based reporting, see *xlwings Reports PRO*.

Note: macOS currently doesn't support the formatting (bold, italic, color etc.) of Markdown text due to a bug with AppleScript/Excel. The text will be rendered correctly though, including bullet points.

See also the API reference:

- Markdown class

- `MarkdownStyle` class

XLWINGS SERVER PRO

This feature requires at least v0.27.0.

Instead of installing Python on each end-user's machine, you can work with a server-based Python installation. It's essentially a web application, but uses your spreadsheet as the frontend instead of a web page in a browser. xlwings Server doesn't just work with the Desktop versions of Excel on Windows and macOS but additionally supports Google Sheets and Excel on the web for a full cloud experience. xlwings Server runs everywhere where Python runs, including Linux, Docker and WSL (Windows Subsystem for Linux). It can run on your local machine, as a (serverless) cloud service, or on an on-premise server.

Important: This feature currently only covers parts of the RunPython API (UDFs are not yet supported). See also [Limitations](#) and [Roadmap](#).

29.1 Why is this useful?

Having to install a local installation of Python with the correct dependencies is the number one friction when using xlwings. Most excitingly though, xlwings Server adds support for the web-based spreadsheets: Google Sheets and Excel on the web.

To automate Office on the web, you have to use Office Scripts (i.e., TypeScript, a typed superset of JavaScript) and for Google Sheets, you have to use Apps Script (i.e., JavaScript). If you don't feel like learning JavaScript, xlwings allows you to write Python code instead. But even if you are comfortable with JavaScript, you are very limited in what you can do, as both Office Scripts and Apps Script are primarily designed to automate simple spreadsheet tasks such as inserting a new sheet or formatting cells rather than performing data-intensive tasks. They also make it very hard/impossible to use external JavaScript libraries and run in environments with minimal resources.

Note: From here on, when I refer to the **xlwings JavaScript module**, I mean either the xlwings Apps Script module if you use Google Sheets or the xlwings Office Scripts module if you use Excel on the web.

On the other hand, xlwings Server brings you these advantages:

- **Work with the whole Python ecosystem:** including pandas, machine learning libraries, database packages, web scraping, boto (for AWS S3), etc. This makes xlwings a great alternative for Power

Query, which isn't currently available for Excel on the web or Google Sheets.

- **Leverage your existing development workflow:** use your favorite IDE/editor (local or cloud-based) with full Git support, allowing you to easily track changes, collaborate and perform code reviews. You can also write unit tests using `pytest`.
- **Remain in control of your data and code:** except for the data you expose in Excel or Google Sheets, everything stays on your server. This can include database passwords and other sensitive info such as customer data. There's also no need to give the Python code to end-users: the whole business logic with your secret sauce is protected on your own infrastructure.
- **Choose the right machine for the job:** whether that means using a GPU, a ton of CPU cores, lots of memory, or a gigantic hard disc. As long as Python runs on it, you can go from serverless functions as offered by the big cloud vendors all the way to a self-managed Kubernetes cluster under your desk (see [Production Deployment](#)).
- **Headache-free deployment and maintenance:** there's only one location (usually a Linux server) where your Python code lives and you can automate the whole deployment process with continuous integration pipelines like GitHub actions etc.
- **Cross-platform:** xlwings Server works with Google Sheets, Excel on the web and the Desktop apps of Excel on Windows and macOS.

29.2 Prerequisites

Excel Desktop

- At least xlwings 0.27.0
- Either the xlwings add-in installed or a workbook that has been set up in standalone mode

Google Sheets

- At least xlwings 0.27.0
- New sheets: no special requirements.
- Older sheets: make sure that Chrome V8 runtime is enabled under `Extensions > Apps Script > Project Settings > Enable Chrome V8 runtime`.

Excel on the web

- At least xlwings 0.27.0
- You need access to Excel on the web with the `Automate` tab enabled, i.e., access to Office Scripts. Note that Office Scripts currently requires OneDrive for Business or SharePoint (it's not available on the free office.com), see also [Office Scripts Requirements](#).
- The `fetch` command in Office Scripts must **not** be disabled by your Microsoft 365 administrator.

29.3 Introduction

xlwings Server consists of two parts:

- Backend: the Python part
- Frontend: the xlwings JavaScript module (for Google Sheets/Excel on the web) or the VBA code in the form of the add-in or standalone modules (Desktop Excel)

The backend exposes your Python functions by using a Python web framework. In more detail, you need to handle a POST request along these lines (the sample shows an excerpt that uses [FastAPI](#) as the web framework, but it works accordingly with any other web framework like Django or Flask):

```
@app.post("/hello")
def hello(data: dict = Body):
    # Instantiate a Book object with the deserialized request body
    book = xw.Book(json=data)

    # Use xlwings as usual
    sheet = book.sheets[0]
    sheet["A1"].value = 'Hello xlwings!'

    # Pass the following back as the response
    return book.json()
```

- For Desktop Excel, you can run the web server locally and call the respective function from VBA right away (given that you have the add-in installed).
- For the cloud-based spreadsheets, you have to run this on a web server that can be reached from Google Sheets or Excel on the web, and you have to paste the xlwings JavaScript module into the respective editor. How this all works, will be shown in detail under *Cloud-based development with Gitpod*.

The next section shows you how you can play around with the xlwings Server on your local desktop before we'll dive into developing against the cloud-based spreadsheets.

29.4 Local Development with Desktop Excel

The easiest way to try things out is to run the web server locally against your Desktop version of Excel. We're going to use [FastAPI](#) as our web framework. While you can use any web framework you like, no quickstart command exists for these yet, so you'd have to set up the boilerplate yourself.

Start by running the following command on a Terminal/Command Prompt. Feel free to replace `demo` with another project name and make sure to run this command in the desired directory:

```
$ xlwings quickstart demo --fastapi
```

This creates a folder called `demo` in the current directory with the following files:

```
app.py
demo.xlsm
main.py
requirements.txt
```

I would recommend you to create a virtual or Conda environment where you install the dependencies via `pip install -r requirements.txt`. In `app.py`, you'll find the FastAPI boilerplate code and in `main.py`, you'll find the `hello` function that is exposed under the `/hello` endpoint.

To run this server locally, run `python main.py` in your Terminal/Command Prompt or use your code editor/IDE's run button. You should see something along these lines:

```
$ python main.py
INFO:      Will watch for changes in these directories: ['/Users/fz/Dev/demo']
INFO:      Uvicorn running on http://127.0.0.1:8000 (Press CTRL+C to quit)
INFO:      Started reloader process [36073] using watchgod
INFO:      Started server process [36075]
INFO:      Waiting for application startup.
INFO:      Application startup complete.
```

Your web server is now listening, so let's open `demo.xlsm`, press `Alt+F11` to open the VBA editor, and in `Module1`, place your cursor somewhere inside the following function:

```
Sub SampleRemoteCall()
    RunRemotePython "http://127.0.0.1:8000/hello", apiKey:="DEVELOPMENT"
End Sub
```

Then hit `F5` to run the function—you should see `Hello xlwings!` in cell `A1` of the first sheet. To move this to production, you need to deploy the backend to a server, set a unique API key and adjust the `url/apiKey` in the `RunRemotePython` function accordingly, see [Production Deployment](#).

The next sections, however, show you how you can make this work with the Google Sheets and Excel on the web.

29.5 Cloud-based development with Gitpod

Using Gitpod is the easiest solution if you'd like to develop against either Google Sheets or Excel on the web.

If you want to have a development environment up and running in less than 5 minutes (even if you're new to web development), simply click the `Open in Gitpod` button to open a [sample project](#) in `Gitpod` (Gitpod is a cloud-based development environment with a generous free tier):

Opening the project in Gitpod will require you to sign in with your GitHub account. A few moments later, you should see an online version of VS Code. In the Terminal, it will ask you to paste the xlwings license key ([get a free trial key](#) if you want to try this out in a commercial context or use the `noncommercial` license key if your usage [qualifies as noncommercial](#)). Note that your browser will ask you for permission to paste. Once you confirm your license key by hitting `Enter`, the server will automatically start with everything properly

configured. You can then open the `app` directory and look at the `main.py` file, where you'll see the `hello` function. This is the function we're going to call from Google Sheets/Excel on the web in just a moment. The other file in this directory, `app.py` contains all the FastAPI boilerplate code. Let's leave this alone for a moment and look at the `js` folder instead. Open the file according to your platform:

Google Sheets

```
xlwings_google.js
```

Excel on the web

```
xlwings_excel.ts
```

Copy all the code, then switch to Google Sheets or Excel on the web, respectively, and continue as follows:

Google Sheets

Click on **Extensions > Apps Script**. This will open a separate browser tab and open a file called `Code.gs` with a function stub. Replace this function stub with the copied code from `xlwings_google.js` and click on the **Save** icon. Then hit the **Run** button (the `hello` function should be automatically selected in the dropdown to the right of it). If you run this the very first time, Google Sheets will ask you for the permissions it needs. Once approved, the script will run the `hello` function and write `Hello xlwings!` into cell A1.

To add a button to a sheet to run this function, switch from the Apps Script editor back to Google Sheets, click on **Insert > Drawing** and draw a rounded rectangle. After hitting **Save** and **Close**, the rectangle will appear on the sheet. Select it so that you can click on the 3 dots on the top right of the shape. Select **Assign Script** and write `hello` in the text box, then hit **OK**.

Excel on the web

In the **Automate** tab, click on **New Script**. This opens a code editor pane on the right-hand side with a function stub. Replace this function stub with the copied code from `xlwings_excel.ts`. Make sure to click on **Save script** before clicking on **Run**: the script will run the `hello` function and write `Hello xlwings!` into cell A1.

To run this script from a button, click on the 3 dots in the Office Scripts pane (above the script), then select **+ Add button**.

Any changes you make to the `hello` function in `app/main.py` in Gitpod are automatically saved and reloaded by the web server and will be reflected the next time you run the script from Google Sheets or Excel on the web.

To test out `yahoo`, the other function of the [sample project](#), replace `hello` with `yahoo` in the `runPython` function in the `xlwings` JavaScript module.

Note: While Excel on the web requires you to create a separate script with a function called `main` for each Python function, Google Sheets allows you to add multiple functions with any name.

Please note that clicking the Gitpod button gets you up and running quickly, but if you want to save your changes (i.e., commit them to Git), you should first fork the project on GitHub to your own account and open it by prepending `https://gitpod.io/#` to your GitHub URL instead of clicking the button (this works with GitLab and Bitbucket too). Or continue with the next section, which shows you how you can start a project from scratch on your local machine.

An alternative for Gitpod is [GitHub Codespaces](#), but unlike Gitpod, GitHub Codespaces only works with GitHub, has no free tier, and may not be available yet on your account.

29.6 Local Development with Google Sheets or Excel on the web

This section walks you through a local development workflow as an alternative to using Gitpod/GitHub Codespaces. What's making this a little harder than using a preconfigured online IDE like Gitpod is the fact that we need to expose our local web server to the internet for easy development.

As before, we're going to use [FastAPI](#) as our web framework. While you can use any web framework you like, no quickstart command exists for these yet, so you'd have to set up the boilerplate yourself. Let's start with the server before turning our attention to the client side (i.e, Google Sheets or Excel on the web).

29.6.1 Part I: Backend

Start a new quickstart project by running the following command on a Terminal/Command Prompt. Feel free to replace `demo` with another project name and make sure to run this command in the desired directory:

```
$ xlwings quickstart demo --fastapi
```

This creates a folder called `demo` in the current directory with a few files. Since we're using an online spreadsheet instead of the Desktop Excel, you can delete `demo.xlsm`, which should leave you with the following files:

```
main.py
app.py
requirements.txt
```

I would recommend you to create a virtual or Conda environment where you install the dependencies via `pip install -r requirements.txt`. In `app.py`, you'll find the FastAPI boilerplate code and in `main.py`, you'll find the `hello` function that is exposed under the `/hello` endpoint.

The application expects you to set the environment variable `XLWINGS_API_KEY` to a unique key in order to protect your application from unauthorized access. You should choose a strong random key, for example by running the following on a Terminal/Command Prompt: `python -c "import secrets; print(secrets.token_hex(32))"`. If you don't set an environment variable, it will use `DEVELOPMENT` as the API key (only use this for quick tests and never for production!).

To run this server locally, run `python main.py` in your Terminal/Command Prompt or use your code editor/IDE's run button. You should see something along these lines:

```
$ python main.py
INFO: Will watch for changes in these directories: ['/Users/fz/Dev/demo']
INFO: Uvicorn running on http://127.0.0.1:8000 (Press CTRL+C to quit)
INFO: Started reloader process [36073] using watchgod
INFO: Started server process [36075]
INFO: Waiting for application startup.
INFO: Application startup complete.
```

Your web server is now listening, however, to enable it to communicate with Google Sheets or Excel on the web, you need to expose the port used by your local server (port 8000 in your example) securely to the internet. There are many free and paid services available to help you do this. One of the more popular ones is [ngrok](#) whose free version will do the trick (for a list of ngrok alternatives, see [Awesome Tunneling](#)):

- [ngrok Installation](#)
- [ngrok Tutorial](#)

For the sake of this tutorial, let's assume you've installed ngrok, in which case you would run the following on your Terminal/Command Prompt to expose your local server to the public internet:

```
$ ngrok http 8000
```

Note that the number of the port (8000) has to correspond to the port that is configured on your local development server as specified at the bottom of `main.py`. ngrok will print something along these lines:

```
ngrok by @inconshreveable
      (Ctrl+C to quit)

Session Status      online
Account             name@domain.com (Plan: Free)
Version             2.3.40
Region              United States (us)
Web Interface       http://127.0.0.1:4040
Forwarding           http://xxxx-xxxx-xx-xx-xxx-xxxx-xxxx-xxxx-xxx.
ngrok.io -> http://localhost:8000
Forwarding           https://xxxx-xxxx-xx-xx-xxx-xxxx-xxxx-xxxx-xxx.
ngrok.io -> http://localhost:8000
```

To configure the xlwings client in the next step, we'll need the `https` version of the Forwarding address that ngrok prints, i.e., `https://xxxx-xxxx-xx-xx-xxx-xxxx-xxxx-xxxx-xxx.ngrok.io`.

Note: When you're not actively developing, you should stop your ngrok session by hitting `Ctrl-C` in the Terminal/Command Prompt.

29.6.2 Part II: Frontend

Now it's time to switch to Google Sheets or Excel on the web! To paste the xlwings JavaScript module, follow these 3 steps:

1. **Copy the xlwings JavaScript module:** On a Terminal/Command Prompt on your local machine, run the following command:

Google Sheets

```
$ xlwings copy gs
```

Excel on the web

```
$ xlwings copy os
```

This will copy the correct xlwings JavaScript module to the clipboard so we can paste it in the next step.

2. **Paste the xlwings JavaScript module**

Google Sheets

Click on **Extensions > Apps Script**. This will open a separate browser tab and open a file called `Code.gs` with a function stub. Replace this function stub with the copied code from the previous step and click on the **Save** icon. Then hit the **Run** button (the `hello` function should be automatically selected in the dropdown to the right of it). If you run this the very first time, Google Sheets will ask you for the permissions it needs. Once approved, the script will run the `hello` function and write **Hello xlwings!** into cell A1.

To add a button to a sheet to run this function, switch from the Apps Script editor back to Google Sheets, click on **Insert > Drawing** and draw a rounded rectangle. After hitting **Save** and **Close**, the rectangle will appear on the sheet. Select it so that you can click on the 3 dots on the top right of the shape. Select **Assign Script** and write `hello` in the text box, then hit **OK**.

Excel on the web

In the **Automate** tab, click on **New Script**. This opens a code editor pane on the right-hand side with a function stub. Replace this function stub with the copied code from the previous step. Make sure to click on **Save script** before clicking on **Run**: the script will run the `hello` function and write **Hello xlwings!** into cell A1.

To run this script from a button, click on the 3 dots in the Office Scripts pane (above the script), then select **+ Add button**.

3. **Configuration:** The final step is to configure the xlwings JavaScript module properly, see the next section [Configuration](#).

29.7 Configuration

xlwings can be configured in two ways:

- Via arguments in the `runPython` (Google Sheets or Excel on the web) or `RunRemotePython` (Desktop Excel) function, respectively.
- Via `xlwings.conf` sheet (in this case, the keys are UPPER_CASE with underscore instead of camel-Case, see the screenshot below).

If you provide a value via config sheet and via function argument, the function argument wins. Let's see what the available settings are:

- `url` (required): This is the full URL of your function. In the above example under *Local Development with Google Sheets or Excel on the web*, this would be `https://xxxx-xxxx-xx-xx-xxx-xxxx-xxxx-xxx.ngrok.io/hello`, i.e., the ngrok URL **with the /hello endpoint appended**.
- `apiKey` (optional): While this is technically optional, it is usually required by the backend. It has to correspond to whatever you set the `XLWINGS_API_KEY` environment variable on your server and will protect your functions from unauthorized access. It's good practice to keep your sensitive keys such as the `apiKey` out of your source code (the JavaScript/VBA module), but putting it in the `xlwings.conf` sheet may only be marginally better. Excel on the web, however, doesn't currently provide you with a better way of handling this. Google Sheets, on the other hand, allows you to work with [Properties Service](#) to keep the API key out of both the JavaScript code and the `xlwings.conf` sheet.

Note: The API key is chosen by you to protect your application and has nothing to do with the xlwings license key!

- `headers` (optional): A dictionary (VBA) or object literal (JS) with name/value pairs. If you set the `Authorization` header, `apiKey` will be ignored.
- `exclude` (optional): By default, xlwings sends over the complete content of the whole workbook to the server. If you have sheets with big amounts of data, this can make the calls slow or you could even hit a timeout. If your backend doesn't need the content of certain sheets, you can exclude them from being sent over via this setting. Currently, you can only exclude entire sheets as comma-delimited string like so: `"Sheet1, Sheet2"`.
- `include` (optional): It's the counterpart to `exclude` and allows you to submit the names of the sheets that you want to send to the server. Like `exclude`, `include` accepts a comma-delimited string, e.g., `"Sheet1, Sheet2"`.

29.7.1 Configuration Examples: Function Arguments

Excel Desktop

Using only required arguments:

```
Sub Hello()  
    RunRemotePython "http://127.0.0.1:8000/hello", apiKey:="YOUR_UNIQUE_API_KEY"  
End Sub
```

Additionally providing the `exclude` parameter to exclude the content of the `xlwings.conf` and `Sheet1` sheets:

```
Sub Hello()  
    RunRemotePython "http://127.0.0.1:8000/hello", apiKey:="YOUR_UNIQUE_API_KEY",  
    ↪ exclude:="xlwings.conf, Sheet1"  
End Sub
```

Google Sheets

Using only required arguments:

```
function hello() {  
    runPython("https://xxxx-xxxx-xx-xx-xxx-xxxx-xxxx-xxxx-xxx.ngrok.io/hello", {  
        apiKey: "YOUR_UNIQUE_API_KEY",  
    });  
}
```

Additionally providing the `exclude` parameter to exclude the content of the `xlwings.conf` and `Sheet1` sheets as well as a custom header:

```
function hello() {  
    runPython("https://xxxx-xxxx-xx-xx-xxx-xxxx-xxxx-xxxx-xxx.ngrok.io/hello", {  
        apiKey: "YOUR_UNIQUE_API_KEY",  
        exclude: "xlwings.conf, Sheet1",  
        headers: { MyHeader: "my value" },  
    });  
}
```

Excel on the web

Using only required arguments:

```
async function main(workbook: ExcelScript.Workbook) {
  await runPython(
    workbook,
    "https://xxxx-xxxx-xx-xx-xxx-xxxx-xxxx-xxxx-xxx.ngrok.io/hello",
    { apiKey: "YOUR_UNIQUE_API_KEY" }
  );
}
```

Additionally providing the `exclude` parameter to exclude the content of the `xlwings.conf` and `Sheet1` sheets as well as a custom header:

```
async function main(workbook: ExcelScript.Workbook) {
  await runPython(
    workbook,
    "https://xxxx-xxxx-xx-xx-xxx-xxxx-xxxx-xxxx-xxx.ngrok.io/hello",
    {
      apiKey: "YOUR_UNIQUE_API_KEY",
      exclude: "xlwings.conf, Sheet1",
      headers: { MyHeader: "my value" },
    }
  );
}
```

29.7.2 Configuration Examples: xlwings.conf sheet

Create a sheet called `xlwings.conf` and fill in key/value pairs like so:

	A	B	C	D	E	F
1	API_KEY	4bd5b65497e41f7a85006fdf23a1fb0e73353ffd7b1c9				
2	EXCLUDE	Sheet1, xlwings.conf				
3						
4						
5						
6						

<
>
≡
Sheet1
xlwings.conf
+

29.8 Production Deployment

The xlwings web server can be built with any web framework and can therefore be deployed using any solution capable of running a Python backend or function. Here is a list for inspiration (non-exhaustive):

- **Fully-managed services:** [Heroku](#), [render](#), [Fly.io](#), etc.
- **Interactive environments:** [PythonAnywhere](#), [Anvil](#), etc.
- **Serverless functions:** [AWS Lambda](#), [Azure Functions](#), [Google Cloud Functions](#), [Vercel](#), etc.
- **Virtual Machines:** [DigitalOcean](#) (referral link), [vultr](#) (referral link), [Linode](#), [AWS EC2](#), [Microsoft Azure VM](#), [Google Cloud Compute Engine](#), etc.
- **Corporate servers:** Anything will work (including Kubernetes) as long as the respective endpoints can be accessed from your spreadsheet app.

Important: For production deployment, always make sure to set a unique and random API key, see [Configuration](#).

If you'd like to deploy the [sample project](#) to production in less than 5 minutes, you can do so by clicking the button below, which will deploy it to Heroku's free tier. Note, however, that on the free plan, the backend will "sleep" after 30 minutes of inactivity, which means that it will take a few moments the next time you call it until it is up and running again. The `XLWINGS_API_KEY` is auto-generated and you can look it up under your app's Settings > Config Vars > Reveal Config Vars once the app is deployed. To get the URL, you'll need to append `/hello` to the app's URL that you'll find in your dashboard.

29.9 Triggers

Google Sheets

For Google Sheets, you can take advantage of the integrated Triggers (accessible from the menu on the left-hand side of the Apps Script editor). You can trigger your xlwings functions on a schedule or by an event, such as opening or editing a sheet.

Excel on the web

Normally, you would use Power Automate to achieve similar things as with Google Sheets Triggers, but unfortunately, Power Automate can't run Office Scripts that contain a `fetch` command like xlwings does, so for the time being, you can only trigger xlwings calls manually on Excel on the web. Alternatively, you can open your Excel file with Google Sheets and leverage the Triggers that Google Sheets offers. This, however, requires you to store your Excel file on Google Drive.

29.10 Limitations

- Currently, only a subset of the xlwings API is covered, mainly the Range and Sheet classes with a focus on reading and writing values and sending pictures (including Matplotlib plots). This, however, includes full support for type conversion including pandas DataFrames, NumPy arrays, datetime objects, etc.
- You are moving within the web's request/response cycle, meaning that values that you write to a range will only be written back to Google Sheets/Excel once the function call returns. Put differently, you'll get the state of the sheets at the moment the call was initiated, but you can't read from a cell you've just written to until the next call.
- You will need to use the same xlwings version for the Python package and the JavaScript module, otherwise, the server will raise an error.
- Currently, custom functions (a.k.a. user-defined functions or UDFs) are not supported.
- For users with no experience in web development, this documentation may not be quite good enough just yet.

Platform-specific limitations:

Google Sheets

- [Quotas for Google Services](#) apply.

Excel on the web

- xlwings relies on the `fetch` command in Office Scripts that cannot be used via Power Automate and that can be disabled by your Microsoft 365 administrator.
- While Excel on the web feels generally slow, it seems to have an extreme lag depending on where in the world you open the browser with Excel on the web. For example, a hello world call takes ~4.5s if you open a browser in Amsterdam/Netherlands while it takes ~8.5s if you do it Buenos Aires/Argentina.
- [Platform limits with Office Scripts](#) apply.

29.11 Roadmap

- Complete the RunPython API by adding features that currently aren't supported yet, e.g., charts, shapes, names collections, tables, etc.
- Add support for UDFs/custom functions.
- Improve efficiency.

WHAT'S NEW

30.1 v0.28.4 (Oct 29, 2022)

- Enhancement Added possibility to install the add-in globally for all users via `xlwings addin install -g` ([GH2075](#)).
- Enhancement Added `App.path` property ([GH2074](#)).
- Enhancement Build wheels for Python 3.11 ([GH2071](#)).

30.2 v0.28.3 (Oct 21, 2022)

- Bug Fix PRO xlwings File Reader: To be in line with the rest of the API, integers are now delivered as floats ([GH2066](#)).
- Bug Fix PRO xlwings File Reader: Fixed a bug that sometimes read in incorrect decimals with the legacy `xls` file formats ([GH2062](#)).
- Bug Fix PRO Fixed a bug introduced with 0.28.1 when `xlwings code embed` was run with the `--file` flag and a relative path ([GH2061](#)).

30.3 v0.28.2 (Oct 17, 2022)

- Breaking Change PRO xlwings File Reader: The reader was including `Chartsheets` etc. in `mybook.sheets`, which was inconsistent with the rest of the API. Accordingly, it now only shows `Worksheets` ([GH2058](#)).
- Bug Fix PRO xlwings File Reader: With `xlsb` formats, slightly unusual defined names caused the reader to fail ([GH2057](#)).
- Enhancement PRO xlwings Reports: the imports have been flattened. What previously was available via `xlwings.pro.reports` is now also available via `xlwings.reports` ([GH2055](#)).
- Enhancement PRO xlwings Reports: the registration of formatters for use with templates has been simplified by allowing you to use the `@formatter` decorator instead of having to register the function via `register_formatter(myfunc)` ([GH2055](#)).

30.4 v0.28.1 (Oct 10, 2022)

- Feature You can now use formatters to format the data you write to Excel or Google Sheets in a very flexible manner (see also *Default Converter*):

```
import pandas as pd
import xlwings as xw

sheet = xw.Book().sheets[0]

def table(rng: xw.Range, df: pd.DataFrame):
    """This is the formatter function"""
    # Header
    rng[0, :].color = "#A9D08E"

    # Rows
    for ix, row in enumerate(rng.rows[1:]):
        if ix % 2 == 0:
            row.color = "#D0CECE" # Even rows

    # Columns
    for ix, col in enumerate(df.columns):
        if "two" in col:
            rng[1:, ix].number_format = "0.0%"

df = pd.DataFrame(data={"one": [1, 2, 3, 4], "two": [5, 6, 7, 8]})
sheet["A1"].options(formatter=table, index=False).value = df
```

	A	B
1	one	two
2	1	500.0%
3	2	600.0%
4	3	700.0%
5	4	800.0%

- Feature PRO Formatters are also available for xlwings Reports via filters: `{{ df | formatter("myformatter") }}`, see *DataFrames Filters*.
- Feature You can now export a sheet to an HTML page via `mysheet.to_html()`
- Feature New convenience property to get a list of the sheet names: `mybook.sheet_names`

- Enhancement PRO The Excel File Reader now supports the Names collection. I.e., you can now run code like this:

```
with xw.Book("myfile.xlsx", mode="r") as book:
    for name in book.names:
        print(name.refers_to_range.value)
```

- Enhancement PRO Code embedding via `xlwings release` or `xlwings code embed` now allows you to work with Python packages, i.e., nested directories.

30.5 v0.28.0 (Oct 4, 2022)

- Feature PRO xlwings PRO adds an ultra fast file reader, allowing you to read Excel files much faster than via `pandas.read_excel()`:

```
with xw.Book("myfile.xlsx", mode="r") as book:
    sheet1 = book.sheets[0]
    df = sheet1["A1:B2"].options("df", index=False).value
```

For all the details, see *Excel File Reader*.

- Enhancement Book can now be used as context manager (i.e., with the `with` statement, see previous bullet point), which will close the book automatically when leaving the body of the `with` statement.
- Enhancement The new option `err_to_str` allows you to deliver cell errors like #N/A as strings instead of None (default): `xw.Book("mybook.xlsx").options(err_to_str=True).value`.
- Breaking Change PRO xlwings Server used to deliver cell errors as strings, which wasn't consistent with the rest of xlwings. This has now been fixed by delivering them as None by default. To get the previous behavior, use the `err_to_str` option, see the previous bullet point.
- Enhancement PRO The *Remote Interpreter* has been rebranded to *xlwings Server*.

30.6 v0.27.15 (Sep 16, 2022)

- Enhancement PRO Reports: Added new `vmerge` filter to vertically merge cells with the same values, for details, see *vmerge* (GH2020).

30.7 v0.27.14 (Aug 26, 2022)

- Enhancement Allow to install/remove the addin via `xlwings addin install` while Excel is running (GH1999).

30.8 v0.27.13 (Aug 22, 2022)

- Feature Add support for alerts: `myapp.alert("Hello World")`, see `myapp.alert()` for more details (GH756).
- Enhancement Handle Timedelta dtypes in pandas DataFrames and Series (GH1991).
- Enhancement PRO Remove the cryptography dependency from xlwings PRO (GH1992).

30.9 v0.27.12 (Aug 8, 2022)

- Enhancement PRO: xlwings Server: added support for named ranges via `mysheet["myname"]` or `mysheet.range("myname")` (GH1975).
- Enhancement PRO: xlwings Server: in addition to Google Sheets, `pictures.add()` is now also supported on Desktop Excel (Windows and macOS). This includes support for Matplotlib plots (GH1974).
- Enhancement Faster UDFs (GH1976).
- Bug Fix Made `myapp.range()` behave the same as `mysheet.range()` (GH1982).
- Bug Fix PRO: xlwings Server: cell errors were causing a bug with Desktop Excel (GH1968).
- Bug Fix PRO: xlwings Server: sending large payloads with Desktop Excel on macOS is now possible (GH1977).

30.10 v0.27.11 (Jul 6, 2022)

- Enhancement Added support for pandas `pd.NA` (GH1939).
- Bug Fix Empty cells in UDFs are now properly returned as `None` / `NaN` instead of an empty string (GH1947).
- Bug Fix Resolved an issue with OneDrive/SharePoint files that are unsynced locally (GH1946).

30.11 v0.27.10 (Jun 8, 2022)

- Bug Fix PRO This release fixes a `FileNotFound` error that could sometimes happen with embedded code (GH1931).

30.12 v0.27.9 (Jun 4, 2022)

- Bug Fix Fixes a bug on Windows that caused an Excel Zombie process with `pywin32 > v301` ([GH1929](#)).

30.13 v0.27.8 (May 22, 2022)

- Enhancement Smarter shrinking of Excel tables when using `mytable.update(df)` as it doesn't delete rows below the table anymore ([GH1908](#)).
- Bug Fix Fixed a regression when `RunPython` was used with `Use UDF Server = True` (introduced in v0.26.2) ([GH1912](#)).
- Bug Fix PRO The `xlwings release` command would sometimes incorrectly show a version mismatch error ([GH1918](#)).
- Bug Fix PRO `xlwings Reports` now raises an explicit error when Jinja2 is missing ([GH1637](#)).

30.14 v0.27.7 (May 1, 2022)

- Feature PRO Google Sheets now support pictures via `mysheet.pictures.add()` incl. Matplotlib/Plotly (note that Excel on the web and Desktop Excel via `xlwings Server` are not yet supported). Also note that Google Sheets allows a maximum of 1 million pixels as calculated by $(\text{width in inches} * \text{dpi}) * (\text{height in inches} * \text{dpi})$, see also *Matplotlib & Plotly Charts* ([GH1906](#)).
- Breaking Change Matplotlib plots are now written to Excel/Google Sheets with a default of 200 dpi instead of 300 dpi. You can change this (and all other options that Matplotlib's `savefig()` and Plotly's `write_image()` offer via `sheet.pictures.add(image=myfigure, export_options={"bbox_inches": "tight", "dpi": 300})` ([GH665](#), [GH519](#)).

30.15 v0.27.6 (Apr 11, 2022)

- Bug Fix macOS: Python modules on OneDrive Personal are now found again in the default setup even if they have been migrated to the new location ([GH1891](#)).
- Enhancement PRO `xlwings Server` now shows nicely formatted error messages across all platforms ([GH1889](#)).

30.16 v0.27.5 (Apr 1, 2022)

- Enhancement PRO xlwings Server: added support for setting the number format of a range via `myrange.number_format = "..."` (GH1887).
- Bug Fix PRO xlwings Server: Google Sheets/Excel on the web were formatting strings like "1" as date (GH1885).

30.17 v0.27.4 (Mar 29, 2022)

- Enhancement Further SharePoint enhancements on Windows, increasing the chance that `mybook.fullname` returns the proper local filepath (by taking into account the info in the registry) (GH1829).
- Enhancement The ribbon, i.e., the config, now allows you to uncheck the box `Add workbook to PYTHONPATH` to not automatically add the directory of your workbook to the `PYTHONPATH`. The respective config is called `ADD_WORKBOOK_TO_PYTHONPATH`. This can be helpful if you experience issues with OneDrive/SharePoint: uncheck this box and provide the path where your source file is manually via the `PYTHONPATH` setting (GH1873).
- Enhancement PRO Added support for `myrange.add_hyperlink()` with remote interpreter (GH1882).
- Enhancement PRO Added a new optional parameter `include` in connection with `runPython` (JS) and `RunRemotePython` (VBA), respectively. It's the counterpart to `exclude` and allows you to submit the names of the sheets that you want to send to the server. Like `exclude`, `include` accepts a comma-delimited string, e.g., "Sheet1,Sheet2" (GH1882).
- Enhancement PRO On Google Sheets, the xlwings JS module now automatically asks for the proper permission to allow authentication based on OAuth Token (GH1876).

30.18 v0.27.3 (Mar 18, 2022)

- Bug Fix PRO Fixes an issue with Date formatting on Google Sheets in case you're not using the U.S. locale (GH1866).
- Bug Fix PRO Fixes the truncating of ranges with xlwings Server in case the range was partly outside the used range (GH1822).

30.19 v0.27.2 (Mar 11, 2022)

- Bug Fix PRO Fixes an issue with xlwings Server that occurred on 64-bit versions of Excel.

30.20 v0.27.0 and v0.27.1 (Mar 8, 2022)

- Feature PRO This release adds support for xlwings Server to the Excel Desktop apps on both Windows and macOS. The new VBA function `RunRemotePython` is equivalent to `runPython` in the JavaScript modules of Google Sheets and Excel on the web, see *xlwings Server* (GH1841).
- Enhancement The xlwings package is now uploaded as wheel to PyPI in addition to the source format (GH1855).
- Enhancement The xlwings package is now compatible with Poetry (GH1265).
- Enhancement The add-in and the dll files are now code signed (GH1848).
- Breaking Change PRO The JavaScript modules (Google Sheet/Excel on the web) changed the parameters in `runPython`, see *xlwings Server* (GH1852).
- Breaking Change xlwings `vba edit` has been refactored and there is an additional command `xlwings vba import` to edit your VBA code outside of the VBA editor, e.g., in VS Code or any other editor, see *Command Line Client (CLI)* (GH1843).
- Breaking Change The `--unprotected` flag has been removed from the `xlwings addin install` command. You can still manually remove the password (xlwings) though (GH1850).
- Bug Fix PRO The Markdown class has been fixed in case the first line was empty (GH1856).
- Bug Fix PRO 0.27.1 fixes an issue with the version string in the new `RunRemotePython` VBA call (GH1859).

30.21 v0.26.3 (Feb 19, 2022)

- Feature If you still have to write VBA code, you can now use the new CLI command `xlwings vba edit`: this will export all the VBA modules locally so that you can edit them with any editor like e.g., VS Code. Every local change is synced back whenever you save the local file, see *Command Line Client (CLI)* (GH1839).
- Enhancement PRO The permissioning feature now allows you to send an Authorization header via the new `PERMISSION_CHECK_AUTHORIZATION` setting (GH1840).

30.22 v0.26.2 (Feb 10, 2022)

- Feature Added support for `myrange.clear_formats` and `mysheet.clear_formats` (GH1802).
- Feature Added support for `mychart.to_pdf()` and `myrange.to_pdf()` (GH1708).
- Feature PRO xlwings Server: added support for `mybook.selection` (GH1819).
- Enhancement The `quickstart` command now makes sure that the project name is a valid Python module name (GH1773).
- Enhancement The `to_pdf` method now accepts an additional parameter `quality` that defaults to "standard" but can be set to "minimum" for smaller PDFs (GH1697).

- Bug Fix Allow space in path to Python interpreter when using UDFs / UDF Server ([GH974](#)).
- Bug Fix A few issues were fixed in case your files are synced with OneDrive or SharePoint ([GH1813](#) and [GH1810](#)).
- Bug Fix PRO Reports: fixed the `aggsmall` filter to work without the optional `min_rows` parameter ([GH1824](#)).

30.23 v0.26.0 and v0.26.1 (Feb 1, 2022)

- PRO Feature Added experimental support for Google Sheets and Excel on the web via a remote Python interpreter. For all the details, see *xlwings Server*.
- PRO Bug Fix 0.26.1 fixes an issue with the `xlwings copy gs` command.
- xlwings PRO is now free for noncommercial usage under the [PolyForm Noncommercial License 1.0.0](#), see *xlwings PRO* for the details.

30.24 v0.25.3 (Dec 16, 2021)

- PRO Bug Fix The xlwings Reports filters `aggsmall` and `maxrows` don't fail with empty DataFrames anymore ([GH1788](#)).

30.25 v0.25.2 (Dec 3, 2021)

- PRO Enhancement xlwings Reports now ignores sheets whose name start with `##` for both rendering and printing to PDF ([GH1779](#)).
- PRO Enhancement The `aggsmall` filter in xlwings Reports now accepts a new parameter `min_rows` ([GH1780](#)).

30.26 v0.25.1 (Nov 21, 2021)

- Enhancement `mybook.save()` now supports the `password` parameter ([GH1568](#)).
- PRO Bug Fix xlwings Reports would sometimes cause a `Could not activate App instance error` ([GH1764](#)).
- PRO Enhancement xlwings now warns about expiring developer license keys 30 days before they expire ([GH1758](#)).

30.27 v0.25.0 (Oct 27, 2021)

- Bug Fix Finally, xlwings adds proper support for OneDrive, OneDrive for Business, and SharePoint. This means that the `quickstart` setup (Excel file and Python file in the same folder with the same name) works even if the files are stored on OneDrive/SharePoint—as long as they are being synced locally. It also makes `mybook.fullname` return the local file path instead of a URL. Sometimes, this requires editing the configuration, see: [OneDrive and SharePoint](#) for the details (GH1630).
- Feature The `update()` method of Excel tables has been moved from PRO to open source. You can now easily update an existing table in Excel with the data from a new pandas DataFrame without messing up any formulas that reference that table: `mytable.update(df)`, see: [Table.update\(\)](#) (GH1751).
- PRO Breaking Change: Reports: `create_report()` is now deprecated in favor of `render_template()` that is available via `app`, `book` (new), and `sheet` objects, see: [xlwings Reports PRO](#) (GH1738).
- Bug Fix Running UDFs from other Office apps has been fixed (GH1729).
- Bug Fix Writing to a protected sheet or using an invalid sheet name etc. caused xlwings to hang instead of raising an Exception (GH1725).

30.28 v0.24.9 (Aug 26, 2021)

- Bug Fix Fixed a regression introduced with 0.24.8 that was causing an error with pandas DataFrames that have repeated column headers (GH1711).

30.29 v0.24.8 (Aug 25, 2021)

- Feature New methods `mychart.to_png()`, `myrange.to_png()` and `myrange.copy_picture()` (GH1707 and GH582).
- Enhancement You can now use the alias `'df'` to convert to a pandas DataFrame: `mysheet['A1:C3'].options('df').value` is equivalent to `import pandas as pd; mysheet['A1:C3'].options(pd.DataFrame).value` (GH1533).
- Enhancement Added `--dir` option to `xlwings addin install` to allow the installation of all files in a directory as add-ins (GH1702).
- Bug Fix Pandas DataFrames now properly work with `PeriodIndex` / `PeriodDtype` (GH1084).
- PRO Reports: If there's just one Frame, keep height of rows (GH1698).

30.30 v0.24.7 (Aug 5, 2021)

- PRO Breaking Change: Reports: Changed the order of the arguments of the arithmetic DataFrame filters: `sum`, `div`, `mul` and `div` to align them with the other filters. E.g., to multiply column 2 by 100, you now have to write your filter as `{{ df | mul(100, 2) }}` (GH1696).
- PRO Bug Fix Reports: Fixed an issue with images when pillow wasn't installed (GH1695).

30.31 v0.24.6 (Jul 31, 2021)

- Enhancement You can now also define the color of cells, shapes and font objects with a hex string instead of just an RGB tuple, e.g., `mysheet["A1"].color = "#efefef"` (GH1535).
- Enhancement When you print a workbook or sheet to a pdf, you can now automatically open the PDF document via the new `show` argument: `mybook.to_pdf(show=True)` (GH1683).
- Bug Fix: This release includes another round of fixing the cleanup actions of the `App()` context manager (GH1687).
- PRO Enhancement Reports: New filter `fontcolor`, allowing you to write text in black and turn it into e.g., white for the report. This gets around the issue that white text isn't visible in Excel on a white background: `{{ myplaceholder | fontcolor("white") }}`. Alternatively, you can also use a hex color (GH1692).
- PRO Bug Fix Positioning shapes wasn't always respecting the top/left filters (GH1687).
- PRO Bug Fix Fixed a bug with non-string headers when calling `table.update` (GH1687).

30.32 v0.24.5 (Jul 27, 2021)

- PRO Bug Fix Reports: Using the header filter in a Frame was causing rows to be inserted (GH1681).

30.33 v0.24.4 (Jul 26, 2021)

- Feature `myapp.properties` is a new context manager that allows you to easily change the app's properties temporarily. Once the code leaves the `with` block, the properties are changed back to their previous state (GH254). For example:

```
import xlwings as xw
app = App()

with app.properties(display_alerts=False):
    # Alerts are disabled until you leave the with block again
```

- Enhancement The app properties `myapp.enable_events` and `myapp.interactive` are now supported (GH254).

- Enhancement `mybook.to_pdf` now ignores sheet names that start with a `#`. This can be changed by setting the new parameter `exclude_start_string` (GH1667).
- Enhancement New method `mytable.resize()` (GH1662).
- Bug Fix The new App context manager introduced with v0.24.3 was sometimes causing an error on Windows during the cleanup actions (GH1668).

PRO `xlwings.pro.reports`:

- Breaking Change: DataFrame placeholders will now ignore the DataFrame's index. If you need the index, reset it via `df.reset_index()` before passing the DataFrame to `create_report` or `render_template`. This was required as the same column index used in filters would point to seemingly different columns in Excel depending on whether the index was included or not. This also means that the `noindex` and `body` filters are no obsolete and have been removed (GH1676).
- Enhancement DataFrame filters now respect the order in which they are called and can be used multiple times (GH1675).
- Enhancement New filters: `format` (to apply f-string like formatting), `datetime` (to format datetime objects), `top` and `left` (to position graphics outside of the grid structure) `header`, `add`, `sub`, `mul`, `div` (to only return the header of a DataFrame or apply an arithmetic operation, respectively) (GH1666, GH1660, GH1677).
- Enhancement: `create_report` can now be accessed as method of the app object like so: `myapp.create_report` (GH1665).
- Bug Fix: Excel tables that had the Header Row unchecked were sometimes causing row shifts in the template (GH1663).
- Bug Fix: Rendering a template was sometimes causing the following error `PasteSpecial` method of `Range` class failed (GH1672).

30.34 v0.24.3 (Jul 15, 2021)

- Enhancement `xlwings.App()` can now be used as context manager, making sure that there are no zombie processes left over on Windows, even if you use a hidden instance and your code fails. It is therefore recommended to use it whenever you can, like so:

```
with xw.App(visible=True) as app:
    print(app.books)
```

- Enhancement `mysheet.pictures.add` now accepts a new `anchor` argument that you can use as an alternative to `top/left` to position the picture by providing an anchor range object, e.g.: `mysheet.pictures.add(img, anchor=mysheet['A1'])` (GH1648).
- Bug Fix macOS: Plots are now sent to Excel in PDF format when you set `format='vector'` which is supporting transparency unlike the previously used `eps` format (GH1647).
- PRO Enhancement `mybook.to_pdf` now accepts a `layout` parameter so you can “print” your reports onto a PDF with your corporate layout including headers, footers and borderless graphics. See [PDF Layout](#).

30.35 v0.24.2 (Jul 6, 2021)

- Feature Added very basic support for `mysheet.page_setup` and `myrange.note` (GH1551 and GH896).
- Enhancement DataFrames are now displayed in Excel tables with empty column names if the DataFrame doesn't have a column or index name. This effect is e.g. visible when using `xw.view()` (GH1643).
- Enhancement `mysheet.pictures.add()` now supports `format='vector'` which translates to 'svg' on Windows and 'eps' on macOS (GH1640).
- PRO Enhancement: The reports package now offers the additional DataFrame filters `rowslice` and `colslice`, see *xlwings Reports* (GH1645).
- PRO Bug Fix: Bug fix with handling Excel tables without headers.

Breaking Change

- PRO Enhancement: `<frame>` markers now have to be defined as cell notes in the first row, see *Frames: Multi-column Layout*. This has the advantage that the Layout view corresponds to the print view (GH1641). Also, the print area is now preserved even if you use Frames.

30.36 v0.24.1 (Jun 27, 2021)

- PRO Enhancement: The reports package now offers the additional DataFrame filters `head` and `tail`, see *xlwings Reports* (GH1633).

30.37 v0.24.0 (Jun 25, 2021)

- Enhancement `pictures.add()` now accepts every picture format (including vector-based formats) that your Excel version supports. For example, on Windows you can use the `svg` format (only supported with Excel that comes with Microsoft 365) and on macOS, you can use `eps` (GH1624).
- [Enhancements] Support for Plotly images was moved from PRO to the Open Source version, i.e. you can now provide a Plotly image directly to `pictures.add()`.
- Enhancement Matplotlib and Plotly plots can now be sent to Excel in a vector-based format by providing the `format` argument, e.g. `svg` on Windows or `eps` on macOS.
- Enhancement Removed dependency on pillow/PIL to properly size images via `pictures.add()`.
- Bug Fix Various fixes with scaling and positioning images via `pictures.add()` (GH1491).
- Feature New methods `mypicture.lock_aspect_ratio` and `myapp.cut_copy_mode` (GH1622 and GH1625).
- PRO Feature: Reports: DataFrames and Images are now offering various filters to influence the behavior of how DataFrames and Images are displayed, giving the template designer the ability to change a lot of things that previously had to be taken care of by the Python developer. For example, to hide a

DataFrame's index, you can now do `{{ df | noindex }}` or to scale the image to double its size, you can do `{{ img | scale(2) }}`. You'll find all available filters under *xlwings Reports* (GH1602).

Breaking Change

- Enhancement: When using `pictures.add()`, pictures arrive now in Excel in the same size as if you would manually add them via the Excel UI and setting width/height now behaves consistently during initial adding and resizing. Consequently, you may have to fix your image sizes when you upgrade. (GH1491).
- PRO The default MarkdownStyle removed the empty space after a h1 heading. You can always reintroduce it by applying a custom style (GH1628).

30.38 v0.23.4 (Jun 15, 2021)

- Bug Fix Windows: Fixed the ImportUDFs function in the VBA standalone module (GH1601).
- Bug Fix Fixed configuration hierarchy: if you have a setting with an empty value in the `xlwings.conf` sheet, it will not be overridden by the same key in the directory or user config file anymore. If you wanted it to be overridden, you'd have to get the key out of the "xlwings.conf" sheet (GH1617).
- PRO Feature Added the ability to block the execution of Python modules based on the file hash and/or machine name (GH1586), see *Permissioning PRO*.
- PRO Feature Added the `xlwings release` command for an easy release management in connection with the one-click installer, see *1-click installer PRO*. (GH1429).

30.39 v0.23.3 (May 17, 2021)

- Bug Fix Windows: UDFs returning a `pandas.NaT` were causing a `#VALUE!` error (GH1590).

30.40 v0.23.2 (May 7, 2021)

- Feature Added support for `myrange.wrap_text` (GH173).
- Enhancement `xlwings.view()` and `xlwings.load()` now use chunking by default (GH1570).
- Bug Fix Allow to save non-Excel file formats (GH1569)
- Bug Fix Calculate formulas by default in the Function Wizard (GH1574).
- PRO Bug Fix Properly embed code with unicode characters (GH1575).

30.41 v0.23.1 (Apr 19, 2021)

- Feature You can now save your workbook in any format you want, simply by specifying its extension:

```
mybook.save('binaryfile.xlsb')
mybook.save('macroenabled.xlsm')
```

- Feature Added support for the `chunksize` option: when you read and write from or to big ranges, you may have to chunk them or you will hit a timeout or a memory error. The ideal `chunksize` will depend on your system and size of the array, so you will have to try out a few different chunksizes to find one that works well ([GH77](#)):

```
import pandas as pd
import numpy as np
sheet = xw.Book().sheets[0]
data = np.arange(75_000 * 20).reshape(75_000, 20)
df = pd.DataFrame(data=data)
sheet['A1'].options(chunksize=10_000).value = df
```

And the same for reading:

```
# As DataFrame
df = sheet['A1'].expand().options(pd.DataFrame, chunksize=10_000).value
# As list of list
df = sheet['A1'].expand().options(chunksize=10_000).value
```

- Enhancement `xw.load()` now expands to the `current_region` instead of relying on `expand()` ([GH1565](#)).
- Enhancement The OneDrive setting has been split up into a Windows and macOS-specific paths: `ONEDRIVE_WIN` and `ONEDRIVE_MAC` ([GH1556](#)).
- Bug Fix macOS: There are no more timeouts when opening or saving large workbooks that take longer than 60 seconds ([GH618](#)).
- Bug Fix `RunPython` was failing when there was a `&` in the Excel file name ([GH1557](#)).

30.42 v0.23.0 (Mar 5, 2021)

- PRO Feature: This release adds support for Markdown-based formatting of text, both in cells as well as in shapes, see [Markdown](#) for the details. This is also supported for template-based reports.

```
from xlwings.pro import Markdown, MarkdownStyle

mytext = """\n
# Title
```

(continues on next page)

(continued from previous page)

```

Text bold and italic

* A first bullet
* A second bullet

# Another Title

This paragraph has a line break.
Another line.
"""

sheet = xw.Book("Book1.xlsx").sheets[0]
sheet['A1'].value = Markdown(mytext)
sheet.shapes[0].text = Markdown(mytext)

```

Running this code will give you this nicely formatted text, but you can also define your own style to match your corporate style guide as explained under [Markdown](#):

	A	B	C	D	E	F
	Title	<div> Title Text bold and <i>italic</i> <ul style="list-style-type: none"> • A first bullet • A second bullet Another Title This paragraph has a line break. Another line. </div>				
	Text bold and <i>italic</i>					
	<ul style="list-style-type: none"> • A first bullet • A second bullet 					
	Another Title					
	This paragraph has a line break. Another line.					
1						
2						

- Feature Added support for the `Font` object via range or shape objects, see [Font](#) (GH897 and GH559).
- Feature Added support for the `Characters` object via range or shape objects, see [Characters](#).

30.43 v0.22.3 (Mar 3, 2021)

- Enhancement As a convenience method, you can now directly export sheets to PDF instead of having to go through the book: `mysheet.to_pdf()` (GH1517).
- PRO Bug Fix Running `RunPython` with embedded code was broken in 0.22.0 (GH1530).

30.44 v0.22.2 (Feb 8, 2021)

- Bug Fix Windows: If the path of the Excel file included a single quote, UDFs were failing (GH1511).
- Bug Fix macOS: Prevent Excel from showing up when using hidden Excel instances via `xw.App(visible=False)` (GH1508).

30.45 v0.22.1 (Feb 4, 2021)

- PRO Bug Fix: `Table.update` has been fixed so it also works when the table is the data source of a chart (GH1507).
- PRO [Docs]: New documentation about how to work with Excel charts in templates; see *xlwings Reports PRO*.

30.46 v0.22.0 (Jan 29, 2021)

- Feature While it's always been possible to *somehow* create your own xlwings-based add-ins, this release adds a toolchain to make it a lot easier to create your own white-labeled add-in, see *Custom Add-ins* (GH1488).
- Enhancement `xw.view` now formats the pandas DataFrames as Excel table and with the new `xw.load` function, you can easily load a DataFrame from your active workbook into a Jupyter notebook. See *Jupyter Notebooks: Interact with Excel* for a full tutorial (GH1487).
- Feature New method `mysheet.copy()` (GH123).
- PRO Feature: in addition to `xw.create_report()`, you can now also work within a workbook by using the new `mysheet.render_template()` method, see also *xlwings Reports PRO* (GH1478).

30.47 Older Releases

v0.21.4 (Nov 23, 2020)

- Enhancement New property `Shape.text` to read and write text to the text frame of shapes (GH1456).
- PRO Feature: xlwings Reports now supports template text in shapes, see *xlwings Reports*.

v0.21.3 (Nov 22, 2020)

- PRO Breaking Change: The `Table.update` method has been changed to treat the DataFrame's index consistently whether or not it's being written to an Excel table: by default, the index is now transferred to Excel in both cases.

v0.21.2 (Nov 15, 2020)

- Bug Fix The default quickstart setup now also works when you store your workbooks on OneDrive (GH1275)

- Bug Fix Excel files that have single quotes in their paths are now working correctly ([GH1021](#))

v0.21.1 (Nov 13, 2020)

- Enhancement Added new method `Book.to_pdf()` to easily export PDF reports. Needless to say, this integrates very nicely with *xlwings Reports* ([GH1363](#)).
- Enhancement Added support for `Sheet.visible` ([GH1459](#)).

v0.21.0 (Nov 9, 2020)

- Enhancement Added support for Excel tables, see: `Table` and `Tables` and `range.table` ([GH47](#) and [GH1364](#))
- Enhancement: When using UDFs, you can now use 'range' for the `convert` argument where you would use before `xw.Range`. The latter will be removed in a future version ([GH1455](#)).
- Enhancement Windows: The `comtypes` requirement has been dropped ([GH1443](#)).
- PRO Feature: `Table.update` offers an easy way to keep your Excel tables in sync with your DataFrame source ([GH1454](#)).
- PRO Enhancement: The reports package now supports Excel tables in the templates. This is e.g. helpful to style the tables with striped rows, see *Excel Tables* ([GH1364](#)).

v0.20.8 (Oct 18, 2020)

- Enhancement Windows: With UDFs, you can now get easy access to the caller (an xlwings range object) by using `caller` as a function argument ([GH1434](#)). In that sense, `caller` is now a reserved argument by xlwings and if you have any existing arguments with this name, you'll need to rename them:

```
@xw.func
def get_caller_address(caller):
    # caller will not be exposed in Excel, so use it like so:
    # =get_caller_address()
    return caller.address
```

- Bug Fix Windows: The setting `Show Console` now also shows/hides the command prompt properly when using the UDF server with Conda. There is no more switching between `python` and `pythonw` required ([GH1435](#) and [GH1421](#)).
- Bug Fix Windows: Functions called via `RunPython` with `Use UDF Server` activated don't require the `xw.sub` decorator anymore ([GH1418](#)).

v0.20.7 (Sep 3, 2020)

- Bug Fix Windows: Fix a regression introduced with 0.20.0 that would cause an `AttributeError: Range.CLSID` with `async` and legacy dynamic array UDFs ([GH1404](#)).
- Enhancement: Matplotlib figures are now converted to 300 dpi pictures for better quality when using them with `pictures.add` ([GH1402](#)).

v0.20.6 (Sep 1, 2020)

- Bug Fix macOS: `App(visible=False)` has been fixed ([GH652](#)).

- Bug Fix macOS: The regression with `Book.fullname` that was introduced with 0.20.1 has been fixed ([GH1390](#)).
- Bug Fix Windows: The retry mechanism has been improved ([GH1398](#)).

v0.20.5 (Aug 27, 2020)

- Bug Fix The conda version check was failing with spaces in the installation path ([GH1396](#)).
- Bug Fix Windows: when running `app.quit()`, the application is now properly closed without leaving a zombie process behind ([GH1397](#)).

v0.20.4 (Aug 20, 2020)

- Enhancement The add-in can now optionally be installed without the password protection: `xlwings addin install --unprotected` ([GH1392](#)).

v0.20.3 (Aug 15, 2020)

- Bug Fix The conda version check was erroneously triggered when importing UDFs on systems without conda. ([GH1389](#)).

v0.20.2 (Aug 13, 2020)

- PRO Feature: Code can now be embedded by calling the new `xlwings code embed [--file]` CLI command ([GH1380](#)).
- Bug Fix Made the import UDFs functionality more robust to prevent an Automation 440 error that some users would see ([GH1381](#)).
- Enhancement The standalone Excel file now includes all VBA dependencies to make it work on Windows and macOS ([GH1349](#)).
- Enhancement xlwings now blocks the call if the Conda Path/Env settings are used with legacy Conda installations ([GH1384](#)).

v0.20.1 (Aug 7, 2020)

- Bug Fix macOS: password-protected sheets caused an alert when calling `xw.Book` ([GH1377](#)).
- Bug Fix macOS: calling `wb.save('newname.xlsx')` wasn't updating the `wb` object properly and caused an alert ([GH1129](#) and [GH626](#) and [GH957](#)).

v0.20.0 (Jul 22, 2020)

This version drops support for Python 3.5

- Feature New property `xlwings.App.status_bar` ([GH1362](#)).
- Enhancement `xlwings.view()` now becomes the active window, making it easier to work with in interactive workflows (please speak up if you feel differently) ([GH1353](#)).
- Bug Fix The UDF server has received a serious upgrade by [njwhite](#), getting rid of the many issues that were around with using a combination of async functions and legacy dynamic arrays. You can now also call functions defined via `async def`, although for the time being they are still called synchronously from Excel ([GH1010](#) and [GH1164](#)).

v0.19.5 (Jul 5, 2020)

- Enhancement When you install the add-in via `xlwings addin install`, it autoconfigures the add-in if it can't find an existing user config file ([GH1322](#)).
- Feature New `xlwings config create [--force]` command that autogenerates the user config file with the Python settings from which you run the command. Can be used to reset the add-in settings with the `--force` option ([GH1322](#)).
- Feature: There is a new option to show/hide the console window. Note that with `Conda Path` and `Conda Env` set, the console always pops up when using the UDF server. Currently only available on Windows ([GH1182](#)).
- Enhancement The `Interpreter` setting has been deprecated in favor of platform-specific settings: `Interpreter_Win` and `Interpreter_Mac`, respectively. This allows you to use the sheet config unchanged on both platforms ([GH1345](#)).
- Enhancement On macOS, you can now use a few environment-like variables in your settings: `$HOME`, `$APPLICATIONS`, `$DOCUMENTS`, `$DESKTOP` ([GH615](#)).
- Bug Fix: Async functions sometimes caused an error on older Excel versions without dynamic arrays ([GH1341](#)).

v0.19.4 (May 20, 2020)

- Feature `xlwings addin install` is now available on macOS. On Windows, it has been fixed so it should now work reliably ([GH704](#)).
- Bug Fix Fixed a `dll load failed` issue with `pywin32` when installed via `pip` on Python 3.8 ([GH1315](#)).

v0.19.3 (May 19, 2020)

- PRO Feature: Added possibility to create deployment keys.

v0.19.2 (May 11, 2020)

- Feature New methods `xlwings.Shape.scale_height()` and `xlwings.Shape.scale_width()` ([GH311](#)).
- Bug Fix Using `Pictures.add` is not distorting the proportions anymore ([GH311](#)).
- PRO Feature: Added support for *Plotly* ([GH1309](#)).

v0.19.1 (May 4, 2020)


- Bug Fix Fixed an issue with the `xlwings PRO` license key when there was no `xlwings.conf` file ([GH1308](#)).

v0.19.0 (May 2, 2020)

- Bug Fix Native dynamic array formulas can now be used with async formulas ([GH1277](#))
- Enhancement Quickstart references the project's name when run from Python instead of the active book ([GH1307](#))

Breaking Change:

- `Conda Base` has been renamed into `Conda Path` to reduce the confusion with the `Conda Env` called `base`. Please adjust your settings accordingly! ([GH1194](#))



v0.18.0 (Feb 15, 2020)

- Feature Added support for merged cells: `xlwings.Range.merge_area`, `xlwings.Range.merge_cells`, `xlwings.Range.merge()` `xlwings.Range.unmerge()` (GH21).
- Bug Fix RunPython now works properly with files that have a URL as fullname, i.e. OneDrive and SharePoint (GH1253).
- Bug Fix Fixed a bug with `wb.names['...'].refers_to_range` on macOS (GH1256).

v0.17.1 (Jan 31, 2020)

- Bug Fix Handle `np.float64('nan')` correctly (GH1116).

v0.17.0 (Jan 6, 2020)

This release drops support for Python 2.7 in xlwings CE. If you still rely on Python 2.7, you will need to stick to v0.16.6.

v0.16.6 (Jan 5, 2020)

- Enhancement CLI changes with respect to xlwings license (GH1227).

v0.16.5 (Dec 30, 2019)

- Enhancement Improvements with regards to the Run main ribbon button (GH1207 and GH1222).

v0.16.4 (Dec 17, 2019)

- Enhancement Added support for `xlwings.Range.copy()` (GH1214).
- Enhancement Added support for `xlwings.Range.paste()` (GH1215).
- Enhancement Added support for `xlwings.Range.insert()` (GH80).
- Enhancement Added support for `xlwings.Range.delete()` (GH862).

v0.16.3 (Dec 12, 2019)

- Bug Fix Sometimes, xlwings would show an error of a previous run. Moreover, 0.16.2 introduced an issue that would not show errors at all on non-conda setups (GH1158 and GH1206)
- Enhancement The xlwings CLI now prints the version number (GH1200)

Breaking Change

- LOG FILE has been retired and removed from the configuration/add-in.

v0.16.2 (Dec 5, 2019)

- Bug Fix RunPython can now be called in parallel from different Excel instances (GH1196).

v0.16.1 (Dec 1, 2019)


- Enhancement `xlwings.Book()` and `myapp.books.open()` now accept parameters like `update_links`, `password` etc. (GH1189).
- Bug Fix Conda Env now works correctly with base for UDFs, too (GH1110).
- Bug Fix Conda Base now allows spaces in the path (GH1176).
- Enhancement The UDF server timeout has been increased to 2 minutes (GH1168).

v0.16.0 (Oct 13, 2019)

This release adds a small but very powerful feature: There's a new **Run main** button in the add-in. With that, you can run your Python scripts from standard **xlsx** files - no need to save your workbook as macro-enabled anymore!

The only condition to make that work is that your Python script has the same name as your workbook and that it contains a function called **main**, which will be called when you click the **Run** button. All settings from your config file or config sheet are still respected, so this will work even if you have the source file in a different directory than your workbook (as long as that directory is added to the **PYTHONPATH** in your config).

The **xlwings quickstart myproject** has been updated accordingly. It still produces an **xlsm** file at the moment but you can save it as **xlsx** file if you intend to run it via the new **Run** button.



v0.15.10 (Aug 31, 2019)

- Bug Fix Fixed a Python 2.7 incompatibility introduced with 0.15.9.

v0.15.9 (Aug 31, 2019)

- Enhancement The **sql** extension now uses the native dynamic arrays if available ([GH1138](#)).
- Enhancement **xlwings** now support **Path** objects from **pathlib** for all file paths ([GH1126](#)).
- Bug Fix Various bug fixes: ([GH1118](#)), ([GH1131](#)), ([GH1102](#)).

v0.15.8 (May 5, 2019)

- Bug Fix Fixed an issue introduced with the previous release that always showed the command prompt when running UDFs, not just when using conda envs ([GH1098](#)).

v0.15.7 (May 5, 2019)

- Bug Fix **Conda Base** and **Conda Env** weren't stored correctly in the config file from the ribbon ([GH1090](#)).
- Bug Fix UDFs now work correctly with **Conda Base** and **Conda Env**. Note, however, that currently there is no way to hide the command prompt in that configuration ([GH1090](#)).
- Enhancement **Restart UDF Server** now actually does what it says: it stops and restarts the server. Previously it was only stopping the server and only when the first call to Python was made, it was started again ([GH1096](#)).

v0.15.6 (Apr 29, 2019)

- Feature New default converter for **OrderedDict** ([GH1068](#)).
- Enhancement **Import Functions** now restarts the UDF server to guarantee a clean state after importing. ([GH1092](#))

- Enhancement The ribbon now shows tooltips on Windows ([GH1093](#))
- Bug Fix RunPython now properly supports conda environments on Windows (they started to require proper activation with packages like numpy etc). Conda >=4.6. required. A fix for UDFs is still pending ([GH954](#)).

Breaking Change

- Bug Fix RunFrozenPython now accepts spaces in the path of the executable, but in turn requires to be called with command line arguments as a separate VBA argument. Example: RunFrozenPython "C:\path\to\python_executable.exe", "arg1 arg2" ([GH1063](#)).

v0.15.5 (Mar 25, 2019)

- Enhancement wb.macro() now accepts xlwings objects as arguments such as range, sheet etc. when the VBA macro expects the corresponding Excel object (e.g. Range, Worksheet etc.) ([GH784](#) and [GH1084](#))

Breaking Change

- Cells that contain a cell error such as #DIV/0!, #N/A, #NAME?, #NULL!, #NUM!, #REF!, #VALUE! return now None as value in Python. Previously they were returned as constant on Windows (e.g. -2146826246) or k.missing_value on Mac.

v0.15.4 (Mar 17, 2019)

- [Win] BugFix: The ribbon was not showing up in Excel 2007. ([GH1039](#))
- Enhancement: Allow to install xlwings on Linux even though it's not a supported platform: export INSTALL_ON_LINUX=1; pip install xlwings ([GH1052](#))

v0.15.3 (Feb 23, 2019)

Bug Fix release:

- [Mac] RunPython was broken by the previous release. If you install via conda, make sure to run xlwings runpython install again! ([GH1035](#))
- [Win] Sometimes, the ribbon was throwing errors ([GH1041](#))

v0.15.2 (Feb 3, 2019)

Better support and docs for deployment, see [Deployment](#):

- You can now package your python modules into a zip file for easier distribution ([GH1016](#)).
- RunFrozenPython now allows to includes arguments, e.g. RunFrozenPython "C:\path\to\my.exe arg1 arg2" ([GH588](#)).

Breaking Change

- Accessing a not existing PID in the apps collection raises now a KeyError instead of an Exception ([GH1002](#)).

v0.15.1 (Nov 29, 2018)

Bug Fix release:

- [Win] Calling Subs or UDFs from VBA was causing an error ([GH998](#)).

v0.15.0 (Nov 20, 2018)

Dynamic Array Refactor

While we're all waiting for the new native dynamic arrays, it's still going to take another while until the majority can use them (they are not yet part of Office 2019).

In the meantime, this refactor improves the current xlwings dynamic arrays in the following way:

- Use of native ("legacy") array formulas instead of having a normal formula in the top left cell and writing around it
- It's up to 2x faster
- There's no empty row/col required outside of the dynamic array anymore
- It continues to overwrite existing cells (no change there)
- There's a small breaking change in the unlikely case that you were assigning values with the `expand` option: `myrange.options(expand='table').value = [['b'] * 3] * 3`. This was previously clearing contiguous cells to the right and bottom (or one of them depending on the option), now you have to do that explicitly.

Bug Fixes:

- Importing multiple UDF modules has been fixed ([GH991](#)).

v0.14.1 (Nov 9, 2018)

This is a bug fix release:

- [Win] Fixed an issue when the new `async_mode` was used together with numpy arrays ([GH984](#))
- [Mac] Fixed an issue with multiple arguments in `RunPython` ([GH905](#))
- [Mac] Fixed an issue with the config file ([GH982](#))

v0.14.0 (Nov 5, 2018)

Features:

This release adds support for asynchronous functions (like all UDF related functionality, this is only available on Windows). Making a function asynchronous is as easy as:

```
import xlwings as xw
import time

@xw.func(async_mode='threading')
def myfunction(a):
    time.sleep(5)  # long running tasks
    return a
```

See *Asynchronous UDFs* for the full docs.

Bug Fixes:

- See [GH970](#) and [GH973](#).

v0.13.0 (Oct 22, 2018)

Features:

This release adds a REST API server to xlwings, allowing you to easily expose your workbook over the internet, see [REST API](#) for all the details!

Enhancements:

- Dynamic arrays are now more robust. Before, they often didn't manage to write everything when there was a lot going on in the workbook ([GH880](#))
- Jagged arrays (lists of lists where not all rows are of equal length) now raise an error ([GH942](#))
- xlwings can now be used with threading, see the docs: [Threading](#) ([GH759](#)).
- [Win] xlwings now enforces pywin32 224 when installing xlwings on Python 3.7 ([GH959](#))
- New `xlwings.Sheet.used_range` property ([GH112](#))

Bug Fixes:

- The current directory is now inserted in front of everything else on the PYTHONPATH ([GH958](#))
- The standalone files had an issue in the VBA module ([GH960](#))

Breaking Change

- Members of the `xw.apps` collection are now accessed by key (=PID) instead of index, e.g.: `xw.apps[12345]` instead of `xw.apps[0]`. The apps collection also has a new `xw.apps.keys()` method. ([GH951](#))

v0.12.1 (Oct 7, 2018)

[Py27] Bug Fix for a Python 2.7 glitch.

v0.12.0 (Oct 7, 2018)

Features:

This release adds support to call Python functions from VBA in all Office apps (e.g. Access, Outlook etc.), not just Excel. As this uses UDFs, it is only available on Windows. See the docs: [xlwings with other Office Apps](#).

Breaking Change

Previously, Python functions were always returning 2d arrays when called from VBA, no matter whether it was actually a 2d array or not. Now you get the proper dimensionality which makes it easier if the return value is e.g. a string or scalar as you don't have to unpack it anymore.

Consider the following example using the VBA Editor's Immediate Window after importing UDFs from a project created using by xlwings `quickstart`:

Old behaviour

```
?TypeName(hello("xlwings"))
Variant()
```

(continues on next page)

(continued from previous page)

```
?hello("xlwings")(0,0)
hello xlwings
```

New behaviour

```
?TypeName(hello("xlwings"))
String
?hello("xlwings")
hello xlwings
```

Bug Fixes:

- [Win] Support expansion of environment variables in config values ([GH615](#))
- Other bug fixes: [GH889](#), [GH939](#), [GH940](#), [GH943](#).

v0.11.8 (May 13, 2018)

- [Win] pywin32 is now automatically installed when using pip ([GH827](#))
- *xlwings.bas* has been readded to the python package. This facilitates e.g. the use of xlwings within other addins ([GH857](#))

v0.11.7 (Feb 5, 2018)

- [Win] This release fixes a bug introduced with v0.11.6 that wouldn't allow to open workbooks by name ([GH804](#))

v0.11.6 (Jan 27, 2018)

Bug Fixes:

- [Win] When constantly writing to a spreadsheet, xlwings now correctly resumes after clicking into cells, previously it was crashing. ([GH587](#))
- Options are now correctly applied when writing to a sheet ([GH798](#))

v0.11.5 (Jan 7, 2018)


This is mostly a bug fix release:

- Config files can now additionally be saved in the directory of the workbooks, overriding the global Ribbon config, see [Making use of Environment Variables](#) ([GH772](#))
- Reading Pandas DataFrames with a simple index was creating a MultiIndex with Pandas > 0.20 ([GH786](#))
- [Win] The xlwings dlls are now properly versioned, allowing to use pre 0.11 releases in parallel with >0.11 releases ([GH743](#))
- [Mac] Sheet.names.add() was always adding the names on workbook level ([GH771](#))
- [Mac] UDF decorators now don't cause errors on Mac anymore ([GH780](#))


v0.11.4 (Jul 23, 2017)

This release brings further improvements with regards to the add-in:

- The add-in now shows the version on the ribbon. This makes it easy to check if you are using the correct version ([GH724](#)):



- [Mac] On Mac Excel 2016, the ribbon now only shows the available functionality ([GH723](#)):



- [Mac] Mac Excel 2011 is now supported again with the new add-in. However, since Excel 2011 doesn't support the ribbon, the config file has been created/edited manually, see [Making use of Environment Variables](#) ([GH714](#)).

Also, some new docs:

- [Win] How to use imported functions in VBA, see [Call UDFs from VBA](#).
- For more up-to-date installations via conda, use the conda-forge channel, see [Installation](#).
- A troubleshooting section: [Troubleshooting](#).

v0.11.3 (Jul 14, 2017)

- Bug Fix: When using the `xlwings.conf` sheet, there was a subscript out of range error ([GH708](#))
- Enhancement: The add-in is now password protected (pw: `xlwings`) to declutter the VBA editor ([GH710](#))

You need to update your xlwings add-in to get the fixes!

v0.11.2 (Jul 6, 2017)

- Bug Fix: The sql extension was sometimes not correctly assigning the table aliases ([GH699](#))
- Bug Fix: Permission errors during pip installation should be resolved now ([GH693](#))


v0.11.1 (Jul 5, 2017)

- Bug Fix: The sql extension installs now correctly ([GH695](#))

v0.11.0 (Jul 2, 2017)

Big news! This release adds a full blown **add-in**! We also throw in a great **In-Excel SQL Extension** and a few **bug fixes**:

Add-in



A few highlights:

- Settings don't have to be manipulated in VBA code anymore, but can be either set globally via Ribbon/config file or for the workbook via a special worksheet
- UDF server can be restarted directly from the add-in
- You can still use a VBA module instead of the add-in, but the recommended way is the add-in
- Get all the details here: [Add-in & Settings](#)

In-Excel SQL Extension

The add-in can be extended with own code. We throw in an sql function, that allows you to perform SQL queries on data in your spreadsheets. It's pretty awesome, get the details here: [Extensions](#).

Bug Fixes

- [Win]: Running Debug > Compile is not throwing errors anymore ([GH678](#))
- Pandas deprecation warnings have been fixed ([GH675](#) and [GH664](#))
- [Mac]: Errors are again shown correctly in a pop up ([GH660](#))
- [Mac]: Like Windows, Mac now also only shows errors in a popup. Before it was including stdout, too ([GH666](#))

Breaking Change

- RunFrozenPython now requires the full path to the executable.
- The xlwings CLI `xlwings template` functionality has been removed. Use `quickstart` instead.

Migrate to v0.11 (Add-in)

This migration guide shows you how you can start using the new xlwings add-in as opposed to the old xlwings VBA module (and the old add-in that consisted of just a single import button).

Upgrade the xlwings Python package

1. Check where xlwings is currently installed

```
>>> import xlwings
>>> xlwings.__path__
```

2. If you installed xlwings with pip, for once, you should first uninstall xlwings: `pip uninstall xlwings`
3. Check the directory that you got under 1): if there are any files left over, delete the xlwings folder and the remaining files manually
4. Install the latest xlwings version: `pip install xlwings`
5. Verify that you have `>= 0.11` by doing

```
>>> import xlwings
>>> xlwings.__version__
```

Install the add-in

1. If you have the old xlwings addin installed, find the location and remove it or overwrite it with the new version (see next step). If you installed it via the xlwings command line client, you should be able to do: `xlwings addin remove`.
2. Close Excel. Run `xlwings addin install` from a command prompt. Reopen Excel and check if the xlwings Ribbon appears. If not, copy `xlwings.xlam` (from your xlwings installation folder under `addin\xlwings.xlam` manually into the XLSTART folder. You can find the location of this folder under Options > Trust Center > Trust Center Settings... > Trusted Locations, under the description Excel default location: User StartUp. Restart Excel and you should see the add-in.

Upgrade existing workbooks

1. Make a backup of your Excel file
2. Open the file and go to the VBA Editor (Alt-F11)
3. Remove the xlwings VBA module
4. Add a reference to the xlwings addin, see [Installation](#)
5. If you want to use workbook specific settings, add a sheet `xlwings.conf`, see [Workbook Config: xlwings.conf Sheet](#)

Note: To import UDFs, you need to have the reference to the xlwings add-in set!

v0.10.4 (Feb 19, 2017)

- [Win] Bug Fix: v0.10.3 introduced a bug that imported UDFs by default with `volatile=True`, this has now been fixed. You will need to reimport your functions after upgrading the xlwings package.

v0.10.3 (Jan 28, 2017)

This release adds new features to User Defined Functions (UDFs):

- categories
- volatile option
- suppress calculation in function wizard

Syntax:

```
import xlwings as xw
@xw.func(category="xlwings", volatile=False, call_in_wizard=True)
def myfunction():
    return ...
```

For details, check out the (also new) and comprehensive API docs about the decorators: *UDF decorators*
v0.10.2 (Dec 31, 2016)

- [Win] Python 3.6 is now supported ([GH592](#))

v0.10.1 (Dec 5, 2016)

- Writing a Pandas Series with a MultiIndex header was not writing out the header ([GH572](#))
- [Win] Docstrings for UDF arguments are now working ([GH367](#))
- [Mac] `Range.clear_contents()` has been fixed (it was doing `clear()` instead) ([GH576](#))
- `xw.Book(...)` and `xw.books.open(...)` raise now the same error in case the file doesn't exist ([GH540](#))

v0.10.0 (Sep 20, 2016)

Dynamic Array Formulas

This release adds an often requested & powerful new feature to User Defined Functions (UDFs): Dynamic expansion for array formulas. While Excel offers array formulas, you need to specify their dimensions up front by selecting the result array first, then entering the formula and finally hitting **Ctrl-Shift-Enter**. While this makes sense from a data integrity point of view, in practice, it often turns out to be a cumbersome limitation, especially when working with dynamic arrays such as time series data.

This is a simple example that demonstrates the syntax and effect of UDF expansion:

```
import numpy as np

@xw.func
@xw.ret(expand='table')
def dynamic_array(r, c):
    return np.random.randn(int(r), int(c))
```

Note: Expanding array formulas will overwrite cells without prompting and leave an empty border around them, i.e. they will clear the row to the bottom and the column to the right of the array.

Bug Fixes

- The `int` converter works now always as you would expect (e.g.: `xw.Range('A1').options(numbers=int).value`). Before, it could happen that the number was off by 1 due to floating point issues ([GH554](#)).

v0.9.3 (Aug 22, 2016)

- [Win] `App.visible` wasn't behaving correctly ([GH551](#)).
- [Mac] Added support for the new 64bit version of Excel 2016 on Mac ([GH549](#)).

File Home Insert Page Layout Formulas Data Review					
B4 ✕ ✓ <i>fx</i> =dynamic_array(B2,C2)					
	A	B	C	D	E
1		rows:	columns:		
2		5	2		
3					
4		2.01156647	-0.0985618		
5		-0.2152179	-0.7541961		
6		0.37168657	-0.1978662		
7		-1.0643897	1.37592295		
8		0.5272535	-0.0508628		
9					

File Home Insert Page Layout Formulas Data Review View xlwings							
B4 ✕ ✓ <i>fx</i> =dynamic_array(B2,C2)							
	A	B	C	D	E	F	
1		rows:	columns:				
2		2	5				
3							
4		-0.6788379	-1.0009999	-0.6342434	-0.9362773	1.02582914	
5		-2.1803953	0.18511092	0.3121721	0.20600051	0.3799863	
6							

- Unicode book names are again supported ([GH546](#)).
- `xlwings.Book.save()` now supports relative paths. Also, when saving an existing book under a new name without specifying the full path, it'll be saved in Python's current working directory instead of in Excel's default directory ([GH185](#)).

v0.9.2 (Aug 8, 2016)

Another round of bug fixes:

- [Mac]: Sometimes, a column was referenced instead of a named range ([GH545](#))
- [Mac]: Python 2.7 was raising a `LookupError: unknown encoding: mbcs` ([GH544](#))
- Fixed docs regarding `set_mock_caller` ([GH543](#))

v0.9.1 (Aug 5, 2016)

This is a bug fix release: As to be expected after a rewrite, there were some rough edges that have now been taken care of:

- [Win] Opening a file via `xw.Book()` was causing an additional Book1 to be opened in case Excel was not running yet ([GH531](#))
- [Win] Some users were getting an `ImportError` ([GH533](#))
- [PY 2.7] `RunPython` was broken with Python 2.7 ([GH537](#))
- Some corrections in the docs ([GH538](#) and [GH536](#))

v0.9.0 (Aug 2, 2016)

Exciting times! v0.9.0 is a complete rewrite of xlwings with loads of syntax changes (hence the version jump). But more importantly, this release adds a ton of new features and bug fixes that would have otherwise been impossible. Some of the highlights are listed below, but make sure to check out the full [migration guide](#) for the syntax changes in details. Note, however, that the syntax for user defined functions (UDFs) did not change. At this point, the API is fairly stable and we're expecting only smaller changes on our way towards a stable v1.0 release.

- **Active** book instead of **current** book: `xw.Range('A1')` goes against the active sheet of the active book like you're used to from VBA. Instantiating an explicit connection to a Book is not necessary anymore:

```
>>> import xlwings as xw
>>> xw.Range('A1').value = 11
>>> xw.Range('A1').value
11.0
```

- Excel Instances: Full support of multiple Excel instances (even on Mac!)

```
>>> app1 = xw.App()
>>> app2 = xw.App()
>>> xw.apps
Apps([<Excel App 1668>, <Excel App 1644>])
```


- New powerful object model based on collections and close to Excel's original, allowing to fully qualify objects: `xw.apps[0].books['MyBook.xlsx'].sheets[0].range('A1:B2').value`

It supports both Python indexing (square brackets) and Excel indexing (round brackets):

`xw.books[0].sheets[0]` is the same as `xw.books(1).sheets(1)`

It also supports indexing and slicing of range objects:

```
>>> rng = xw.Range('A1:E10')
>>> rng[1]
<Range [Workbook1]Sheet1!$B$1>
>>> rng[:2, :2]
<Range [Workbook1]Sheet1!$A$1:$B$2>
```

For more details, see [Syntax Overview](#).

- UDFs can now also be imported from packages, not just modules ([GH437](#))
- Named Ranges: Introduction of full object model and proper support for sheet and workbook scope ([GH256](#))
- Excel doesn't become the active window anymore so the focus stays on your Python environment ([GH414](#))
- When writing to ranges while Excel is busy, xlwings is now retrying until Excel is idle again ([GH468](#))
- `xlwings.view()` has been enhanced to accept an optional sheet object ([GH469](#))
- Objects like books, sheets etc. can now be compared (e.g. `wb1 == wb2`) and are properly hashable
- Note that support for Python 2.6 has been dropped

Some of the new methods/properties worth mentioning are:

- `xlwings.App.display_alerts`
- `xlwings.App.macro()` in addition to `xlwings.Book.macro()`
- `xlwings.App.kill()`
- `xlwings.Sheet.cells`
- `xlwings.Range.rows`
- `xlwings.Range.columns`
- `xlwings.Range.end()`
- `xlwings.Range.raw_value`

Bug Fixes

- See [here](#) for details about which bugs have been fixed.

Migrate to v0.9

The purpose of this document is to enable you a smooth experience when upgrading to xlwings v0.9.0 and above by laying out the concept and syntax changes in detail. If you want to get an overview of the new

features and bug fixes, have a look at the [release notes](#). Note that the syntax for User Defined Functions (UDFs) didn't change.

Full qualification: Using collections

The new object model allows to specify the Excel application instance if needed:

- **old:** `xw.Range('Sheet1', 'A1', wkb=xw.Workbook('Book1'))`
- **new:** `xw.apps[0].books['Book1'].sheets['Sheet1'].range('A1')`

See [Syntax Overview](#) for the details of the new object model.

Connecting to Books

- **old:** `xw.Workbook()`
- **new:** `xw.Book()` or via `xw.books` if you need to control the app instance.

See [Connect to a Book](#) for the details.

Active Objects

```
# Active app (i.e. Excel instance)
>>> app = xw.apps.active

# Active book
>>> wb = xw.books.active # in active app
>>> wb = app.books.active # in specific app

# Active sheet
>>> sht = xw.sheets.active # in active book
>>> sht = wb.sheets.active # in specific book

# Range on active sheet
>>> xw.Range('A1') # on active sheet of active book of active app
```

Round vs. Square Brackets

Round brackets follow Excel's behavior (i.e. 1-based indexing), while square brackets use Python's 0-based indexing/slicing.

As an example, the following all reference the same range:

```
xw.apps[0].books[0].sheets[0].range('A1')
xw.apps(1).books(1).sheets(1).range('A1')
xw.apps[0].books['Book1'].sheets['Sheet1'].range('A1')
xw.apps(1).books('Book1').sheets('Sheet1').range('A1')
```

Access the underlying Library/Engine

- **old:** `xw.Range('A1').xl_range` and `xl_sheet` etc.
- **new:** `xw.Range('A1').api`, same for all other objects

This returns a pywin32 COM object on Windows and an appscript object on Mac.

Cheat sheet

Note that sht stands for a sheet object, like e.g. (in 0.9.0 syntax): `sht = xw.books['Book1'].sheets[0]`

	v0.9.0	v0.7.2
Active Excel instance	<code>xw.apps.active</code>	unsupported
New Excel instance	<code>app = xw.App()</code>	unsupported
Get app from book	<code>app = wb.app</code>	<code>app = xw.Application(wb)</code>
Target installation (Mac)	<code>app = xw.App(spec=...)</code>	<code>wb = xw.Workbook(app_target)</code>
Hide Excel Instance	<code>app = xw.App(visible=False)</code>	<code>wb = xw.Workbook(app_visible=False)</code>
Selected Range	<code>app.selection</code>	<code>wb.get_selection()</code>
Calculation mode	<code>app.calculation = 'manual'</code>	<code>app.calculation = xw.constants.xlCalculationManual</code>
All books in app	<code>app.books</code>	unsupported
Fully qualified book	<code>app.books['Book1']</code>	unsupported
Active book in active app	<code>xw.books.active</code>	<code>xw.Workbook.active()</code>
New book in active app	<code>wb = xw.Book()</code>	<code>wb = xw.Workbook()</code>
New book in specific app	<code>wb = app.books.add()</code>	unsupported
All sheets in book	<code>wb.sheets</code>	<code>xw.Sheet.all(wb)</code>
Call a macro in an addin	<code>app.macro('MacroName')</code>	unsupported
First sheet of book wb	<code>wb.sheets[0]</code>	<code>xw.Sheet(1, wkb=wb)</code>
Active sheet	<code>wb.sheets.active</code>	<code>xw.Sheet.active(wkb=wb) or wb.ActiveSheet</code>
Add sheet	<code>wb.sheets.add()</code>	<code>xw.Sheet.add(wkb=wb)</code>
Sheet count	<code>wb.sheets.count</code> or <code>len(wb.sheets)</code>	<code>xw.Sheet.count(wb)</code>
Add chart to sheet	<code>chart = wb.sheets[0].charts.add()</code>	<code>chart = xw.Chart.add(sheet, wkb=wb)</code>
Existing chart	<code>wb.sheets['Sheet 1'].charts[0]</code>	<code>xw.Chart('Sheet 1', 1)</code>
Chart Type	<code>chart.chart_type = '3d_area'</code>	<code>chart.chart_type = xw.constants.xlChartType3dArea</code>
Add picture to sheet	<code>wb.sheets[0].pictures.add('path/to/pic')</code>	<code>xw.Picture.add('path/to/pic', wkb=wb)</code>
Existing picture	<code>wb.sheets['Sheet 1'].pictures[0]</code>	<code>xw.Picture('Sheet 1', 1)</code>
Matplotlib	<code>sht.pictures.add(fig, name='x', update=True)</code>	<code>xw.Plot(fig).show('MyPlot')</code>
Table expansion	<code>sht.range('A1').expand('table')</code>	<code>xw.Range(sht, 'A1', wkb=wb).expand(xlExpandFromTo, xlExpandTo='table')</code>
Vertical expansion	<code>sht.range('A1').expand('down')</code>	<code>xw.Range(sht, 'A1', wkb=wb).expand(xlExpandFromTo, xlExpandTo='down')</code>
Horizontal expansion	<code>sht.range('A1').expand('right')</code>	<code>xw.Range(sht, 'A1', wkb=wb).expand(xlExpandFromTo, xlExpandTo='right')</code>
Set name of range	<code>sht.range('A1').name = 'name'</code>	<code>xw.Range(sht, 'A1', wkb=wb).name = 'name'</code>
Get name of range	<code>sht.range('A1').name.name</code>	<code>xw.Range(sht, 'A1', wkb=wb).name.name</code>
mock caller	<code>xw.Book('file.xlsm').set_mock_caller()</code>	<code>xw.Workbook.set_mock_caller()</code>

v0.7.2 (May 18, 2016)

Bug Fixes

- [Win] UDFs returning Pandas DataFrames/Series containing nan were failing ([GH446](#)).
- [Win] RunFrozenPython was not finding the executable ([GH452](#)).
- The xlwings VBA module was not finding the Python interpreter if PYTHON_WIN or PYTHON_MAC contained spaces ([GH461](#)).

v0.7.1 (April 3, 2016)

Enhancements

- [Win]: User Defined Functions (UDFs) support now optional/default arguments ([GH363](#))
- [Win]: User Defined Functions (UDFs) support now multiple source files, see also under API changes below. For example (VBA settings): UDF_MODULES="common;myproject"
- VBA Subs & Functions are now callable from Python:

As an example, this VBA function:

```
Function MySum(x, y)
    MySum = x + y
End Function
```

can be accessed like this:

```
>>> import xlwings as xw
>>> wb = xw.Workbook.active()
>>> my_sum = wb.macro('MySum')
>>> my_sum(1, 2)
3.0
```

- New `xw.view` method: This opens a new workbook and displays an object on its first sheet. E.g.:

```
>>> import xlwings as xw
>>> import pandas as pd
>>> import numpy as np
>>> df = pd.DataFrame(np.random.rand(10, 4), columns=['a', 'b', 'c', 'd'])
>>> xw.view(df)
```

- New docs about *Matplotlib* and *Custom Converter*
- New method: `xlwings.Range.formula_array()` ([GH411](#))

API changes

- VBA settings: PYTHON_WIN and PYTHON_MAC must now include the interpreter if you are not using the default (PYTHON_WIN = "") ([GH289](#)). E.g.:

```
PYTHON_WIN: "C:\Python35\pythonw.exe"
PYTHON_MAC: "/usr/local/bin/python3.5"
```

- [Win]: VBA settings: UDF_PATH has been replaced with UDF_MODULES. The default behaviour doesn't change though (i.e. if UDF_MODULES = "", then a Python source file with the same name as the Excel file, but with .py ending will be imported from the same directory as the Excel file).

New:

```
UDF_MODULES: "mymodule"
PYTHONPATH: "C:\path\to"
```

Old:

```
UDF_PATH: "C:\path\to\mymodule.py"
```

Bug Fixes

- Numpy scalars issues were resolved ([GH415](#))
- [Win]: xlwings was failing with freezers like cx_Freeze ([GH413](#))
- [Win]: UDFs were failing if they were returning None or np.nan ([GH390](#))
- Multiindex Pandas Series have been fixed ([GH383](#))
- [Mac]: xlwings runpython install was failing ([GH424](#))

v0.7.0 (March 4, 2016)

This version marks an important first step on our path towards a stable release. It introduces **converters**, a new and powerful concept that brings a consistent experience for how Excel Ranges and their values are treated both when **reading** and **writing** but also across **xlwings.Range** objects and **User Defined Functions** (UDFs).

As a result, a few highlights of this release include:

- Pandas DataFrames and Series are now supported for reading and writing, both via Range object and UDFs
- New Range converter options: `transpose`, `dates`, `numbers`, `empty`, `expand`
- New dictionary converter
- New UDF debug server
- No more pyc files when using RunPython

Converters are accessed via the new `options` method when dealing with `xlwings.Range` objects or via the `@xw.arg` and `@xw.ret` decorators when using UDFs. As an introductory sample, let's look at how to read and write Pandas DataFrames:

Range object:

```
>>> import xlwings as xw
>>> import pandas as pd
>>> wb = xw.Workbook()
>>> df = xw.Range('A1:D5').options(pd.DataFrame, header=2).value
```

(continues on next page)

	A	B	C	D
1		a	a	b
2	ix	c	d	e
3	10	1	2	3
4	20	4	5	6
5	30	7	8	9
6				
7		a	a	b
8		c	d	e
9		1	2	3
10		4	5	6
11		7	8	9
12				
13		a	a	b
14		c	d	e
15		1	2	3
16		4	5	6
17		7	8	9
18				

(continued from previous page)

```
>>> df
      a  b
      c  d  e
ix
10  1  2  3
20  4  5  6
30  7  8  9

# Writing back using the defaults:
>>> Range('A1').value = df

# Writing back and changing some of the options, e.g. getting rid of the index:
>>> Range('B7').options(index=False).value = df
```

UDFs:

This is the same sample as above (starting in Range('A13') on screenshot). If you wanted to return a DataFrame with the defaults, the @xw.ret decorator can be left away.

```
@xw.func
@xw.arg('x', pd.DataFrame, header=2)
@xw.ret(index=False)
```

(continues on next page)

(continued from previous page)

```
def myfunction(x):
    # x is a DataFrame, do something with it
    return x
```

Enhancements

- Dictionary (dict) converter:

	A	B
1	a	1
2	b	2
3		
4	a	b
5	1	2

```
>>> Range('A1:B2').options(dict).value
{'a': 1.0, 'b': 2.0}
>>> Range('A4:B5').options(dict, transpose=True).value
{'a': 1.0, 'b': 2.0}
```

- transpose option: This works in both directions and finally allows us to e.g. write a list in column orientation to Excel (GH11):

```
Range('A1').options(transpose=True).value = [1, 2, 3]
```

- dates option: This allows us to read Excel date-formatted cells in specific formats:

```
>>> import datetime as dt
>>> Range('A1').value
datetime.datetime(2015, 1, 13, 0, 0)
>>> Range('A1').options(dates=dt.date).value
datetime.date(2015, 1, 13)
```

- empty option: This allows us to override the default behavior for empty cells:

```
>>> Range('A1:B1').value
[None, None]
>>> Range('A1:B1').options(empty='NA')
['NA', 'NA']
```

- numbers option: This transforms all numbers into the indicated type.

```
>>> xw.Range('A1').value = 1
>>> type(xw.Range('A1').value) # Excel stores all numbers internally as_
↳ floats
float
>>> type(xw.Range('A1').options(numbers=int).value)
int
```

- `expand` option: This works the same as the Range properties `table`, `vertical` and `horizontal` but is only evaluated when getting the values of a Range:

```
>>> import xlwings as xw
>>> wb = xw.Workbook()
>>> xw.Range('A1').value = [[1,2], [3,4]]
>>> rng1 = xw.Range('A1').table
>>> rng2 = xw.Range('A1').options(expand='table')
>>> rng1.value
[[1.0, 2.0], [3.0, 4.0]]
>>> rng2.value
[[1.0, 2.0], [3.0, 4.0]]
>>> xw.Range('A3').value = [5, 6]
>>> rng1.value
[[1.0, 2.0], [3.0, 4.0]]
>>> rng2.value
[[1.0, 2.0], [3.0, 4.0], [5.0, 6.0]]
```

All these options work the same with decorators for UDFs, e.g. for transpose:

```
@xw.arg('x', transpose=True)
@xw.ret(transpose=True)
def myfunction(x):
    # x will be returned unchanged as transposed both when reading and writing
    return x
```

Note: These options (`dates`, `empty`, `numbers`) currently apply to the whole Range and can't be selectively applied to e.g. only certain columns.

- UDF debug server

The new UDF debug server allows you to easily debug UDFs: just set `UDF_DEBUG_SERVER = True` in the VBA Settings, at the top of the xlwings VBA module (make sure to update it to the latest version!). Then add the following lines to your Python source file and run it:

```
if __name__ == '__main__':
    xw.serve()
```

When you recalculate the Sheet, the code will stop at breakpoints or print any statements that you may have. For details, see: [Debugging](#).

- pyc files: The creation of pyc files has been disabled when using RunPython, leaving your directory in an uncluttered state when having the Python source file next to the Excel workbook ([GH326](#)).

API changes

- UDF decorator changes (it is assumed that xlwings is imported as `xw` and numpy as `np`):

New	Old
@xw.func	@xw.xlfunc
@xw.arg	@xw.xlarg
@xw.ret	@xw.xlret
@xw.sub	@xw.xlsub

Pay attention to the following subtle change:

New	Old
@xw.arg("x", np.array)	@xw.xlarg("x", "nparray")

- Samples of how the new options method replaces the old Range keyword arguments:

New	Old
Range('A1:A2').options(ndim=2)	Range('A1:A2', atleast_2d=True)
Range('A1:B2').options(np.array)	Range('A1:B2', asarray=True)
Range('A1').options(index=False, header=False).value = df	Range('A1', index=False, header=False).value = df

- Upon writing, Pandas Series are now shown by default with their name and index name, if they exist. This can be changed using the same options as for DataFrames ([GH276](#)):

```
import pandas as pd

# unchanged behaviour
Range('A1').value = pd.Series([1,2,3])

# Changed behaviour: This will print a header row in Excel
s = pd.Series([1,2,3], name='myseries', index=pd.Index([0,1,2], name='myindex'))
Range('A1').value = s

# Control this behaviour like so (as with DataFrames):
Range('A1').options(header=False, index=True).value = s
```

- NumPy scalar values

Previously, NumPy scalar values were returned as `np.atleast_1d`. To keep the same behaviour, this now has to be set explicitly using `ndim=1`. Otherwise they're returned as numpy scalar values.

New	Old
Range('A1').options(np.array, ndim=1).value	Range('A1', asarray=True).value

Bug Fixes

A few bugfixes were made: [GH352](#), [GH359](#).

v0.6.4 (January 6, 2016)

API changes

None

Enhancements

- Quickstart: It's now easier than ever to start a new xlwings project, simply use the command line client ([GH306](#)):

`xlwings quickstart myproject` will produce a folder with the following files, ready to be used (see *Command Line Client (CLI)*):

```
myproject
|--myproject.xlsm
|--myproject.py
```

- New documentation about how to use xlwings with other languages like R and Julia.

Bug Fixes

- [Win]: Importing UDFs with the add-in was throwing an error if the filename was including characters like spaces or dashes ([GH331](#)). To fix this, close Excel completely and run `xlwings addin update`.
- [Win]: `Workbook.caller()` is now also accessible within functions that are decorated with `@xlfunc`. Previously, it was only available with functions that used the `@xlsub` decorator ([GH316](#)).
- Writing a Pandas DataFrame failed in case the index was named the same as a column ([GH334](#)).

v0.6.3 (December 18, 2015)

Bug Fixes

- [Mac]: This fixes a bug introduced in v0.6.2: When using `RunPython` from VBA, errors were not shown in a pop-up window ([GH330](#)).

v0.6.2 (December 15, 2015)

API changes

- `LOG_FILE`: So far, the log file has been placed next to the Excel file per default (VBA settings). This has been changed as it was causing issues for files on SharePoint/OneDrive and Mac Excel 2016: The place where `LOG_FILE = ""` refers to depends on the OS and the Excel version.

Enhancements

- [Mac]: This version adds support for the VBA module on Mac Excel 2016 (i.e. the `RunPython` command) and is now feature equivalent with Mac Excel 2011 ([GH206](#)).

Bug Fixes

- [Win]: On certain systems, the xlwings dlls weren't found ([GH323](#)).

v0.6.1 (December 4, 2015)

Bug Fixes

- [Python 3]: The command line client has been fixed ([GH319](#)).
- [Mac]: It now works correctly with `psutil>=3.0.0` ([GH315](#)).

v0.6.0 (November 30, 2015)

API changes

None

Enhancements

- **User Defined Functions (UDFs) - currently Windows only**

The [ExcelPython](#) project has been fully merged into xlwings. This means that on Windows, UDF's are now supported via decorator syntax. A simple example:

```
from xlwings import xlfunc

@xlfunc
def double_sum(x, y):
    """Returns twice the sum of the two arguments"""
    return 2 * (x + y)
```

For **array formulas** with or without **NumPy**, see the docs: *User Defined Functions (UDFs)*

- **Command Line Client**

The new xlwings command line client makes it easy to work with the xlwings **template** and the developer **add-in** (the add-in is currently Windows-only). E.g. to create a new Excel spreadsheet from the template, run:

```
xlwings template open
```

For all commands, see the docs: *Command Line Client (CLI)*

- **Other enhancements:**

- New method: `xlwings.Sheet.delete()`
- New method: `xlwings.Range.top()`
- New method: `xlwings.Range.left()`

v0.5.0 (November 10, 2015)

API changes


None

Enhancements

This version adds support for Matplotlib! Matplotlib figures can be shown in Excel as pictures in just 2 lines of code:

1) Get a matplotlib figure object:

- via PyPlot interface:



```
import matplotlib.pyplot as plt
fig = plt.figure()
plt.plot([1, 2, 3, 4, 5])
```

- via object oriented interface:

```
from matplotlib.figure import Figure
fig = Figure(figsize=(8, 6))
ax = fig.add_subplot(111)
ax.plot([1, 2, 3, 4, 5])
```

- via Pandas:

```
import pandas as pd
import numpy as np

df = pd.DataFrame(np.random.rand(10, 4), columns=['a', 'b', 'c', 'd'])
ax = df.plot(kind='bar')
fig = ax.get_figure()
```

- 2) Show it in Excel as picture:

```
plot = Plot(fig)
plot.show('Plot1')
```

See the full API: `xlwings.Plot()`. There's also a new example available both on [GitHub](#) and as download on the [homepage](#).

Other enhancements:

- New `xlwings.Shape()` class
- New `xlwings.Picture()` class
- The PYTHONPATH in the VBA settings now accepts multiple directories, separated by ; ([GH258](#))
- An explicit exception is raised when Range is called with 0-based indices ([GH106](#))

Bug Fixes

- `Sheet.add` was not always acting on the correct workbook ([GH287](#))
- Iteration over a Range only worked the first time ([GH272](#))
- [Win]: Sometimes, an error was raised when Excel was not running ([GH269](#))
- [Win]: Non-default Python interpreters (as specified in the VBA settings under PYTHON_WIN) were not found if the path contained a space ([GH257](#))

v0.4.1 (September 27, 2015)

API changes

None

Enhancements

This release makes it easier than ever to connect to Excel from Python! In addition to the existing ways, you can now connect to the active Workbook (on Windows across all instances) and if the Workbook is already open, it's good enough to refer to it by name (instead of having to use the full path). Accordingly, this is how you make a connection to... ([GH30](#) and [GH226](#)):

- a new workbook: `wb = Workbook()`
- the active workbook [New!]: `wb = Workbook.active()`
- an unsaved workbook: `wb = Workbook('Book1')`
- a saved (open) workbook by name (incl. xlsx etc.) [New!]: `wb = Workbook('MyWorkbook.xlsx')`
- a saved (open or closed) workbook by path: `wb = Workbook(r'C:\\path\\to\\file.xlsx')`

Also, there are some new docs:

- [Connect to a Book](#)
- [Missing Features](#)

Bug Fixes

- The Excel template was updated to the latest VBA code ([GH234](#)).
- Connections to files that are saved on OneDrive/SharePoint are now working correctly ([GH215](#)).
- Various issues with timezone-aware objects were fixed ([GH195](#)).
- [Mac]: A certain range of integers were not written to Excel ([GH227](#)).

v0.4.0 (September 13, 2015)

API changes

None

Enhancements

The most important update with this release was made on Windows: The methodology used to make a connection to Workbooks has been completely replaced. This finally allows xlwings to reliably connect to multiple instances of Excel even if the Workbooks are opened from untrusted locations (network drives or files downloaded from the internet). This gets rid of the dreaded `Filename is already open...` error message that was sometimes shown in this context. It also allows the VBA hooks (`RunPython`) to work correctly if the very same file is opened in various instances of Excel.

Note that you will need to update the VBA module and that apart from `pywin32` there is now a new dependency for the Windows version: `comtypes`. It should be installed automatically though when installing/upgrading xlwings with `pip`.

Other updates:

- Added support to manipulate named Ranges ([GH92](#)):

```
>>> wb = Workbook()
>>> Range('A1').name = 'Name1'
>>> Range('A1').name
>>> 'Name1'
>>> del wb.names['Name1']
```

- New Range properties ([GH81](#)):

- `xlwings.Range.column_width()`
- `xlwings.Range.row_height()`
- `xlwings.Range.width()`
- `xlwings.Range.height()`

- Range now also accepts Sheet objects, the following 3 ways are hence all valid ([GH92](#)):

```
r = Range(1, 'A1')
r = Range('Sheet1', 'A1')
sheet1 = Sheet(1)
r = Range(sheet1, 'A1')
```

- [Win]: Error pop-ups show now the full error message that can also be copied with `Ctrl-C` ([GH221](#)).

Bug Fixes

- The VBA module was not accepting lower case drive letters ([GH205](#)).
- Fixed an error when adding a new Sheet that was already existing ([GH211](#)).

v0.3.6 (July 14, 2015)

API changes

Application as attribute of a Workbook has been removed (`wb` is a Workbook object):

Correct Syntax (as before)	Removed
Application(wkb=wb)	wb.application

Enhancements

Excel 2016 for Mac Support (GH170)

Excel 2016 for Mac is finally supported (Python side). The VBA hooks (RunPython) are currently not yet supported. In more details:

- This release allows Excel 2011 and Excel 2016 to be installed in parallel.
- `Workbook()` will open the default Excel installation (usually Excel 2016).
- The new keyword argument `app_target` allows to connect to a different Excel installation, e.g.:

```
Workbook(app_target='/Applications/Microsoft Office 2011/Microsoft Excel')
```

Note that `app_target` is only available on Mac. On Windows, if you want to change the version of Excel that xlwings talks to, go to Control Panel > Programs and Features and Repair the Office version that you want as default.

- The RunPython calls in VBA are not yet available through Excel 2016 but Excel 2011 doesn't get confused anymore if Excel 2016 is installed on the same system - make sure to update your VBA module!

Other enhancements

- New method: `xlwings.Application.calculate()` (GH207)

Bug Fixes

- [Win]: When using the `OPTIMIZED_CONNECTION` on Windows, Excel left an orphaned process running after closing (GH193).

Various improvements regarding unicode file path handling, including:

- [Mac]: Excel 2011 for Mac now supports unicode characters in the filename when called via VBA's RunPython (but not in the path - this is a limitation of Excel 2011 that will be resolved in Excel 2016) (GH154).
- [Win]: Excel on Windows now handles unicode file paths correctly with untrusted documents. (GH154).

v0.3.5 (April 26, 2015)

API changes

`Sheet.autofit()` and `Range.autofit()`: The integer argument for the axis has been removed (GH186). Use string arguments `rows` or `r` for autofitting rows and `columns` or `c` for autofitting columns (as before).

Enhancements

New methods:

- `xlwings.Range.row()` (GH143)

- `xlwings.Range.column()` (GH143)
- `xlwings.Range.last_cell()` (GH142)

Example:

```
>>> rng = Range('A1').table
>>> rng.row, rng.column
(1, 1)
>>> rng.last_cell.row, rng.last_cell.column
(4, 5)
```

Bug Fixes

- The unicode bug on Windows/Python3 has been fixed (GH161)

v0.3.4 (March 9, 2015)

Bug Fixes

- The installation error on Windows has been fixed (GH160)

v0.3.3 (March 8, 2015)

API changes

None

Enhancements

- New class `Application` with `quit` method and properties `screen_updating` und `calculation` (GH101, GH158, GH159). It can be conveniently accessed from within a `Workbook` (on Windows, `Application` is instance dependent). A few examples:

```
>>> from xlwings import Workbook, Calculation
>>> wb = Workbook()
>>> wb.application.screen_updating = False
>>> wb.application.calculation = Calculation.xlCalculationManual
>>> wb.application.quit()
```

- New headless mode: The Excel application can be hidden either during `Workbook` instantiation or through the application object:

```
>>> wb = Workbook(app_visible=False)
>>> wb.application.visible
False
>>> wb.application.visible = True
```

- Newly included Excel template which includes the `xlwings` VBA module and boilerplate code. This is currently accessible from an interactive interpreter session only:

```
>>> from xlwings import Workbook
>>> Workbook.open_template()
```


Bug Fixes

- [Win]: `datetime.date` objects were causing an error ([GH44](#)).
- Depending on how it was instantiated, `Workbook` was sometimes missing the `fullname` attribute ([GH76](#)).
- `Range.hyperlink` was failing if the hyperlink had been set as formula ([GH132](#)).
- A bug introduced in v0.3.0 caused frozen versions (eg. with `cx_Freeze`) to fail ([GH133](#)).
- [Mac]: Sometimes, `xlwings` was causing an error when quitting the Python interpreter ([GH136](#)).

v0.3.2 (January 17, 2015)

API changes

None

Enhancements

None

Bug Fixes

- The `xlwings.Workbook.save()` method has been fixed to show the expected behavior ([GH138](#)): Previously, calling `save()` without a *path* argument would always create a new file in the current working directory. This is now only happening if the file hasn't been previously saved.

v0.3.1 (January 16, 2015)

API changes

None

Enhancements

- New method `xlwings.Workbook.save()` ([GH110](#)).
- New method `xlwings.Workbook.set_mock_caller()` ([GH129](#)). This makes calling files from both Excel and Python much easier:

```
import os
from xlwings import Workbook, Range

def my_macro():
    wb = Workbook.caller()
    Range('A1').value = 1

if __name__ == '__main__':
    # To run from Python, not needed when called from Excel.
    # Expects the Excel file next to this source file, adjust accordingly.
    path = os.path.abspath(os.path.join(os.path.dirname(__file__), 'myfile.
    ↪xlsm'))
    Workbook.set_mock_caller(path)
    my_macro()
```

- The simulation example on the homepage works now also on Mac.

Bug Fixes

- [Win]: A long-standing bug that caused the Excel file to close and reopen under certain circumstances has been fixed ([GH10](#)): Depending on your security settings (Trust Center) and in connection with files downloaded from the internet or possibly in connection with some add-ins, Excel was either closing the file and reopening it or giving a “file already open” warning. This has now been fixed which means that the examples downloaded from the homepage should work right away after downloading and unzipping.

v0.3.0 (November 26, 2014)

API changes

- To reference the calling Workbook when running code from VBA, you now have to use `Workbook.caller()`. This means that `wb = Workbook()` is now consistently creating a new Workbook, whether the code is called interactively or from VBA.

New	Old
<code>Workbook.caller()</code>	<code>Workbook()</code>

Enhancements

This version adds two exciting but still **experimental** features from *ExcelPython* (**Windows only!**):

- Optimized connection: Set the `OPTIMIZED_CONNECTION = True` in the VBA settings. This will use a COM server that will keep the connection to Python alive between different calls and is therefore much more efficient. However, changes in the Python code are not being picked up until the `pythonw.exe` process is restarted by killing it manually in the Windows Task Manager. The suggested workflow is hence to set `OPTIMIZED_CONNECTION = False` for development and only set it to `True` for production - keep in mind though that this feature is still experimental!
- User Defined Functions (UDFs): Using ExcelPython’s wrapper syntax in VBA, you can expose Python functions as UDFs, see [User Defined Functions \(UDFs\)](#) for details.

Note: ExcelPython’s developer add-in that autogenerates the VBA wrapper code by simply using Python decorators isn’t available through xlwings yet.

Further enhancements include:

- New method `xlwings.Range.resize()` ([GH90](#)).
- New method `xlwings.Range.offset()` ([GH89](#)).
- New property `xlwings.Range.shape` ([GH109](#)).
- New property `xlwings.Range.size` ([GH109](#)).
- New property `xlwings.Range.hyperlink` and new method `xlwings.Range.add_hyperlink()` ([GH104](#)).
- New property `xlwings.Range.color` ([GH97](#)).
- The `len` built-in function can now be used on Range ([GH109](#)):

```
>>> len(Range('A1:B5'))
5
```

- The Range object is now iterable ([GH108](#)):

```
for cell in Range('A1:B2'):
    if cell.value < 2:
        cell.color = (255, 0, 0)
```

- [Mac]: The VBA module finds now automatically the default Python installation as per PATH variable on .bash_profile when PYTHON_MAC = "" (the default in the VBA settings) ([GH95](#)).
- The VBA error pop-up can now be muted by setting SHOW_LOG = False in the VBA settings. To be used with care, but it can be useful on Mac, as the pop-up window is currently showing printed log messages even if no error occurred([GH94](#)).

Bug Fixes

- [Mac]: Environment variables from .bash_profile are now available when called from VBA, e.g. by using: os.environ['USERNAME'] ([GH95](#))

v0.2.3 (October 17, 2014)

API changes

None

Enhancements

- New method Sheet.add() ([GH71](#)):

```
>>> Sheet.add() # Place at end with default name
>>> Sheet.add('NewSheet', before='Sheet1') # Include name and position
>>> new_sheet = Sheet.add(after=3)
>>> new_sheet.index
4
```

- New method Sheet.count():

```
>>> Sheet.count()
3
```

- autofit() works now also on Sheet objects, not only on Range objects ([GH66](#)):

```
>>> Sheet(1).autofit() # autofit columns and rows
>>> Sheet('Sheet1').autofit('c') # autofit columns
```

- New property number_format for Range objects ([GH60](#)):

```
>>> Range('A1').number_format
'General'
```

(continues on next page)

(continued from previous page)

```
>>> Range('A1:C3').number_format = '0.00%'
>>> Range('A1:C3').number_format
'0.00%'
```

Works also with the Range properties table, vertical, horizontal:

```
>>> Range('A1').value = [1,2,3,4,5]
>>> Range('A1').table.number_format = '0.00%'
```

- New method `get_address` for Range objects (GH7):

```
>>> Range((1,1)).get_address()
'$A$1'
>>> Range((1,1)).get_address(False, False)
'A1'
>>> Range('Sheet1', (1,1), (3,3)).get_address(True, False, include_
↳ sheetname=True)
'Sheet1!A$1:C$3'
>>> Range('Sheet1', (1,1), (3,3)).get_address(True, False, external=True)
'[Workbook1]Sheet1!A$1:C$3'
```

- New method `Sheet.all()` returning a list with all Sheet objects:

```
>>> Sheet.all()
[<Sheet 'Sheet1' of Workbook 'Book1'>, <Sheet 'Sheet2' of Workbook 'Book1'>]
>>> [i.name.lower() for i in Sheet.all()]
['sheet1', 'sheet2']
>>> [i.autofit() for i in Sheet.all()]
```

Bug Fixes

- xlwings works now also with NumPy < 1.7.0. Before, doing something like `Range('A1').value = 'Foo'` was causing a `NotImplementedError: Not implemented for this type error` when NumPy < 1.7.0 was installed (GH73).
- [Win]: The VBA module caused an error on the 64bit version of Excel (GH72).
- [Mac]: The error pop-up wasn't shown on Python 3 (GH85).
- [Mac]: Autofitting bigger Ranges, e.g. `Range('A:D').autofit()` was causing a time out (GH74).
- [Mac]: Sometimes, calling xlwings from Python was causing Excel to show old errors as pop-up alert (GH70).

v0.2.2 (September 23, 2014)

API changes

- The `Workbook` qualification changed: It now has to be specified as keyword argument. Assume we have instantiated two `Workbooks` like so: `wb1 = Workbook()` and `wb2 = Workbook()`. `Sheet`,

Range and Chart classes will default to wb2 as it was instantiated last. To target wb1, use the new wkb keyword argument:

New	Old
Range('A1', wkb=wb1).value	wb1.range('A1').value
Chart('Chart1', wkb=wb1)	wb1.chart('Chart1')

Alternatively, simply set the current Workbook before using the Sheet, Range or Chart classes:

```
wb1.set_current()
Range('A1').value
```

- Through the introduction of the Sheet class (see Enhancements), a few methods moved from the Workbook to the Sheet class. Assume the current Workbook is: `wb = Workbook()`:


New	Old
Sheet('Sheet1').activate()	wb.activate('Sheet1')
Sheet('Sheet1').clear()	wb.clear('Sheet1')
Sheet('Sheet1').clear_contents()	wb.clear_contents('Sheet1')
Sheet.active().clear_contents()	wb.clear_contents()

- The syntax to add a new Chart has been slightly changed (it is a class method now):

New	Old
Chart.add()	Chart().add()

Enhancements

- [Mac]: Python errors are now also shown in a Message Box. This makes the Mac version feature equivalent with the Windows version ([GH57](#)):



- New Sheet class: The new class handles everything directly related to a Sheet. See the Python API section about Sheet for details ([GH62](#)). A few examples:

```
>>> Sheet(1).name
'Sheet1'
>>> Sheet('Sheet1').clear_contents()
>>> Sheet.active()
<Sheet 'Sheet1' of Workbook 'Book1'>
```

- The Range class has a new method `autofit()` that autofits the width/height of either columns, rows or both (GH33).

Arguments:

```
axis : string or integer, default None
    - To autofit rows, use one of the following: 'rows' or 'r'
    - To autofit columns, use one of the following: 'columns' or 'c'
    - To autofit rows and columns, provide no arguments
```

Examples:

```
# Autofit column A
Range('A:A').autofit()
# Autofit row 1
Range('1:1').autofit()
# Autofit columns and rows, taking into account Range('A1:E4')
Range('A1:E4').autofit()
# AutoFit rows, taking into account Range('A1:E4')
Range('A1:E4').autofit('rows')
```

- The Workbook class has the following additional methods: `current()` and `set_current()`. They determine the default Workbook for Sheet, Range or Chart. On Windows, in case there are various Excel instances, when creating new or opening existing Workbooks, they are being created in the same instance as the current Workbook.

```
>>> wb1 = Workbook()
>>> wb2 = Workbook()
>>> Workbook.current()
<Workbook 'Book2'>
>>> wb1.set_current()
>>> Workbook.current()
<Workbook 'Book1'>
```

- If a Sheet, Range or Chart object is instantiated without an existing Workbook object, a user-friendly error message is raised (GH58).
- New docs about [Debugging](#) and [Data Structures Tutorial](#).

Bug Fixes

- The `atleast_2d` keyword had no effect on Ranges consisting of a single cell and was raising an error when used in combination with the `asarray` keyword. Both have been fixed (GH53):

```
>>> Range('A1').value = 1
>>> Range('A1', at_least_2d=True).value
[[1.0]]
>>> Range('A1', at_least_2d=True, asarray=True).value
array([[1.]])
```

- [Mac]: After creating two new unsaved Workbooks with `Workbook()`, any `Sheet`, `Range` or `Chart` object would always just access the latest one, even if the `Workbook` had been specified (GH63).
- [Mac]: When `xlwings` was imported without ever instantiating a `Workbook` object, Excel would start upon quitting the Python interpreter (GH51).
- [Mac]: When installing `xlwings`, it now requires `psutil` to be at least version 2.0.0 (GH48).

v0.2.1 (August 7, 2014)

API changes

None

Enhancements

- All VBA user settings have been reorganized into a section at the top of the VBA `xlwings` module:

```
PYTHON_WIN = ""
PYTHON_MAC = GetMacDir("Home") & "/anaconda/bin"
PYTHON_FROZEN = ThisWorkbook.Path & "\\build\\exe.win32-2.7"
PYTHONPATH = ThisWorkbook.Path
LOG_FILE = ThisWorkbook.Path & "\\xlwings_log.txt"
```

- Calling Python from within Excel VBA is now also supported on Mac, i.e. Python functions can be called like this: `RunPython("import bar; bar.foo()")`. Running frozen executables (`RunFrozenPython`) isn't available yet on Mac though.

Note that there is a slight difference in the way that this functionality behaves on Windows and Mac:

- **Windows:** After calling the Macro (e.g. by pressing a button), Excel waits until Python is done. In case there's an error in the Python code, a pop-up message is being shown with the traceback.
- **Mac:** After calling the Macro, the call returns instantly but Excel's Status Bar turns into "Running..." during the duration of the Python call. Python errors are currently not shown as a pop-up, but need to be checked in the log file. I.e. if the Status Bar returns to its default ("Ready") but nothing has happened, check out the log file for the Python traceback.

Bug Fixes

None

Special thanks go to Georgi Petrov for helping with this release.

v0.2.0 (July 29, 2014)

API changes

None

Enhancements

- Cross-platform: xlwings is now additionally supporting Microsoft Excel for Mac. The only functionality that is not yet available is the possibility to call the Python code from within Excel via VBA macros.
- The `clear` and `clear_contents` methods of the `Workbook` object now default to the active sheet (GH5):

```
wb = Workbook()
wb.clear_contents() # Clears contents of the entire active sheet
```

Bug Fixes

- DataFrames with MultiHeaders were sometimes getting truncated (GH41).

v0.1.1 (June 27, 2014)

API Changes

- If `asarray=True`, NumPy arrays are now always at least 1d arrays, even in the case of a single cell (GH14):

```
>>> Range('A1', asarray=True).value
array([34.])
```

- Similar to NumPy's logic, 1d Ranges in Excel, i.e. rows or columns, are now being read in as flat lists or 1d arrays. If you want the same behavior as before, you can use the `atleast_2d` keyword (GH13).

Note: The `table` property is also delivering a 1d array/list, if the table Range is really a column or row.

	A	B	C	D	E	F
1	1		1	2	3	4
2	2					
3	3					
4	4					
5						

```
>>> Range('A1').vertical.value
[1.0, 2.0, 3.0, 4.0]
>>> Range('A1', atleast_2d=True).vertical.value
[[1.0], [2.0], [3.0], [4.0]]
>>> Range('C1').horizontal.value
[1.0, 2.0, 3.0, 4.0]
>>> Range('C1', atleast_2d=True).horizontal.value
[[1.0, 2.0, 3.0, 4.0]]
>>> Range('A1', asarray=True).table.value
```

(continues on next page)

(continued from previous page)

```
array([ 1.,  2.,  3.,  4.])
>>> Range('A1', asarray=True, atleast_2d=True).table.value
array([[ 1.],
       [ 2.],
       [ 3.],
       [ 4.]])
```

- The single file approach has been dropped. xlwings is now a traditional Python package.

Enhancements

- xlwings is now officially supported on Python 2.6-2.7 and 3.1-3.4
- Support for Pandas Series has been added (GH24):

```
>>> import numpy as np
>>> import pandas as pd
>>> from xlwings import Workbook, Range
>>> wb = Workbook()
>>> s = pd.Series([1.1, 3.3, 5., np.nan, 6., 8.])
>>> s
0    1.1
1    3.3
2    5.0
3    NaN
4    6.0
5    8.0
dtype: float64
>>> Range('A1').value = s
>>> Range('D1', index=False).value = s
```

	A	B	C	D
1	0	1.1		1.1
2	1	3.3		3.3
3	2	5		5
4	3			
5	4	6		6
6	5	8		8
7				

- Excel constants have been added under their original Excel name, but categorized under their enum (GH18), e.g.:

```
# Extra long version
import xlwings as xl
xl.constants.ChartType.xlArea
```

(continues on next page)

(continued from previous page)

```
# Long version
from xlwings import constants
constants.ChartType.xlArea


# Short version
from xlwings import ChartType
ChartType.xlArea
```

- Slightly enhanced Chart support to control the ChartType (GH1):

```
>>> from xlwings import Workbook, Range, Chart, ChartType
>>> wb = Workbook()
>>> Range('A1').value = [['one', 'two'],[10, 20]]
>>> my_chart = Chart().add(chart_type=ChartType.xlLine,
                           name='My Chart',
                           source_data=Range('A1').table)
```

alternatively, the properties can also be set like this:

```
>>> my_chart = Chart().add() # Existing Charts: my_chart = Chart('My Chart')
>>> my_chart.name = 'My Chart'
>>> my_chart.chart_type = ChartType.xlLine
>>> my_chart.set_source_data(Range('A1').table)
```



- `pytz` is no longer a dependency as `datetime` objects are now being read in from Excel as time-zone naive (Excel doesn't know timezones). Before, `datetime` objects got the UTC timezone attached.
- The `Workbook` class has the following additional methods: `close()`
- The `Range` class has the following additional methods: `is_cell()`, `is_column()`, `is_row()`, `is_table()`

Bug Fixes

- Writing `None` or `np.nan` to Excel works now ([GH16](#) & [GH15](#)).
- The import error on Python 3 has been fixed ([GH26](#)).
- Python 3 now handles Pandas DataFrames with MultiIndex headers correctly ([GH39](#)).
- Sometimes, a Pandas DataFrame was not handling `nan` correctly in Excel or numbers were being truncated ([GH31](#)) & ([GH35](#)).
- Installation is now putting all files in the correct place ([GH20](#)).

v0.1.0 (March 19, 2014)

Initial release of xlwings.

31.1 xlwings (Open Source)

xlwings (Open Source) is distributed under a BSD-3-Clause license. xlwings (Open Source) includes all files in the xlwings package except the `pro` folder, i.e., the `xlwings.pro` subpackage.

- [xlwings \(Open Source\) License](#)

31.2 xlwings PRO

xlwings PRO is [source available](#) and dual-licensed under one of the following licenses:

- [PolyForm Noncommercial License 1.0.0](#) (noncommercial use is free)
- [xlwings PRO License](#) (commercial use requires a [paid plan](#))

OPEN SOURCE LICENSES

Depending on the platform and features that you use, xlwings requires various Open Source dependencies.

- The licenses of the compiled code are available in a [separate document](#)
- All other licenses are listed below

32.1 pywin32 (Windows only)

com subpackage

Unless stated in the specific source file, this work is Copyright (c) 1996-2008, Greg Stein and Mark Hammond. All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.

Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.

Neither names of Greg Stein, Mark Hammond nor the name of contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS ‘AS IS’ AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE REGENTS OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

win32 subpackage

Unless stated in the specific source file, this work is Copyright (c) 1994-2008, Mark Hammond All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.

Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.

Neither name of Mark Hammond nor the name of contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS "AS IS" AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE REGENTS OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

Pythonwin subpackage

Unless stated in the specific source file, this work is Copyright (c) 1994-2008, Mark Hammond All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.

Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.

Neither name of Mark Hammond nor the name of contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS "AS IS" AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE REGENTS OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

32.2 psutil (macOS only)

BSD 3-Clause License

Copyright (c) 2009, Jay Loden, Dave Daeschler, Giampaolo Rodola' All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

- Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.
- Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.
- Neither the name of the psutil authors nor the names of its contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS "AS IS" AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE COPYRIGHT OWNER OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

32.3 Appscript (macOS only)

Appscript is released into the public domain, except for the following code:

- portions of ae.c, which are Copyright (C) the original authors:
Original code taken from _AEmodule.c, _CFmodule.c, _Launchmodule.c
Copyright (C) 2001-2008 Python Software Foundation.
License: <https://docs.python.org/3/license.html>.
- SendThreadSafe.h/SendThreadSafe.m, which are modified versions of Apple code (<https://developer.apple.com/library/archive/samplecode/AESendThreadSafe/>):
Written by: DTS
Copyright: Copyright (c) 2007 Apple Inc. All Rights Reserved.
Disclaimer: IMPORTANT: This Apple software is supplied to you by Apple Inc.

("Apple") in consideration of your agreement to the following terms, and your use, installation, modification or redistribution of this Apple software constitutes acceptance of these terms. If you do not agree with these terms, please do not use, install, modify or redistribute this Apple software. In consideration of your agreement to abide by the following terms, and subject to these terms, Apple grants you a personal, non-exclusive license, under Apple's copyrights in this original Apple software (the

“Apple Software”), to use, reproduce, modify and redistribute the Apple Software, with or without modifications, in source and/or binary forms; provided that if you redistribute the Apple Software in its entirety and without modifications, you must retain this notice and the following text and disclaimers in all such redistributions of the Apple Software. Neither the name, trademarks, service marks or logos of Apple Inc. may be used to endorse or promote products derived from the Apple Software without specific prior written permission from Apple. Except as expressly stated in this notice, no other rights or licenses, express or implied, are granted by Apple herein, including but not limited to any patent rights that may be infringed by your derivative works or by other works in which the Apple Software may be incorporated. The Apple Software is provided by Apple on an “AS IS” basis.

APPLE MAKES NO WARRANTIES, EXPRESS OR IMPLIED, INCLUDING WITHOUT LIMITATION THE IMPLIED WARRANTIES OF NON-INFRINGEMENT, MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, REGARDING THE APPLE SOFTWARE OR ITS USE AND OPERATION ALONE OR IN COMBINATION WITH YOUR PRODUCTS. IN NO EVENT SHALL APPLE BE LIABLE FOR ANY SPECIAL, INDIRECT, INCIDENTAL OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) ARISING IN ANY WAY OUT OF THE USE, REPRODUCTION, MODIFICATION AND/OR DISTRIBUTION OF THE APPLE SOFTWARE, HOWEVER CAUSED AND WHETHER UNDER THEORY OF CONTRACT, TORT (INCLUDING NEGLIGENCE), STRICT LIABILITY OR OTHERWISE, EVEN IF APPLE HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

32.4 Mistune

BSD 3-Clause License

Copyright (c) 2014, Hsiaoming Yang

All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

- Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.
- Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.
- Neither the name of the creator nor the names of its contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS “AS IS” AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE COPYRIGHT HOLDER OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY,

OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

32.5 VBA-Dictionary

The MIT License (MIT)

Copyright (c) 2020 Tim Hall

Permission is hereby granted, free of charge, to any person obtaining a copy of this software and associated documentation files (the “Software”), to deal in the Software without restriction, including without limitation the rights to use, copy, modify, merge, publish, distribute, sublicense, and/or sell copies of the Software, and to permit persons to whom the Software is furnished to do so, subject to the following conditions:

The above copyright notice and this permission notice shall be included in all copies or substantial portions of the Software.

THE SOFTWARE IS PROVIDED “AS IS”, WITHOUT WARRANTY OF ANY KIND, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO THE WARRANTIES OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE AND NONINFRINGEMENT. IN NO EVENT SHALL THE AUTHORS OR COPYRIGHT HOLDERS BE LIABLE FOR ANY CLAIM, DAMAGES OR OTHER LIABILITY, WHETHER IN AN ACTION OF CONTRACT, TORT OR OTHERWISE, ARISING FROM, OUT OF OR IN CONNECTION WITH THE SOFTWARE OR THE USE OR OTHER DEALINGS IN THE SOFTWARE.

32.6 VBA-Web

The MIT License (MIT)

Copyright (c) 2016-2019 Tim Hall

Permission is hereby granted, free of charge, to any person obtaining a copy of this software and associated documentation files (the “Software”), to deal in the Software without restriction, including without limitation the rights to use, copy, modify, merge, publish, distribute, sublicense, and/or sell copies of the Software, and to permit persons to whom the Software is furnished to do so, subject to the following conditions:

The above copyright notice and this permission notice shall be included in all copies or substantial portions of the Software.

THE SOFTWARE IS PROVIDED “AS IS”, WITHOUT WARRANTY OF ANY KIND, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO THE WARRANTIES OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE AND NONINFRINGEMENT. IN NO EVENT SHALL THE AUTHORS OR COPYRIGHT HOLDERS BE LIABLE FOR ANY CLAIM, DAMAGES OR OTHER LIABILITY, WHETHER IN AN ACTION OF CONTRACT, TORT OR OTHERWISE, ARISING FROM, OUT OF OR IN CONNECTION WITH THE SOFTWARE OR THE USE OR OTHER DEALINGS IN THE SOFTWARE.

33.1 Top-level functions

`xlwings.load(index=1, header=1, chunksize=5000)`

Loads the selected cell(s) of the active workbook into a pandas DataFrame. If you select a single cell that has adjacent cells, the range is auto-expanded (via current region) and turned into a pandas DataFrame. If you don't have pandas installed, it returns the values as nested lists.

Note: Only use this in an interactive context like e.g. a Jupyter notebook! Don't use this in a script as it depends on the active book.

Parameters

- **index** (*bool or int, default 1*) – Defines the number of columns on the left that will be turned into the DataFrame's index
- **header** (*bool or int, default 1*) – Defines the number of rows at the top that will be turned into the DataFrame's columns
- **chunksize** (*int, default 5000*) – Chunks the loading of big arrays.

Examples

```
>>> import xlwings as xw
>>> xw.load()
```

See also: `view`

Changed in version 0.23.1.

`xlwings.view(obj, sheet=None, table=True, chunksize=5000)`

Opens a new workbook and displays an object on its first sheet by default. If you provide a sheet object, it will clear the sheet before displaying the object on the existing sheet.

Note: Only use this in an interactive context like e.g., a Jupyter notebook! Don't use this in a script as it depends on the active book.

Parameters

- **obj** (*any type with built-in converter*) – the object to display, e.g. numbers, strings, lists, numpy arrays, pandas DataFrames
- **sheet** (*Sheet*, *default None*) – Sheet object. If none provided, the first sheet of a new workbook is used.
- **table** (*bool*, *default True*) – If your object is a pandas DataFrame, by default it is formatted as an Excel Table
- **chunksize** (*int*, *default 5000*) – Chunks the loading of big arrays.

Examples

```
>>> import xlwings as xw
>>> import pandas as pd
>>> import numpy as np
>>> df = pd.DataFrame(np.random.rand(10, 4), columns=['a', 'b', 'c', 'd'])
>>> xw.view(df)
```

See also: [load](#)

Changed in version 0.22.0.

33.2 Object model

33.2.1 Apps

class xlwings.main.Apps(*impl*)

A collection of all [app](#) objects:

```
>>> import xlwings as xw
>>> xw.apps
Apps([<Excel App 1668>, <Excel App 1644>])
```

property active

Returns the active app.

New in version 0.9.0.

add(***kwargs*)

Creates a new App. The new App becomes the active one. Returns an App object.

property count

Returns the number of apps.

New in version 0.9.0.

keys()

Provides the PIDs of the Excel instances that act as keys in the Apps collection.

New in version 0.13.0.

33.2.2 App

class `xlwings.App(visible=None, spec=None, add_book=True, impl=None)`

An app corresponds to an Excel instance and should normally be used as context manager to make sure that everything is properly cleaned up again and to prevent zombie processes. New Excel instances can be fired up like so:

```
import xlwings as xw

with xw.App() as app:
    print(app.books)
```

An app object is a member of the `apps` collection:

```
>>> xw.apps
Apps([<Excel App 1668>, <Excel App 1644>])
>>> xw.apps[1668] # get the available PIDs via xw.apps.keys()
<Excel App 1668>
>>> xw.apps.active
<Excel App 1668>
```

Parameters

- **visible** (*bool*, *default None*) – Returns or sets a boolean value that determines whether the app is visible. The default leaves the state unchanged or sets `visible=True` if the object doesn't exist yet.
- **spec** (*str*, *default None*) – Mac-only, use the full path to the Excel application, e.g. `/Applications/Microsoft Office 2011/Microsoft Excel` or `/Applications/Microsoft Excel`

On Windows, if you want to change the version of Excel that xlwings talks to, go to **Control Panel > Programs and Features** and **Repair** the Office version that you want as default.

Note: On Mac, while xlwings allows you to run multiple instances of Excel, it's a feature that is not officially supported by Excel for Mac: Unlike on Windows, Excel will not ask you to open a read-only

version of a file if it is already open in another instance. This means that you need to watch out yourself so that the same file is not being overwritten from different instances.

activate(*steal_focus=False*)

Activates the Excel app.

Parameters

steal_focus (*bool*, *default False*) – If True, make frontmost application and hand over focus from Python to Excel.

New in version 0.9.0.

alert(*prompt*, *title=None*, *buttons='ok'*, *mode=None*, *callback=None*)

This corresponds to `MsgBox` in VBA, shows an alert/message box and returns the value of the pressed button. For the remote interpreter, instead of returning a value, the function accepts the name of a callback to which it will supply the value of the pressed button.

Parameters

- **prompt** (*str*, *default None*) – The message to be displayed.
- **title** (*str*, *default None*) – The title of the alert.
- **buttons** (*str*, *default "ok"*) – Can be either "ok", "ok_cancel", "yes_no", or "yes_no_cancel".
- **mode** (*str*, *default None*) – Can be "info" or "critical". Not supported by Google Sheets.
- **callback** (*str*, *default None*) – Only used by the remote interpreter: you can provide the name of a function that will be called with the value of the pressed button as argument. The function has to exist on the client side, i.e., in VBA or JavaScript.

Returns

button_value – Returns `None` when used with the remote interpreter, otherwise the value of the pressed button in lowercase: "ok", "cancel", "yes", "no".

Return type

str or None

New in version 0.27.13.

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.9.0.

property books

A collection of all Book objects that are currently open.

New in version 0.9.0.

calculate()

Calculates all open books.

New in version 0.3.6.

property calculation

Returns or sets a calculation value that represents the calculation mode. Modes: 'manual', 'automatic', 'semiautomatic'

Examples

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> wb.app.calculation = 'manual'
```

Changed in version 0.9.0.

property cut_copy_mode

Gets or sets the status of the cut or copy mode. Accepts False for setting and returns None, copy or cut when getting the status.

New in version 0.24.0.

property display_alerts

The default value is True. Set this property to False to suppress prompts and alert messages while code is running; when a message requires a response, Excel chooses the default response.

New in version 0.9.0.

property enable_events

True if events are enabled. Read/write boolean.

New in version 0.24.4.

property hwnd

Returns the Window handle (Windows-only).

New in version 0.9.0.

property interactive

True if Excel is in interactive mode. If you set this property to False, Excel blocks all input from the keyboard and mouse (except input to dialog boxes that are displayed by your code). Read/write Boolean. NOTE: Not supported on macOS.

New in version 0.24.4.

kill()

Forces the Excel app to quit by killing its process.

New in version 0.9.0.

macro(*name*)

Runs a Sub or Function in Excel VBA that are not part of a specific workbook but e.g. are part of an add-in.

Parameters

name (*Name of Sub or Function with or without module name,*) – e.g., 'Module1.MyMacro' or 'MyMacro'

Examples

This VBA function:

```
Function MySum(x, y)
    MySum = x + y
End Function
```

can be accessed like this:

```
>>> import xlwings as xw
>>> app = xw.App()
>>> my_sum = app.macro('MySum')
>>> my_sum(1, 2)
3
```

Types are supported too:

```
>>> import xlwings as xw
>>> app = xw.App()
>>> my_sum = app.macro('MySum')
>>> my_sum(1, 2)
3
```

However typed arrays are not supported. So the following won't work

```
Function MySum(arr() as integer)
    ' code here
End Function
```

See also: [*Book.macro\(\)*](#)

New in version 0.9.0.

property path

Returns the path to where the App is installed.

New in version 0.28.4.

property pid

Returns the PID of the app.

New in version 0.9.0.

properties(kwargs)**

Context manager that allows you to easily change the app's properties temporarily. Once the code leaves the with block, the properties are changed back to their previous state. Note: Must be used as context manager or else will have no effect. Also, you can only use app properties that you can both read and write.

Examples

```
import xlwings as xw
app = App()

# Sets app.display_alerts = False
with app.properties(display_alerts=False):
    # do stuff

# Sets app.calculation = 'manual' and app.enable_events = True
with app.properties(calculation='manual', enable_events=True):
    # do stuff

# Makes sure the status bar is reset even if an error happens in the
↪with block
with app.properties(status_bar='Calculating...'):
    # do stuff
```

New in version 0.24.4.

quit()

Quits the application without saving any workbooks.

New in version 0.3.3.

range(cell1, cell2=None)

Range object from the active sheet of the active book, see [Range\(\)](#).

New in version 0.9.0.

render_template(template=None, output=None, book_settings=None, **data)

This function requires xlwings PRO.

This is a convenience wrapper around `mysheet.render_template`

Writes the values of all key word arguments to the output file according to the template and the variables contained in there (Jinja variable syntax). Following variable types are supported: strings, numbers, lists, simple dicts, NumPy arrays, Pandas DataFrames, pictures and Matplotlib/Plotly figures.

Parameters

- **template** (*str or path-like object*) – Path to your Excel template, e.g. `r'C:\Path\to\my_template.xlsx'`

- **output** (*str or path-like object*) – Path to your Report, e.g. `r'C:\Path\to\my_report.xlsx'`
- **book_settings** (*dict, default None*) – A dictionary of xlwings. Book parameters, for details see: [xlwings.Book](#). For example: `book_settings={'update_links': False}`.
- **data** (*kwargs*) – All key/value pairs that are used in the template.

Returns

wb

Return type

xlwings Book

New in version 0.24.4.

property screen_updating

Turn screen updating off to speed up your script. You won't be able to see what the script is doing, but it will run faster. Remember to set the `screen_updating` property back to `True` when your script ends.

New in version 0.3.3.

property selection

Returns the selected cells as `Range`.

New in version 0.9.0.

property startup_path

Returns the path to XLSTART which is where the xlwings add-in gets copied to by doing `xlwings addin install`.

New in version 0.19.4.

property status_bar

Gets or sets the value of the status bar. Returns `False` if Excel has control of it.

New in version 0.20.0.

property version

Returns the Excel version number object.

Examples

```
>>> import xlwings as xw
>>> xw.App().version
VersionNumber('15.24')
>>> xw.apps[10559].version.major
15
```

Changed in version 0.9.0.

property visible

Gets or sets the visibility of Excel to True or False.

New in version 0.3.3.

33.2.3 Books

class xlwings.main.**Books**(*impl*)

A collection of all *book* objects:

```
>>> import xlwings as xw
>>> xw.books # active app
Books([<Book [Book1]>, <Book [Book2]>])
>>> xw.apps[10559].books # specific app, get the PIDs via xw.apps.keys()
Books([<Book [Book1]>, <Book [Book2]>])
```

New in version 0.9.0.

property active

Returns the active Book.

add()

Creates a new Book. The new Book becomes the active Book. Returns a Book object.

open(*fullname=None, update_links=None, read_only=None, format=None, password=None, write_res_password=None, ignore_read_only_recommended=None, origin=None, delimiter=None, editable=None, notify=None, converter=None, add_to_mru=None, local=None, corrupt_load=None, json=None*)

Opens a Book if it is not open yet and returns it. If it is already open, it doesn't raise an exception but simply returns the Book object.

Parameters

- **fullname** (*str or path-like object*) – filename or fully qualified filename, e.g. `r'C:\path\to\file.xlsx'` or `'file.xlsm'`. Without a full path, it looks for the file in the current working directory.
- **Parameters** (*Other*) – see: `xlwings.Book()`

Returns

Book

Return type

Book that has been opened.

33.2.4 Book

```
class xlwings.Book(fullname=None, update_links=None, read_only=None, format=None,
                    password=None, write_res_password=None,
                    ignore_read_only_recommended=None, origin=None, delimiter=None,
                    editable=None, notify=None, converter=None, add_to_mru=None, local=None,
                    corrupt_load=None, impl=None, json=None, mode=None, engine=None)
```

A book object is a member of the `books` collection:

```
>>> import xlwings as xw
>>> xw.books[0]
<Book [Book1]>
```

The easiest way to connect to a book is offered by `xw.Book`: it looks for the book in all app instances and returns an error, should the same book be open in multiple instances. To connect to a book in the active app instance, use `xw.books` and to refer to a specific app, use:

```
>>> app = xw.App() # or xw.apps[10559] (get the PIDs via xw.apps.keys())
>>> app.books['Book1']
```

	<code>xw.Book</code>	<code>xw.books</code>
New book	<code>xw.Book()</code>	<code>xw.books.add()</code>
Unsaved book	<code>xw.Book('Book1')</code>	<code>xw.books['Book1']</code>
Book by (full)name	<code>xw.Book(r'C:/path/to/file.xlsx')</code>	<code>xw.books.open(r'C:/path/to/file.xlsx')</code>

Parameters

- **fullname** (*str or path-like object, default None*) – Full path or name (incl. `xlsx`, `xlsm` etc.) of existing workbook or name of an unsaved workbook. Without a full path, it looks for the file in the current working directory.
- **update_links** (*bool, default None*) – If this argument is omitted, the user is prompted to specify how links will be updated
- **read_only** (*bool, default False*) – True to open workbook in read-only mode
- **format** (*str*) – If opening a text file, this specifies the delimiter character
- **password** (*str*) – Password to open a protected workbook
- **write_res_password** (*str*) – Password to write to a write-reserved workbook
- **ignore_read_only_recommended** (*bool, default False*) – Set to True to mute the read-only recommended message
- **origin** (*int*) – For text files only. Specifies where it originated. Use Platform constants.
- **delimiter** (*str*) – If format argument is 6, this specifies the delimiter.

- **editable** (*bool*, *default False*) – This option is only for legacy Microsoft Excel 4.0 addins.
- **notify** (*bool*, *default False*) – Notify the user when a file becomes available. If the file cannot be opened in read/write mode.
- **converter** (*int*) – The index of the first file converter to try when opening the file.
- **add_to_mru** (*bool*, *default False*) – Add this workbook to the list of recently added workbooks.
- **local** (*bool*, *default False*) – If **True**, saves files against the language of Excel, otherwise against the language of VBA. Not supported on macOS.
- **corrupt_load** (*int*, *default xlNormalLoad*) – Can be one of `xlNormalLoad`, `xlRepairFile` or `xlExtractData`. Not supported on macOS.
- **json** (*dict*) – A JSON object as delivered by the MS Office Scripts or Google Apps Script xlwings module but in a deserialized form, i.e., as dictionary.
New in version 0.26.0.
- **mode** (*str*, *default None*) – Either **"i"** (interactive (default)) or **"r"** (read). In interactive mode, xlwings opens the workbook in Excel, i.e., Excel needs to be installed. In read mode, xlwings reads from the file directly, without requiring Excel to be installed. Read mode requires xlwings PRO.

New in version 0.28.0.

activate (*steal_focus=False*)

Activates the book.

Parameters

steal_focus (*bool*, *default False*) – If **True**, make frontmost window and hand over focus from Python to Excel.

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.9.0.

property app

Returns an app object that represents the creator of the book.

New in version 0.9.0.

classmethod caller()

References the calling book when the Python function is called from Excel via `RunPython`. Pack it into the function being called from Excel, e.g.:

```
import xlwings as xw

def my_macro():
```

(continues on next page)

(continued from previous page)

```
wb = xw.Book.caller()
wb.sheets[0].range('A1').value = 1
```

To be able to easily invoke such code from Python for debugging, use `xw.Book.set_mock_caller()`.

New in version 0.3.0.

close()

Closes the book without saving it.

New in version 0.1.1.

property fullname

Returns the name of the object, including its path on disk, as a string. Read-only String.

json()

Returns a JSON serializable object as expected by the MS Office Scripts or Google Apps Script xlwings module. Only available with book objects that have been instantiated via `xw.Book(json=...)`.

New in version 0.26.0.

macro(name)

Runs a Sub or Function in Excel VBA.

Parameters

- **name** (*Name of Sub or Function with or without module name, e.g.,*) –
- **'MyMacro'** (*'Module1.MyMacro' or*) –

Examples

This VBA function:

```
Function MySum(x, y)
    MySum = x + y
End Function
```

can be accessed like this:

```
>>> import xlwings as xw
>>> wb = xw.books.active
>>> my_sum = wb.macro('MySum')
>>> my_sum(1, 2)
3
```


See also: [App.macro\(\)](#)

New in version 0.7.1.

property name

Returns the name of the book as str.

property names

Returns a names collection that represents all the names in the specified book (including all sheet-specific names).

Changed in version 0.9.0.

render_template(**data)

This method requires xlwings PRO.

Replaces all Jinja variables (e.g. `{{ myvar }}`) in the book with the keyword argument of the same name.

New in version 0.25.0.

Parameters

data (*kwargs*) – All key/value pairs that are used in the template.

Examples

```
>>> import xlwings as xw
>>> book = xw.Book()
>>> book.sheets[0]['A1:A2'].value = '{{ myvar }}'
>>> book.render_template(myvar='test')
```

save(path=None, password=None)

Saves the Workbook. If a path is provided, this works like `SaveAs()` in Excel. If no path is specified and if the file hasn't been saved previously, it's saved in the current working directory with the current filename. Existing files are overwritten without prompting. To change the file type, provide the appropriate extension, e.g. to save `myfile.xlsx` in the `xlsb` format, provide `myfile.xlsb` as path.

Parameters

- **path** (*str or path-like object, default None*) – Path where you want to save the Book.
- **password** (*str, default None*) – Protection password with max. 15 characters

New in version 0.25.1.

Example

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> wb.save()
>>> wb.save(r'C:\path\to\new_file_name.xlsx')
```

New in version 0.3.1.

property selection

Returns the selected cells as Range.

New in version 0.9.0.

set_mock_caller()

Sets the Excel file which is used to mock `xw.Book.caller()` when the code is called from Python and not from Excel via RunPython.

Examples

```
# This code runs unchanged from Excel via RunPython and from Python,
↪ directly
import os
import xlwings as xw

def my_macro():
    sht = xw.Book.caller().sheets[0]
    sht.range('A1').value = 'Hello xlwings!'

if __name__ == '__main__':
    xw.Book('file.xlsm').set_mock_caller()
    my_macro()
```

New in version 0.3.1.

property sheet_names

Returns

sheet_names – List of sheet names in order of appearance.

Return type

List

New in version 0.28.1.

property sheets

Returns a sheets collection that represents all the sheets in the book.

New in version 0.9.0.

to_pdf(*path=None, include=None, exclude=None, layout=None, exclude_start_string='#', show=False, quality='standard'*)

Exports the whole Excel workbook or a subset of the sheets to a PDF file. If you want to print hidden sheets, you will need to list them explicitly under `include`.

Parameters

- **path** (*str or path-like object, default None*) – Path to the PDF file, defaults to the same name as the workbook, in the same directory. For unsaved workbooks, it defaults to the current working directory instead.
- **include** (*int or str or list, default None*) – Which sheets to include: provide a selection of sheets in the form of sheet indices (1-based like in Excel) or sheet names. Can be an int/str for a single sheet or a list of int/str for multiple sheets.
- **exclude** (*int or str or list, default None*) – Which sheets to exclude: provide a selection of sheets in the form of sheet indices (1-based like in Excel) or sheet names. Can be an int/str for a single sheet or a list of int/str for multiple sheets.
- **layout** (*str or path-like object, default None*) – This argument requires xlwings PRO.

Path to a PDF file on which the report will be printed. This is ideal for headers and footers as well as borderless printing of graphics/artwork. The PDF file either needs to have only 1 page (every report page uses the same layout) or otherwise needs the same amount of pages as the report (each report page is printed on the respective page in the layout PDF).

New in version 0.24.3.

- **exclude_start_string** (*str, default '#'*) – Sheet names that start with this character/string will not be printed.

New in version 0.24.4.

- **show** (*bool, default False*) – Once created, open the PDF file with the default application.

New in version 0.24.6.

- **quality** (*str, default 'standard'*) – Quality of the PDF file. Can either be 'standard' or 'minimum'.

New in version 0.26.2.

Examples

```
>>> wb = xw.Book()
>>> wb.sheets[0]['A1'].value = 'PDF'
>>> wb.to_pdf()
```

See also `xlwings.Sheet.to_pdf()`

New in version 0.21.1.

33.2.5 PageSetup

class xlwings.main.**PageSetup**(*impl*)

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.24.2.

property print_area

Gets or sets the range address that defines the print area.

Examples

```
>>> mysheet.page_setup.print_area = '$A$1:$B$3'
>>> mysheet.page_setup.print_area
'$A$1:$B$3'
>>> mysheet.page_setup.print_area = None # clear the print_area
```

New in version 0.24.2.

33.2.6 Sheets

class xlwings.main.**Sheets**(*impl*)

A collection of all [sheet](#) objects:

```
>>> import xlwings as xw
>>> xw.sheets # active book
Sheets([<Sheet [Book1]Sheet1>, <Sheet [Book1]Sheet2>])
>>> xw.Book('Book1').sheets # specific book
Sheets([<Sheet [Book1]Sheet1>, <Sheet [Book1]Sheet2>])
```

New in version 0.9.0.

property active

Returns the active Sheet.

add(*name=None, before=None, after=None*)

Creates a new Sheet and makes it the active sheet.

Parameters

- **name** (*str, default None*) – Name of the new sheet. If None, will default to Excel's default name.
- **before** (*Sheet, default None*) – An object that specifies the sheet before which the new sheet is added.
- **after** (*Sheet, default None*) – An object that specifies the sheet after which the new sheet is added.

Returns

sheet – Added sheet object

Return type

Sheet

33.2.7 Sheet

class `xlwings.Sheet`(*sheet=None, impl=None*)

A sheet object is a member of the *sheets* collection:

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> wb.sheets[0]
<Sheet [Book1] Sheet1>
>>> wb.sheets['Sheet1']
<Sheet [Book1] Sheet1>
>>> wb.sheets.add()
<Sheet [Book1] Sheet2>
```

Changed in version 0.9.0.

activate()

Activates the Sheet and returns it.

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.9.0.

autofit(*axis=None*)

Autofits the width of either columns, rows or both on a whole Sheet.

Parameters

axis (*string, default None*) –

- To autofit rows, use one of the following: `rows` or `r`
- To autofit columns, use one of the following: `columns` or `c`

- To autofit rows and columns, provide no arguments

Examples

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> wb.sheets['Sheet1'].autofit('c')
>>> wb.sheets['Sheet1'].autofit('r')
>>> wb.sheets['Sheet1'].autofit()
```

New in version 0.2.3.

property book

Returns the Book of the specified Sheet. Read-only.

property cells

Returns a Range object that represents all the cells on the Sheet (not just the cells that are currently in use).

New in version 0.9.0.

property charts

See [Charts](#)

New in version 0.9.0.

clear()

Clears the content and formatting of the whole sheet.

clear_contents()

Clears the content of the whole sheet but leaves the formatting.

clear_formats()

Clears the format of the whole sheet but leaves the content.

New in version 0.26.2.

copy(*before=None, after=None, name=None*)

Copy a sheet to the current or a new Book. By default, it places the copied sheet after all existing sheets in the current Book. Returns the copied sheet.

New in version 0.22.0.

Parameters

- **before** (*sheet object, default None*) – The sheet object before which you want to place the sheet
- **after** (*sheet object, default None*) – The sheet object after which you want to place the sheet, by default it is placed after all existing sheets
- **name** (*str, default None*) – The sheet name of the copy

Returns

Sheet object – The copied sheet

Return type

Sheet

Examples

```

# Create two books and add a value to the first sheet of the first book
first_book = xw.Book()
second_book = xw.Book()
first_book.sheets[0]['A1'].value = 'some value'

# Copy to same Book with the default location and name
first_book.sheets[0].copy()

# Copy to same Book with custom sheet name
first_book.sheets[0].copy(name='copied')

# Copy to second Book requires to use before or after
first_book.sheets[0].copy(after=second_book.sheets[0])

```

delete()

Deletes the Sheet.

New in version 0.6.0.

property index

Returns the index of the Sheet (1-based as in Excel).

property name

Gets or sets the name of the Sheet.

property names

Returns a names collection that represents all the sheet-specific names (names defined with the “SheetName!” prefix).

New in version 0.9.0.

property page_setup

Returns a PageSetup object.

New in version 0.24.2.

property pictures

See *Pictures*

New in version 0.9.0.

range(*cell1*, *cell2=None*)

Returns a Range object from the active sheet of the active book, see [Range\(\)](#).

New in version 0.9.0.

render_template(***data*)

This method requires xlwings PRO.

Replaces all Jinja variables (e.g `{{ myvar }}`) in the sheet with the keyword argument that has the same name. Following variable types are supported:

strings, numbers, lists, simple dicts, NumPy arrays, Pandas DataFrames, PIL Image objects that have a filename and Matplotlib figures.

New in version 0.22.0.

Parameters

data (*kwargs*) – All key/value pairs that are used in the template.

Examples

```
>>> import xlwings as xw
>>> book = xw.Book()
>>> book.sheets[0]['A1:A2'].value = '{{ myvar }}'
>>> book.sheets[0].render_template(myvar='test')
```

select()

Selects the Sheet. Select only works on the active book.

New in version 0.9.0.

property shapes

See [Shapes](#)

New in version 0.9.0.

property tables

See [Tables](#)

New in version 0.21.0.

to_html(*path=None*)

Export a Sheet as HTML page.

Parameters

path (*str or path-like, default None*) – Path where you want to save the HTML file. Defaults to Sheet name in the current working directory.

New in version 0.28.1.

to_pdf(*path=None, layout=None, show=False, quality='standard'*)

Exports the sheet to a PDF file.

Parameters

- **path** (*str or path-like object, default None*) – Path to the PDF file, defaults to the name of the sheet in the same directory of the workbook. For unsaved workbooks, it defaults to the current working directory instead.
- **layout** (*str or path-like object, default None*) – This argument requires xlwings PRO.

Path to a PDF file on which the report will be printed. This is ideal for headers and footers as well as borderless printing of graphics/artwork. The PDF file either needs to have only 1 page (every report page uses the same layout) or otherwise needs the same amount of pages as the report (each report page is printed on the respective page in the layout PDF).

New in version 0.24.3.

- **show** (*bool, default False*) – Once created, open the PDF file with the default application.

New in version 0.24.6.

- **quality** (*str, default 'standard'*) – Quality of the PDF file. Can either be 'standard' or 'minimum'.

New in version 0.26.2.

Examples

```
>>> wb = xw.Book()
>>> sheet = wb.sheets[0]
>>> sheet['A1'].value = 'PDF'
>>> sheet.to_pdf()
```

See also `xlwings.Book.to_pdf()`

New in version 0.22.3.

property `used_range`

Used Range of Sheet.

Returns

Return type

`xw.Range`

New in version 0.13.0.

property `visible`

Gets or sets the visibility of the Sheet (bool).

New in version 0.21.1.

33.2.8 Range

class `xlwings.Range(cell1=None, cell2=None, **options)`

Returns a Range object that represents a cell or a range of cells.

Parameters

- **cell1** (*str or tuple or Range*) – Name of the range in the upper-left corner in A1 notation or as index-tuple or as name or as `xw.Range` object. It can also specify a range using the range operator (a colon), .e.g. ‘A1:B2’
- **cell2** (*str or tuple or Range, default None*) – Name of the range in the lower-right corner in A1 notation or as index-tuple or as name or as `xw.Range` object.

Examples

```
import xlwings as xw
sheet1 = xw.Book("MyBook.xlsx").sheets[0]

sheet1.range("A1")
sheet1.range("A1:C3")
sheet1.range((1,1))
sheet1.range((1,1), (3,3))
sheet1.range("NamedRange")

# Or using index/slice notation
sheet1["A1"]
sheet1["A1:C3"]
sheet1[0, 0]
sheet1[0:4, 0:4]
sheet1["NamedRange"]
```

add_hyperlink(*address, text_to_display=None, screen_tip=None*)

Adds a hyperlink to the specified Range (single Cell)

Parameters

- **address** (*str*) – The address of the hyperlink.
- **text_to_display** (*str, default None*) – The text to be displayed for the hyperlink. Defaults to the hyperlink address.
- **screen_tip** (*str, default None*) – The screen tip to be displayed when the mouse pointer is paused over the hyperlink. Default is set to ‘<address> - Click once to follow. Click and hold to select this cell.’

New in version 0.3.0.

property address

Returns a string value that represents the range reference. Use `get_address()` to be able to provide parameters.

New in version 0.9.0.

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.9.0.

autofit()

Autofits the width and height of all cells in the range.

- To autofit only the width of the columns use `myrange.columns.autofit()`
- To autofit only the height of the rows use `myrange.rows.autofit()`

Changed in version 0.9.0.

clear()

Clears the content and the formatting of a Range.

clear_contents()

Clears the content of a Range but leaves the formatting.

clear_formats()

Clears the format of a Range but leaves the content.

New in version 0.26.2.

property color

Gets and sets the background color of the specified Range.

To set the color, either use an RGB tuple (0, 0, 0) or a hex string like #efefef or an Excel color constant. To remove the background, set the color to `None`, see Examples.

Returns

RGB

Return type

tuple

Examples

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> sheet1 = wb.sheets[0]
>>> sheet1.range('A1').color = (255, 255, 255) # or '#ffffff'
>>> sheet1.range('A2').color
(255, 255, 255)
>>> sheet1.range('A2').color = None
```

(continues on next page)

(continued from previous page)

```
>>> sheet1.range('A2').color is None
True
```

New in version 0.3.0.

property column

Returns the number of the first column in the in the specified range. Read-only.

Returns**Return type**

Integer

New in version 0.3.5.

property column_width

Gets or sets the width, in characters, of a Range. One unit of column width is equal to the width of one character in the Normal style. For proportional fonts, the width of the character 0 (zero) is used.

If all columns in the Range have the same width, returns the width. If columns in the Range have different widths, returns None.

column_width must be in the range: $0 \leq \text{column_width} \leq 255$

Note: If the Range is outside the used range of the Worksheet, and columns in the Range have different widths, returns the width of the first column.

Returns**Return type**

float

New in version 0.4.0.

property columns

Returns a [*RangeColumns*](#) object that represents the columns in the specified range.

New in version 0.9.0.

copy(*destination=None*)

Copy a range to a destination range or clipboard.

Parameters

destination ([*xlwings.Range*](#)) – xlwings Range to which the specified range will be copied. If omitted, the range is copied to the clipboard.

Returns**Return type**

None

copy_picture(*appearance='screen', format='picture'*)

Copies the range to the clipboard as picture.

Parameters

- **appearance** (*str*, *default* 'screen') – Either 'screen' or 'printer'.
- **format** (*str*, *default* 'picture') – Either 'picture' or 'bitmap'.

New in version 0.24.8.

property count

Returns the number of cells.

property current_region

This property returns a Range object representing a range bounded by (but not including) any combination of blank rows and blank columns or the edges of the worksheet. It corresponds to Ctrl-* on Windows and Shift-Ctrl-Space on Mac.

Returns**Return type**

Range object

delete(*shift=None*)

Deletes a cell or range of cells.

Parameters

shift (*str*, *default* None) – Use left or up. If omitted, Excel decides based on the shape of the range.

Returns**Return type**

None

end(*direction*)

Returns a Range object that represents the cell at the end of the region that contains the source range. Equivalent to pressing Ctrl+Up, Ctrl+down, Ctrl+left, or Ctrl+right.

Parameters

direction (One of 'up', 'down', 'right', 'left') –

Examples

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> sheet1 = wb.sheets[0]
>>> sheet1.range('A1:B2').value = 1
>>> sheet1.range('A1').end('down')
<Range [Book1]Sheet1!$A$2>
>>> sheet1.range('B2').end('right')
<Range [Book1]Sheet1!$B$2>
```

New in version 0.9.0.

expand(mode='table')

Expands the range according to the mode provided. Ignores empty top-left cells (unlike `Range.end()`).

Parameters

mode (*str*, default 'table') – One of 'table' (=down and right), 'down', 'right'.

Returns**Return type**

Range

Examples

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> sheet1 = wb.sheets[0]
>>> sheet1.range('A1').value = [[None, 1], [2, 3]]
>>> sheet1.range('A1').expand().address
$A$1:$B$2
>>> sheet1.range('A1').expand('right').address
$A$1:$B$1
```

New in version 0.9.0.

property formula

Gets or sets the formula for the given Range.

property formula2

Gets or sets the formula2 for the given Range.

property formula_array

Gets or sets an array formula for the given Range.

New in version 0.7.1.

get_address(row_absolute=True, column_absolute=True, include_sheetname=False, external=False)

Returns the address of the range in the specified format. `address` can be used instead if none of the defaults need to be changed.

Parameters

- **row_absolute** (*bool*, default *True*) – Set to *True* to return the row part of the reference as an absolute reference.
- **column_absolute** (*bool*, default *True*) – Set to *True* to return the column part of the reference as an absolute reference.
- **include_sheetname** (*bool*, default *False*) – Set to *True* to include the Sheet name in the address. Ignored if `external=True`.

- **external** (*bool*, *default False*) – Set to True to return an external reference with workbook and worksheet name.

Returns**Return type**

str

Examples

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> sheet1 = wb.sheets[0]
>>> sheet1.range((1,1)).get_address()
'$A$1'
>>> sheet1.range((1,1)).get_address(False, False)
'A1'
>>> sheet1.range((1,1), (3,3)).get_address(True, False, True)
'Sheet1!A$1:C$3'
>>> sheet1.range((1,1), (3,3)).get_address(True, False, external=True)
'[Book1]Sheet1!A$1:C$3'
```

New in version 0.2.3.

property has_array

True if the range is part of a legacy CSE Array formula and False otherwise.

property height

Returns the height, in points, of a Range. Read-only.

Returns**Return type**

float

New in version 0.4.0.

property hyperlink

Returns the hyperlink address of the specified Range (single Cell only)

Examples

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> sheet1 = wb.sheets[0]
>>> sheet1.range('A1').value
'www.xlwings.org'
>>> sheet1.range('A1').hyperlink
'http://www.xlwings.org'
```

New in version 0.3.0.

insert(*shift=None, copy_origin='format_from_left_or_above'*)

Insert a cell or range of cells into the sheet.

Parameters

- **shift** (*str, default None*) – Use **right** or **down**. If omitted, Excel decides based on the shape of the range.
- **copy_origin** (*str, default format_from_left_or_above*) – Use **format_from_left_or_above** or **format_from_right_or_below**. Note that this is not supported on macOS.

Returns

Return type

None

property last_cell

Returns the bottom right cell of the specified range. Read-only.

Returns

Return type

Range

Example

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> sheet1 = wb.sheets[0]
>>> myrange = sheet1.range('A1:E4')
>>> myrange.last_cell.row, myrange.last_cell.column
(4, 5)
```

New in version 0.3.5.

property left

Returns the distance, in points, from the left edge of column A to the left edge of the range. Read-only.

Returns

Return type

float

New in version 0.6.0.

merge(*across=False*)

Creates a merged cell from the specified Range object.

Parameters

across (*bool*, *default False*) – True to merge cells in each row of the specified Range as separate merged cells.

property merge_area

Returns a Range object that represents the merged Range containing the specified cell. If the specified cell isn't in a merged range, this property returns the specified cell.

property merge_cells

Returns True if the Range contains merged cells, otherwise False

property name

Sets or gets the name of a Range.

New in version 0.4.0.

property note

Returns a Note object. Before the introduction of threaded comments, a Note was called a Comment.

New in version 0.24.2.

property number_format

Gets and sets the number_format of a Range.

Examples

```
>>> import xlwings as xw
>>> wb = xw.Book()
>>> sheet1 = wb.sheets[0]
>>> sheet1.range('A1').number_format
'General'
>>> sheet1.range('A1:C3').number_format = '0.00%'
>>> sheet1.range('A1:C3').number_format
'0.00%'
```

New in version 0.2.3.

offset (*row_offset=0*, *column_offset=0*)

Returns a Range object that represents a Range that's offset from the specified range.

Returns

Range object

Return type

Range

New in version 0.3.0.

options(*convert=None, **options*)

Allows you to set a converter and their options. Converters define how Excel Ranges and their values are being converted both during reading and writing operations. If no explicit converter is specified, the base converter is being applied, see [Converters and Options](#).

Parameters

convert (*object, default None*) – A converter, e.g. dict, np.array, pd.DataFrame, pd.Series, defaults to default converter

Keyword Arguments

- **ndim** (*int, default None*) – number of dimensions
- **numbers** (*type, default None*) – type of numbers, e.g. int
- **dates** (*type, default None*) – e.g. datetime.date defaults to datetime.datetime
- **empty** (*object, default None*) – transformation of empty cells
- **transpose** (*Boolean, default False*) – transpose values
- **expand** (*str, default None*) – One of 'table', 'down', 'right'
- **chunksize** (*int*) – Use a chunksize, e.g. 10000 to prevent timeout or memory issues when reading or writing large amounts of data. Works with all formats, including DataFrames, NumPy arrays, and list of lists.
- **err_to_str** (*Boolean, default False*) – If True, will include cell errors such as #N/A as strings. By default, they will be converted to None.

New in version 0.28.0.

:keyword => For converter-specific options, see [Converters and Options](#).

Returns

Return type

Range object

paste(*paste=None, operation=None, skip_blanks=False, transpose=False*)

Pastes a range from the clipboard into the specified range.

Parameters

- **paste** (*str, default None*) – One of all_merging_conditional_formats, all, all_except_borders, all_using_source_theme, column_widths, comments, formats, formulas, formulas_and_number_formats, validation, values, values_and_number_formats.
- **operation** (*str, default None*) – One of “add”, “divide”, “multiply”, “subtract”.
- **skip_blanks** (*bool, default False*) – Set to True to skip over blank cells
- **transpose** (*bool, default False*) – Set to True to transpose rows and columns.

Returns**Return type**

None

property raw_value

Gets and sets the values directly as delivered from/accepted by the engine that s being used (pywin32 or appscript) without going through any of xlwings' data cleaning/converting. This can be helpful if speed is an issue but naturally will be engine specific, i.e. might remove the cross-platform compatibility.

resize(*row_size=None, column_size=None*)

Resizes the specified Range

Parameters

- **row_size** (*int* > 0) – The number of rows in the new range (if None, the number of rows in the range is unchanged).
- **column_size** (*int* > 0) – The number of columns in the new range (if None, the number of columns in the range is unchanged).

Returns

Range object

Return type*Range*

New in version 0.3.0.

property row

Returns the number of the first row in the specified range. Read-only.

Returns**Return type**

Integer

New in version 0.3.5.

property row_height

Gets or sets the height, in points, of a Range. If all rows in the Range have the same height, returns the height. If rows in the Range have different heights, returns None.

row_height must be in the range: 0 <= row_height <= 409.5

Note: If the Range is outside the used range of the Worksheet, and rows in the Range have different heights, returns the height of the first row.

Returns**Return type**

float

New in version 0.4.0.

property rows

Returns a *RangeRows* object that represents the rows in the specified range.

New in version 0.9.0.

select()

Selects the range. Select only works on the active book.

New in version 0.9.0.

property shape

Tuple of Range dimensions.

New in version 0.3.0.

property sheet

Returns the Sheet object to which the Range belongs.

New in version 0.9.0.

property size

Number of elements in the Range.

New in version 0.3.0.

property table

Returns a Table object if the range is part of one, otherwise *None*.

New in version 0.21.0.

to_pdf(*path=None, layout=None, show=None, quality='standard'*)

Exports the range as PDF.

Parameters

- **path** (*str or path-like, default None*) – Path where you want to store the pdf. Defaults to the address of the range in the same directory as the Excel file if the Excel file is stored and to the current working directory otherwise.

- **layout** (*str or path-like object, default None*) – This argument requires xlwings PRO.

Path to a PDF file on which the report will be printed. This is ideal for headers and footers as well as borderless printing of graphics/artwork. The PDF file either needs to have only 1 page (every report page uses the same layout) or otherwise needs the same amount of pages as the report (each report page is printed on the respective page in the layout PDF).

- **show** (*bool, default False*) – Once created, open the PDF file with the default application.

- **quality** (*str, default 'standard'*) – Quality of the PDF file. Can either be 'standard' or 'minimum'.

New in version 0.26.2.

to_png(*path=None*)

Exports the range as PNG picture.

Parameters

path (*str or path-like, default None*) – Path where you want to store the picture. Defaults to the name of the range in the same directory as the Excel file if the Excel file is stored and to the current working directory otherwise.

New in version 0.24.8.

property top

Returns the distance, in points, from the top edge of row 1 to the top edge of the range. Read-only.

Returns**Return type**

float

New in version 0.6.0.

unmerge()

Separates a merged area into individual cells.

property value

Gets and sets the values for the given Range. See [xlwings.Range.options\(\)](#) about how to set options, e.g., to transform it into a DataFrame or how to set a chunksize.

Returns

object – see [xlwings.Range.options\(\)](#)

Return type

returned object depends on the converter being used,

property width

Returns the width, in points, of a Range. Read-only.

Returns**Return type**

float

New in version 0.4.0.

property wrap_text

Returns True if the wrap_text property is enabled and False if it's disabled. If not all cells have the same value in a range, on Windows it returns None and on macOS False.

New in version 0.23.2.

33.2.9 RangeRows

class `xlwings.RangeRows(rng)`

Represents the rows of a range. Do not construct this class directly, use [*Range.rows*](#) instead.

Example

```
import xlwings as xw

wb = xw.Book("MyBook.xlsx")
sheet1 = wb.sheets[0]
myrange = sheet1.range('A1:C4')

assert len(myrange.rows) == 4 # or myrange.rows.count

myrange.rows[0].value = 'a'

assert myrange.rows[2] == sheet1.range('A3:C3')
assert myrange.rows(2) == sheet1.range('A2:C2')

for r in myrange.rows:
    print(r.address)
```

autofit()

Autofits the height of the rows.

property count

Returns the number of rows.

New in version 0.9.0.

33.2.10 RangeColumns

class `xlwings.RangeColumns(rng)`

Represents the columns of a range. Do not construct this class directly, use [*Range.columns*](#) instead.

Example

```
import xlwings as xw

wb = xw.Book("MyFile.xlsx")
sheet1 = wb.sheets[0]
myrange = sheet1.range('A1:C4')
```

(continues on next page)

(continued from previous page)

```

assert len(myrange.columns) == 3 # or myrange.columns.count

myrange.columns[0].value = 'a'

assert myrange.columns[2] == sheet1.range('C1:C4')
assert myrange.columns(2) == sheet1.range('B1:B4')

for c in myrange.columns:
    print(c.address)

```

autofit()

Autofits the width of the columns.

property count

Returns the number of columns.

New in version 0.9.0.

33.2.11 Shapes

class xlwings.main.Shapes(*impl*)

A collection of all *shape* objects on the specified sheet:

```

>>> import xlwings as xw
>>> xw.books['Book1'].sheets[0].shapes
Shapes([<Shape 'Oval 1' in <Sheet [Book1]Sheet1>>,
        <Shape 'Rectangle 1' in <Sheet [Book1]Sheet1>>])

```

New in version 0.9.0.

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

property count

Returns the number of objects in the collection.

33.2.12 Shape

class xlwings.Shape(*args, **options)

The shape object is a member of the *shapes* collection:

```

>>> import xlwings as xw
>>> sht = xw.books['Book1'].sheets[0]
>>> sht.shapes[0] # or sht.shapes['ShapeName']
<Shape 'Rectangle 1' in <Sheet [Book1]Sheet1>>

```

Changed in version 0.9.0.

activate()

Activates the shape.

New in version 0.5.0.

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.19.2.

delete()

Deletes the shape.

New in version 0.5.0.

property height

Returns or sets the number of points that represent the height of the shape.

New in version 0.5.0.

property left

Returns or sets the number of points that represent the horizontal position of the shape.

New in version 0.5.0.

property name

Returns or sets the name of the shape.

New in version 0.5.0.

property parent

Returns the parent of the shape.

New in version 0.9.0.

scale_height(*factor*, *relative_to_original_size=False*, *scale='scale_from_top_left'*)

factor

[float] For example 1.5 to scale it up to 150%

relative_to_original_size

[bool, optional] If `False`, it scales relative to current height (default). For `True` must be a picture or OLE object.

scale

[str, optional] One of `scale_from_top_left` (default), `scale_from_bottom_right`, `scale_from_middle`

New in version 0.19.2.

scale_width(*factor*, *relative_to_original_size=False*, *scale='scale_from_top_left'*)

factor

[float] For example 1.5 to scale it up to 150%

relative_to_original_size

[bool, optional] If False, it scales relative to current width (default). For True must be a picture or OLE object.

scale

[str, optional] One of `scale_from_top_left` (default), `scale_from_bottom_right`, `scale_from_middle`

New in version 0.19.2.

property text

Returns or sets the text of a shape.

New in version 0.21.4.

property top

Returns or sets the number of points that represent the vertical position of the shape.

New in version 0.5.0.

property type

Returns the type of the shape.

New in version 0.9.0.

property width

Returns or sets the number of points that represent the width of the shape.

New in version 0.5.0.

33.2.13 Charts

class xlwings.main.Charts(*impl*)

A collection of all [chart](#) objects on the specified sheet:

```
>>> import xlwings as xw
>>> xw.books['Book1'].sheets[0].charts
Charts([<Chart 'Chart 1' in <Sheet [Book1]Sheet1>>,
        <Chart 'Chart 1' in <Sheet [Book1]Sheet1>>])
```

New in version 0.9.0.

add(*left=0, top=0, width=355, height=211*)

Creates a new chart on the specified sheet.

Parameters

- **left** (*float*, *default* 0) – left position in points
- **top** (*float*, *default* 0) – top position in points
- **width** (*float*, *default* 355) – width in points
- **height** (*float*, *default* 211) – height in points

Returns**Return type***Chart***Examples**

```
>>> import xlwings as xw
>>> sht = xw.Book().sheets[0]
>>> sht.range('A1').value = [['Foo1', 'Foo2'], [1, 2]]
>>> chart = sht.charts.add()
>>> chart.set_source_data(sht.range('A1').expand())
>>> chart.chart_type = 'line'
>>> chart.name
'Chart1'
```

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

property count

Returns the number of objects in the collection.

33.2.14 Chart

class xlwings.**Chart**(name_or_index=None, impl=None)

The chart object is a member of the *charts* collection:

```
>>> import xlwings as xw
>>> sht = xw.books['Book1'].sheets[0]
>>> sht.charts[0] # or sht.charts['ChartName']
<Chart 'Chart 1' in <Sheet [Book1]Sheet1>>
```

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.9.0.

property chart_type

Returns and sets the chart type of the chart. The following chart types are available:

3d_area, 3d_area_stacked, 3d_area_stacked_100, 3d_bar_clustered,
3d_bar_stacked, 3d_bar_stacked_100, 3d_column, 3d_column_clustered,
3d_column_stacked, 3d_column_stacked_100, 3d_line, 3d_pie, 3d_pie_exploded,
area, area_stacked, area_stacked_100, bar_clustered, bar_of_pie,
bar_stacked, bar_stacked_100, bubble, bubble_3d_effect, column_clustered,
column_stacked, column_stacked_100, combination, cone_bar_clustered,
cone_bar_stacked, cone_bar_stacked_100, cone_col, cone_col_clustered,
cone_col_stacked, cone_col_stacked_100, cylinder_bar_clustered,

cylinder_bar_stacked, cylinder_bar_stacked_100, cylinder_col,
 cylinder_col_clustered, cylinder_col_stacked, cylinder_col_stacked_100,
 doughnut, doughnut_exploded, line, line_markers, line_markers_stacked,
 line_markers_stacked_100, line_stacked, line_stacked_100, pie,
 pie_exploded, pie_of_pie, pyramid_bar_clustered, pyramid_bar_stacked,
 pyramid_bar_stacked_100, pyramid_col, pyramid_col_clustered,
 pyramid_col_stacked, pyramid_col_stacked_100, radar, radar_filled,
 radar_markers, stock_hlc, stock_ohlc, stock_vhlc, stock_vohlc, surface,
 surface_top_view, surface_top_view_wireframe, surface_wireframe, xy_scatter,
 xy_scatter_lines, xy_scatter_lines_no_markers, xy_scatter_smooth,
 xy_scatter_smooth_no_markers

New in version 0.1.1.

delete()

Deletes the chart.

property height

Returns or sets the number of points that represent the height of the chart.

property left

Returns or sets the number of points that represent the horizontal position of the chart.

property name

Returns or sets the name of the chart.

property parent

Returns the parent of the chart.

New in version 0.9.0.

set_source_data(source)

Sets the source data range for the chart.

Parameters

source ([Range](#)) – Range object, e.g. `xw.books['Book1'].sheets[0].range('A1')`

to_pdf(path=None, show=None, quality='standard')

Exports the chart as PDF.

Parameters

- **path** (*str or path-like, default None*) – Path where you want to store the pdf. Defaults to the name of the chart in the same directory as the Excel file if the Excel file is stored and to the current working directory otherwise.
- **show** (*bool, default False*) – Once created, open the PDF file with the default application.
- **quality** (*str, default 'standard'*) – Quality of the PDF file. Can either be 'standard' or 'minimum'.

New in version 0.26.2.

to_png(*path=None*)

Exports the chart as PNG picture.

Parameters

path (*str* or *path-like*, *default None*) – Path where you want to store the picture. Defaults to the name of the chart in the same directory as the Excel file if the Excel file is stored and to the current working directory otherwise.

New in version 0.24.8.

property top

Returns or sets the number of points that represent the vertical position of the chart.

property width

Returns or sets the number of points that represent the width of the chart.

33.2.15 Pictures

class xlwings.main.Pictures(*impl*)

A collection of all *picture* objects on the specified sheet:

```
>>> import xlwings as xw
>>> xw.books['Book1'].sheets[0].pictures
Pictures([<Picture 'Picture 1' in <Sheet [Book1]Sheet1>>,
         <Picture 'Picture 2' in <Sheet [Book1]Sheet1>>])
```

New in version 0.9.0.

add(*image*, *link_to_file=False*, *save_with_document=True*, *left=None*, *top=None*, *width=None*, *height=None*, *name=None*, *update=False*, *scale=None*, *format=None*, *anchor=None*, *export_options=None*)

Adds a picture to the specified sheet.

Parameters

- **image** (*str* or *path-like object* or *matplotlib.figure.Figure*) – Either a filepath or a Matplotlib figure object.
- **left** (*float*, *default None*) – Left position in points, defaults to 0. If you use top/left, you must not provide a value for anchor.
- **top** (*float*, *default None*) – Top position in points, defaults to 0. If you use top/left, you must not provide a value for anchor.
- **width** (*float*, *default None*) – Width in points. Defaults to original width.
- **height** (*float*, *default None*) – Height in points. Defaults to original height.
- **name** (*str*, *default None*) – Excel picture name. Defaults to Excel standard name if not provided, e.g., ‘Picture 1’.

- **update** (*bool*, *default False*) – Replace an existing picture with the same name. Requires *name* to be set.
- **scale** (*float*, *default None*) – Scales your picture by the provided factor.
- **format** (*str*, *default None*) – Only used if image is a Matplotlib or Plotly plot. By default, the plot is inserted in the “png” format, but you may want to change this to a vector-based format like “svg” on Windows (may require Microsoft 365) or “eps” on macOS for better print quality. If you use 'vector', it will be using 'svg' on Windows and 'eps' on macOS. To find out which formats your version of Excel supports, see: <https://support.microsoft.com/en-us/topic/support-for-eps-images-has-been-turned-off-in-office-a069d664-4bcf-415e-a1b5-cbb0c334a840>
- **anchor** (*xw.Range*, *default None*) – The xlwings Range object of where you want to insert the picture. If you use anchor, you must not provide values for top/left.

New in version 0.24.3.

- **export_options** (*dict*, *default None*) – For Matplotlib plots, this dictionary is passed on to `image.savefig()` with the following defaults: `{"bbox_inches": "tight", "dpi": 200}`, so if you want to leave the picture uncropped and increase dpi to 300, use: `export_options={"dpi": 300}`. For Plotly, the options are passed to `write_image()`.

New in version 0.27.7.

Returns

Return type

Picture

Examples

1. Picture

```
>>> import xlwings as xw
>>> sht = xw.Book().sheets[0]
>>> sht.pictures.add(r'C:\path\to\file.png')
<Picture 'Picture 1' in <Sheet [Book1]Sheet1>>
```

2. Matplotlib

```
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.plot([1, 2, 3, 4, 5])
>>> sht.pictures.add(fig, name='MyPlot', update=True)
<Picture 'MyPlot' in <Sheet [Book1]Sheet1>>
```

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

property count

Returns the number of objects in the collection.

33.2.16 Picture

class xlwings.Picture(impl=None)

The picture object is a member of the *pictures* collection:

```
>>> import xlwings as xw
>>> sht = xw.books['Book1'].sheets[0]
>>> sht.pictures[0] # or sht.charts['PictureName']
<Picture 'Picture 1' in <Sheet [Book1]Sheet1>>
```

Changed in version 0.9.0.

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.9.0.

delete()

Deletes the picture.

New in version 0.5.0.

property height

Returns or sets the number of points that represent the height of the picture.

New in version 0.5.0.

property left

Returns or sets the number of points that represent the horizontal position of the picture.

New in version 0.5.0.

property lock_aspect_ratio

True will keep the original proportion, False will allow you to change height and width independently of each other (read/write).

New in version 0.24.0.

property name

Returns or sets the name of the picture.

New in version 0.5.0.

property parent

Returns the parent of the picture.

New in version 0.9.0.

property top

Returns or sets the number of points that represent the vertical position of the picture.

New in version 0.5.0.

update(*image, format=None, export_options=None*)

Replaces an existing picture with a new one, taking over the attributes of the existing picture.

Parameters

- **image** (*str or path-like object or matplotlib.figure.Figure*) – Either a filepath or a Matplotlib figure object.
- **format** (*str, default None*) – See under `Pictures.add()`
- **export_options** (*dict, default None*) – See under `Pictures.add()`

New in version 0.5.0.

property width

Returns or sets the number of points that represent the width of the picture.

New in version 0.5.0.

33.2.17 Names

class `xlwings.main.Names`(*impl*)

A collection of all [name](#) objects in the workbook:

```
>>> import xlwings as xw
>>> book = xw.books['Book1'] # book scope and sheet scope
>>> book.names
[<Name 'MyName': =Sheet1!$A$3>]
>>> book.sheets[0].names # sheet scope only
```

New in version 0.9.0.

add(*name, refers_to*)

Defines a new name for a range of cells.

Parameters

- **name** (*str*) – Specifies the text to use as the name. Names cannot include spaces and cannot be formatted as cell references.
- **refers_to** (*str*) – Describes what the name refers to, in English, using A1-style notation.

Returns**Return type**

Name

New in version 0.9.0.

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.9.0.

property count

Returns the number of objects in the collection.

33.2.18 Name

class xlwings.Name(impl)

The name object is a member of the *names* collection:

```
>>> import xlwings as xw
>>> sht = xw.books['Book1'].sheets[0]
>>> sht.names[0] # or sht.names['MyName']
<Name 'MyName': =Sheet1!$A$3>
```

New in version 0.9.0.

property api

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.9.0.

delete()

Deletes the name.

New in version 0.9.0.

property name

Returns or sets the name of the name object.

New in version 0.9.0.

property refers_to

Returns or sets the formula that the name is defined to refer to, in A1-style notation, beginning with an equal sign.

New in version 0.9.0.

property refers_to_range

Returns the Range object referred to by a Name object.

New in version 0.9.0.

33.2.19 Note

class xlwings.main.**Note**(*impl*)

property **api**

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.24.2.

delete()

Delete the note.

New in version 0.24.2.

property **text**

Gets or sets the text of a note. Keep in mind that the note must already exist!

Examples

```
>>> sheet = xw.Book(...).sheets[0]
>>> sheet['A1'].note.text = 'mynote'
>>> sheet['A1'].note.text
>>> 'mynote'
```

New in version 0.24.2.

33.2.20 Tables

class xlwings.main.**Tables**(*impl*)

A collection of all *table* objects on the specified sheet:

```
>>> import xlwings as xw
>>> xw.books['Book1'].sheets[0].tables
Tables([<Table 'Table1' in <Sheet [Book1]Sheet1>>,
        <Table 'Table2' in <Sheet [Book1]Sheet1>>])
```

New in version 0.21.0.

add(*source=None, name=None, source_type=None, link_source=None, has_headers=True, destination=None, table_style_name='TableStyleMedium2'*)

Creates a Table to the specified sheet.

Parameters

- **source** (*xlwings range, default None*) – An xlwings range object, representing the data source.
- **name** (*str, default None*) – The name of the Table. By default, it uses the autogenerated name that is assigned by Excel.

- **source_type** (*str, default None*) – This currently defaults to `xlSrcRange`, i.e. expects an `xlwings` range object. No other options are allowed at the moment.
- **link_source** (*bool, default None*) – Currently not implemented as this is only in case `source_type` is `xlSrcExternal`.
- **has_headers** (*bool or str, default True*) – Indicates whether the data being imported has column labels. Defaults to `True`. Possible values: `True`, `False`, `'guess'`
- **destination** (*xlwings range, default None*) – Currently not implemented as this is used in case `source_type` is `xlSrcExternal`.
- **table_style_name** (*str, default 'TableStyleMedium2'*) – Possible strings: `'TableStyleLightN'` (where `N` is 1-21), `'TableStyleMediumN'` (where `N` is 1-28), `'TableStyleDarkN'` (where `N` is 1-11)

Returns

Return type

Table

Examples

```
>>> import xlwings as xw
>>> sheet = xw.Book().sheets[0]
>>> sheet['A1'].value = [['a', 'b'], [1, 2]]
>>> table = sheet.tables.add(source=sheet['A1'].expand(), name='MyTable
↪')
>>> table
<Table 'MyTable' in <Sheet [Book1]Sheet1>>
```

33.2.21 Table

class `xlwings.main.Table(*args, **options)`

The table object is a member of the `tables` collection:

```
>>> import xlwings as xw
>>> sht = xw.books['Book1'].sheets[0]
>>> sht.tables[0] # or sht.tables['TableName']
<Table 'Table 1' in <Sheet [Book1]Sheet1>>
```

New in version 0.21.0.

property `api`

Returns the native object (pywin32 or appscript obj) of the engine being used.

property data_body_range

Returns an xlwings range object that represents the range of values, excluding the header row

property display_name

Returns or sets the display name for the specified Table object

property header_row_range

Returns an xlwings range object that represents the range of the header row

property insert_row_range

Returns an xlwings range object representing the row where data is going to be inserted. This is only available for empty tables, otherwise it'll return None

property name

Returns or sets the name of the Table.

property parent

Returns the parent of the table.

property range

Returns an xlwings range object of the table.

resize(*range*)

Resize a Table by providing an xlwings range object

New in version 0.24.4.

property show_autofilter

Turn the autofilter on or off by setting it to True or False (read/write boolean)

property show_headers

Show or hide the header (read/write)

property show_table_style_column_stripes

Returns or sets if the Column Stripes table style is used for (read/write boolean)

property show_table_style_first_column

Returns or sets if the first column is formatted (read/write boolean)

property show_table_style_last_column

Returns or sets if the last column is displayed (read/write boolean)

property show_table_style_row_stripes

Returns or sets if the Row Stripes table style is used (read/write boolean)

property show_totals

Gets or sets a boolean to show/hide the Total row.

property table_style

Gets or sets the table style. See [Tables.add](#) for possible values.

property totals_row_range

Returns an xlwings range object representing the Total row

update(data, index=True)

Updates the Excel table with the provided data. Currently restricted to DataFrames.

Changed in version 0.24.0.

Parameters

- **data** (*pandas DataFrame*) – Currently restricted to pandas DataFrames.
- **index** (*bool, default True*) – Whether or not the index of a pandas DataFrame should be written to the Excel table.

Returns**Return type**

Table

Examples

```
import pandas as pd
import xlwings as xw

sheet = xw.Book('Book1.xlsx').sheets[0]
table_name = 'mytable'

# Sample DataFrame
nrows, ncols = 3, 3
df = pd.DataFrame(data=nrows * [ncols * ['test']],
                  columns=['col ' + str(i) for i in range(ncols)])

# Hide the index, then insert a new table if it doesn't exist yet,
# otherwise update the existing one
df = df.set_index('col 0')
if table_name in [table.name for table in sheet.tables]:
    sheet.tables[table_name].update(df)
else:
    mytable = sheet.tables.add(source=sheet['A1'],
                              name=table_name).update(df)
```

33.2.22 Font

class xlwings.main.**Font**(*impl*)

The font object can be accessed as an attribute of the range or shape object.

- `mysheet['A1'].font`
- `mysheet.shapes[0].font`

New in version 0.23.0.

property **api**

Returns the native object (pywin32 or appscript obj) of the engine being used.

New in version 0.23.0.

property **bold**

Returns or sets the bold property (boolean).

```
>>> sheet['A1'].font.bold = True
>>> sheet['A1'].font.bold
True
```

New in version 0.23.0.

property **color**

Returns or sets the color property (tuple).

```
>>> sheet['A1'].font.color = (255, 0, 0) # or '#ff0000'
>>> sheet['A1'].font.color
(255, 0, 0)
```

New in version 0.23.0.

property **italic**

Returns or sets the italic property (boolean).

```
>>> sheet['A1'].font.italic = True
>>> sheet['A1'].font.italic
True
```

New in version 0.23.0.

property **name**

Returns or sets the name of the font (str).

```
>>> sheet['A1'].font.name = 'Calibri'
>>> sheet['A1'].font.name
Calibri
```

New in version 0.23.0.

property size

Returns or sets the size (float).

```
>>> sheet['A1'].font.size = 13
>>> sheet['A1'].font.size
13
```

New in version 0.23.0.

33.2.23 Characters

class xlwings.main.**Characters**(*impl*)

The characters object can be accessed as an attribute of the range or shape object.

- `mysheet['A1'].characters`
- `mysheet.shapes[0].characters`

Note: On macOS, characters are currently not supported due to bugs/lack of support in AppleScript.

New in version 0.23.0.

property api

Returns the native object (pywin32 or applescript obj) of the engine being used.

New in version 0.23.0.

property font

Returns or sets the text property of a characters object.

```
>>> sheet['A1'].characters[1:3].font.bold = True
>>> sheet['A1'].characters[1:3].font.bold
True
```

New in version 0.23.0.

property text

Returns or sets the text property of a characters object.

```
>>> sheet['A1'].value = 'Python'
>>> sheet['A1'].characters[:3].text
Pyt
```

New in version 0.23.0.

33.2.24 Markdown

33.2.25 MarkdownStyle

33.3 UDF decorators

`xlwings.func(category='xlwings', volatile=False, call_in_wizard=True)`

Functions decorated with `xlwings.func` will be imported as `Function` to Excel when running “Import Python UDFs”.

33.3.1 Arguments

category

[int or str, default “xlwings”] 1-14 represent built-in categories, for user-defined categories use strings

New in version 0.10.3.

volatile

[bool, default False] Marks a user-defined function as volatile. A volatile function must be recalculated whenever calculation occurs in any cells on the worksheet. A nonvolatile function is recalculated only when the input variables change. This method has no effect if it’s not inside a user-defined function used to calculate a worksheet cell.

New in version 0.10.3.

call_in_wizard

[bool, default True] Set to False to suppress the function call in the function wizard.

New in version 0.10.3.

`xlwings.sub()`

Functions decorated with `xlwings.sub` will be imported as `Sub` (i.e. macro) to Excel when running “Import Python UDFs”.

`xlwings.arg(arg, convert=None, **options)`

Apply converters and options to arguments, see also [Range.options\(\)](#).

Examples:

Convert `x` into a 2-dimensional numpy array:

```
import xlwings as xw
import numpy as np

@xw.func
@xw.arg('x', np.array, ndim=2)
def add_one(x):
    return x + 1
```

`xlwings.ret(convert=None, **options)`

Apply converters and options to return values, see also [Range.options\(\)](#).

Examples

- 1) Suppress the index and header of a returned DataFrame:

```
import pandas as pd

@xw.func
@xw.ret(index=False, header=False)
def get_dataframe(n, m):
    return pd.DataFrame(np.arange(n * m).reshape((n, m)))
```

- 2) Dynamic array:

Note: If your version of Excel supports the new native dynamic arrays, then you don't have to do anything special, and you shouldn't use the `expand` decorator! To check if your version of Excel supports it, see if you have the `=UNIQUE()` formula available. Native dynamic arrays were introduced in Office 365 Insider Fast at the end of September 2018.

`expand='table'` turns the UDF into a dynamic array. Currently you must not use volatile functions as arguments of a dynamic array, e.g. you cannot use `=TODAY()` as part of a dynamic array. Also note that a dynamic array needs an empty row and column at the bottom and to the right and will overwrite existing data without warning.

Unlike standard Excel arrays, dynamic arrays are being used from a single cell like a standard function and auto-expand depending on the dimensions of the returned array:

```
import xlwings as xw
import numpy as np

@xw.func
@xw.ret(expand='table')
def dynamic_array(n, m):
    return np.arange(n * m).reshape((n, m))
```

New in version 0.10.0.

33.4 Reports

REST API

Note: This is an experimental feature and may be removed in the future.

New in version 0.13.0.

34.1 Quickstart

xlwings offers an easy way to expose an Excel workbook via REST API both on Windows and macOS. This can be useful when you have a workbook running on a single computer and want to access it from another computer. Or you can build a Linux based web app that can interact with a legacy Excel application while you are in the progress of migrating the Excel functionality into your web app (if you need help with that, [give us a shout](#)).

You can run the REST API server from a command prompt or terminal as follows (this requires Flask>=1.0, so make sure to `pip install Flask`):

```
xlwings restapi run
```

Then perform a GET request e.g. via PowerShell on Windows or Terminal on Mac (while having an unsaved “Book1” open). Note that you need to run the server and the GET request from two separate terminals (or you can use something more convenient like [Postman](#) or [Insomnia](#) for testing the API):

```
$ curl "http://127.0.0.1:5000/book/book1/sheets/0/range/A1:B2"
{
  "address": "$A$1:$B$2",
  "color": null,
  "column": 1,
  "column_width": 10.0,
  "count": 4,
  "current_region": "$A$1:$B$2",
  "formula": [
    [
      "1",
      "2"
    ]
  ]
}
```

(continues on next page)

(continued from previous page)

```
    ],
    [
        "3",
        "4"
    ]
],
"formula_array": null,
"height": 32.0,
"last_cell": "$B$2",
"left": 0.0,
"name": null,
"number_format": "General",
"row": 1,
"row_height": 16.0,
"shape": [
    2,
    2
],
"size": 4,
"top": 0.0,
"value": [
    [
        1.0,
        2.0
    ],
    [
        3.0,
        4.0
    ]
],
"width": 130.0
}
```

In the command prompt where your server is running, press **Ctrl-C** to shut it down again.

The xlwings REST API is a thin wrapper around the [Python API](#) which makes it very easy if you have worked previously with xlwings. It also means that the REST API does require the Excel application to be up and running which makes it a great choice if the data in your Excel workbook is constantly changing as the REST API will always deliver the current state of the workbook without the need of saving it first.

Note: Currently, we only provide the GET methods to read the workbook. If you are also interested in the POST methods to edit the workbook, let us know via GitHub issues. Some other things will also need improvement, most notably exception handling.

34.2 Run the server

`xlwings restapi run` will run a Flask development server on <http://127.0.0.1:5000>. You can provide `--host` and `--port` as command line args and it also respects the Flask environment variables like `FLASK_ENV=development`.

If you want to have more control, you can run the server directly with Flask, see the [Flask docs](#) for more details:

```
set FLASK_APP=xlwings.rest.api
flask run
```

If you are on Mac, use `export FLASK_APP=xlwings.rest.api` instead of `set FLASK_APP=xlwings.rest.api`.

For production, you can use any WSGI HTTP Server like [gunicorn](#) (on Mac) or [waitress](#) (on Mac/Windows) to serve the API. For example, with gunicorn you would do: `gunicorn xlwings.rest.api:api`. Or with waitress (adjust the host accordingly if you want to make the api accessible from outside of localhost):

```
from xlwings.rest.api import api
from waitress import serve
serve(wsgiapp, host='127.0.0.1', port=5000)
```

34.3 Indexing

While the Python API offers Python's 0-based indexing (e.g. `xw.books[0]`) as well as Excel's 1-based indexing (e.g. `xw.books(1)`), the REST API only offers 0-based indexing, e.g. `/books/0`.

34.4 Range Options

The REST API accepts Range options as query parameters, see [xlwings.Range.options\(\)](#) e.g.

`/book/book1/sheets/0/range/A1?expand=table&transpose=true`

Remember that options only affect the value property.

34.5 Endpoint overview

End-point	Corresponds to	Short Description
<i>Book</i>	<i>Book</i>	Finds your workbook across all open instances of Excel and will open it if it can't find it
<i>Books</i>	<i>Books</i>	Books collection of the active Excel instance
<i>Apps</i>	<i>Apps</i>	This allows you to specify the Excel instance you want to work with

34.6 Endpoint details

34.6.1 /book

GET /book/<fullname_or_name>

Example response:

```
{
  "app": 1104,
  "fullname": "C:\\\\Users\\felix\\DEV\\xlwings\\scripts\\Book1.xlsx",
  "name": "Book1.xlsx",
  "names": [
    "Sheet1!myname1",
    "myname2"
  ],
  "selection": "Sheet2!$A$1",
  "sheets": [
    "Sheet1",
    "Sheet2"
  ]
}
```

GET /book/<fullname_or_name>/names

Example response:

```
{
  "names": [
    {
      "name": "Sheet1!myname1",
      "refers_to": "=Sheet1!$B$2:$C$3"
    },
    {
      "name": "myname2",
      "refers_to": "=Sheet1!$A$1"
    }
  ]
}
```

GET /book/<fullname_or_name>/names/<name>

Example response:

```
{
  "name": "myname2",
  "refers_to": "=Sheet1!$A$1"
}
```

GET /book/<fullname_or_name>/names/<name>/range

Example response:

```
{
  "address": "$A$1",
  "color": null,
  "column": 1,
  "column_width": 8.47,
  "count": 1,
  "current_region": "$A$1:$B$2",
  "formula": "=1+1.1",
  "formula_array": "=1+1,1",
  "height": 14.25,
  "last_cell": "$A$1",
  "left": 0.0,
  "name": "myname2",
  "number_format": "General",
  "row": 1,
  "row_height": 14.3,
  "shape": [
    1,
    1
  ],
  "size": 1,
  "top": 0.0,
  "value": 2.1,
  "width": 51.0
}
```

GET /book/<fullname_or_name>/sheets

Example response:

```
{
  "sheets": [
    {
      "charts": [
        "Chart 1"
      ],
      "name": "Sheet1",
      "names": [
        "Sheet1!myname1"
      ],
      "pictures": [
        "Picture 3"
      ],
      "shapes": [
```

(continues on next page)

(continued from previous page)

```

        "Chart 1",
        "Picture 3"
    ],
    "used_range": "$A$1:$B$2"
},
{
    "charts": [],
    "name": "Sheet2",
    "names": [],
    "pictures": [],
    "shapes": [],
    "used_range": "$A$1"
}
]
}

```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>

Example response:

```

{
  "charts": [
    "Chart 1"
  ],
  "name": "Sheet1",
  "names": [
    "Sheet1!myname1"
  ],
  "pictures": [
    "Picture 3"
  ],
  "shapes": [
    "Chart 1",
    "Picture 3"
  ],
  "used_range": "$A$1:$B$2"
}

```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/charts

Example response:

```

{
  "charts": [
    {
      "chart_type": "line",
      "height": 211.0,

```

(continues on next page)

(continued from previous page)

```

    "left": 0.0,
    "name": "Chart 1",
    "top": 0.0,
    "width": 355.0
  }
]
}

```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/charts/<chart_name_or_ix>

Example response:

```

{
  "chart_type": "line",
  "height": 211.0,
  "left": 0.0,
  "name": "Chart 1",
  "top": 0.0,
  "width": 355.0
}

```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/names

Example response:

```

{
  "names": [
    {
      "name": "Sheet1!myname1",
      "refers_to": "=Sheet1!$B$2:$C$3"
    }
  ]
}

```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/names/<sheet_scope_name>

Example response:

```

{
  "name": "Sheet1!myname1",
  "refers_to": "=Sheet1!$B$2:$C$3"
}

```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/names/<sheet_scope_name>/range

Example response:

```
{
  "address": "$B$2:$C$3",
  "color": null,
  "column": 2,
  "column_width": 8.47,
  "count": 4,
  "current_region": "$A$1:$B$2",
  "formula": [
    [
      "",
      ""
    ],
    [
      "",
      ""
    ]
  ],
  "formula_array": "",
  "height": 28.5,
  "last_cell": "$C$3",
  "left": 51.0,
  "name": "Sheet1!myname1",
  "number_format": "General",
  "row": 2,
  "row_height": 14.3,
  "shape": [
    2,
    2
  ],
  "size": 4,
  "top": 14.25,
  "value": [
    [
      null,
      null
    ],
    [
      null,
      null
    ]
  ],
  "width": 102.0
}
```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/pictures

Example response:

```
{
  "pictures": [
    {
      "height": 100.0,
      "left": 0.0,
      "name": "Picture 3",
      "top": 0.0,
      "width": 100.0
    }
  ]
}
```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/pictures/
<picture_name_or_ix>

Example response:

```
{
  "height": 100.0,
  "left": 0.0,
  "name": "Picture 3",
  "top": 0.0,
  "width": 100.0
}
```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/range

Example response:

```
{
  "address": "$A$1:$B$2",
  "color": null,
  "column": 1,
  "column_width": 8.47,
  "count": 4,
  "current_region": "$A$1:$B$2",
  "formula": [
    [
      "=1+1.1",
      "a string"
    ],
    [
      "43395.0064583333",
      ""
    ]
  ],
  "formula_array": null,
}
```

(continues on next page)

(continued from previous page)

```

"height": 28.5,
"last_cell": "$B$2",
"left": 0.0,
"name": null,
"number_format": null,
"row": 1,
"row_height": 14.3,
"shape": [
    2,
    2
],
"size": 4,
"top": 0.0,
"value": [
    [
        2.1,
        "a string"
    ],
    [
        "Mon, 22 Oct 2018 00:09:18 GMT",
        null
    ]
],
"width": 102.0
}

```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/range/<address>

Example response:

```

{
  "address": "$A$1:$B$2",
  "color": null,
  "column": 1,
  "column_width": 8.47,
  "count": 4,
  "current_region": "$A$1:$B$2",
  "formula": [
    [
        "=1+1.1",
        "a string"
    ],
    [
        "43395.0064583333",
        ""
    ]
  ]
}

```

(continues on next page)

(continued from previous page)

```

],
"formula_array": null,
"height": 28.5,
"last_cell": "$B$2",
"left": 0.0,
"name": null,
"number_format": null,
"row": 1,
"row_height": 14.3,
"shape": [
    2,
    2
],
"size": 4,
"top": 0.0,
"value": [
    [
        2.1,
        "a string"
    ],
    [
        "Mon, 22 Oct 2018 00:09:18 GMT",
        null
    ]
],
"width": 102.0
}

```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/shapes

Example response:

```

{
  "shapes": [
    {
      "height": 211.0,
      "left": 0.0,
      "name": "Chart 1",
      "top": 0.0,
      "type": "chart",
      "width": 355.0
    },
    {
      "height": 100.0,
      "left": 0.0,
      "name": "Picture 3",

```

(continues on next page)

(continued from previous page)

```
    "top": 0.0,
    "type": "picture",
    "width": 100.0
  }
]
```

GET /book/<fullname_or_name>/sheets/<sheet_name_or_ix>/shapes/<shape_name_or_ix>

Example response:

```
{
  "height": 211.0,
  "left": 0.0,
  "name": "Chart 1",
  "top": 0.0,
  "type": "chart",
  "width": 355.0
}
```

34.6.2 /books

GET /books

Example response:

```
{
  "books": [
    {
      "app": 1104,
      "fullname": "Book1",
      "name": "Book1",
      "names": [],
      "selection": "Sheet2!$A$1",
      "sheets": [
        "Sheet1"
      ]
    },
    {
      "app": 1104,
      "fullname": "C:\\Users\\felix\\DEV\\xlwings\\scripts\\Book1.xlsx",
      "name": "Book1.xlsx",
      "names": [
        "Sheet1!myname1",
        "myname2"
      ]
    }
  ]
}
```

(continues on next page)

(continued from previous page)

```

    ],
    "selection": "Sheet2!$A$1",
    "sheets": [
        "Sheet1",
        "Sheet2"
    ]
  },
  {
    "app": 1104,
    "fullname": "Book4",
    "name": "Book4",
    "names": [],
    "selection": "Sheet2!$A$1",
    "sheets": [
        "Sheet1"
    ]
  }
]
}

```

GET /books/<book_name_or_ix>

Example response:

```

{
  "app": 1104,
  "fullname": "C:\\Users\\felix\\DEV\\xlwings\\scripts\\Book1.xlsx",
  "name": "Book1.xlsx",
  "names": [
    "Sheet1!myname1",
    "myname2"
  ],
  "selection": "Sheet2!$A$1",
  "sheets": [
    "Sheet1",
    "Sheet2"
  ]
}

```

GET /books/<book_name_or_ix>/names

Example response:

```

{
  "names": [
    {
      "name": "Sheet1!myname1",

```

(continues on next page)

(continued from previous page)

```
    "refers_to": "=Sheet1!$B$2:$C$3"
  },
  {
    "name": "myname2",
    "refers_to": "=Sheet1!$A$1"
  }
]
```

GET /books/<book_name_or_ix>/names/<name>

Example response:

```
{
  "name": "myname2",
  "refers_to": "=Sheet1!$A$1"
}
```

GET /books/<book_name_or_ix>/names/<name>/range

Example response:

```
{
  "address": "$A$1",
  "color": null,
  "column": 1,
  "column_width": 8.47,
  "count": 1,
  "current_region": "$A$1:$B$2",
  "formula": "=1+1.1",
  "formula_array": "=1+1,1",
  "height": 14.25,
  "last_cell": "$A$1",
  "left": 0.0,
  "name": "myname2",
  "number_format": "General",
  "row": 1,
  "row_height": 14.3,
  "shape": [
    1,
    1
  ],
  "size": 1,
  "top": 0.0,
  "value": 2.1,
  "width": 51.0
}
```


GET /books/<book_name_or_ix>/sheets

Example response:

```
{
  "sheets": [
    {
      "charts": [
        "Chart 1"
      ],
      "name": "Sheet1",
      "names": [
        "Sheet1!myname1"
      ],
      "pictures": [
        "Picture 3"
      ],
      "shapes": [
        "Chart 1",
        "Picture 3"
      ],
      "used_range": "$A$1:$B$2"
    },
    {
      "charts": [],
      "name": "Sheet2",
      "names": [],
      "pictures": [],
      "shapes": [],
      "used_range": "$A$1"
    }
  ]
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>

Example response:

```
{
  "charts": [
    "Chart 1"
  ],
  "name": "Sheet1",
  "names": [
    "Sheet1!myname1"
  ],
  "pictures": [
    "Picture 3"
  ]
}
```

(continues on next page)

(continued from previous page)

```
],
"shapes": [
  "Chart 1",
  "Picture 3"
],
"used_range": "$A$1:$B$2"
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/charts

Example response:

```
{
  "charts": [
    {
      "chart_type": "line",
      "height": 211.0,
      "left": 0.0,
      "name": "Chart 1",
      "top": 0.0,
      "width": 355.0
    }
  ]
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/charts/<chart_name_or_ix>

Example response:

```
{
  "chart_type": "line",
  "height": 211.0,
  "left": 0.0,
  "name": "Chart 1",
  "top": 0.0,
  "width": 355.0
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/names

Example response:

```
{
  "names": [
    {
      "name": "Sheet1!myname1",
      "refers_to": "=Sheet1!$B$2:$C$3"
    }
  ]
}
```

(continues on next page)

(continued from previous page)

```

    }
  ]
}

```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/names/<sheet_scope_name>

Example response:

```

{
  "name": "Sheet1!myname1",
  "refers_to": "=Sheet1!$B$2:$C$3"
}

```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/names/<sheet_scope_name>/range

Example response:

```

{
  "address": "$B$2:$C$3",
  "color": null,
  "column": 2,
  "column_width": 8.47,
  "count": 4,
  "current_region": "$A$1:$B$2",
  "formula": [
    [
      "",
      ""
    ],
    [
      "",
      ""
    ]
  ],
  "formula_array": "",
  "height": 28.5,
  "last_cell": "$C$3",
  "left": 51.0,
  "name": "Sheet1!myname1",
  "number_format": "General",
  "row": 2,
  "row_height": 14.3,
  "shape": [
    2,
    2
  ],
}

```

(continues on next page)

(continued from previous page)

```
"size": 4,
"top": 14.25,
"value": [
  [
    null,
    null
  ],
  [
    null,
    null
  ]
],
"width": 102.0
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/pictures

Example response:

```
{
  "pictures": [
    {
      "height": 100.0,
      "left": 0.0,
      "name": "Picture 3",
      "top": 0.0,
      "width": 100.0
    }
  ]
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/pictures/
<picture_name_or_ix>

Example response:

```
{
  "height": 100.0,
  "left": 0.0,
  "name": "Picture 3",
  "top": 0.0,
  "width": 100.0
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/range

Example response:

```
{
  "address": "$A$1:$B$2",
  "color": null,
  "column": 1,
  "column_width": 8.47,
  "count": 4,
  "current_region": "$A$1:$B$2",
  "formula": [
    [
      "=1+1.1",
      "a string"
    ],
    [
      "43395.0064583333",
      ""
    ]
  ],
  "formula_array": null,
  "height": 28.5,
  "last_cell": "$B$2",
  "left": 0.0,
  "name": null,
  "number_format": null,
  "row": 1,
  "row_height": 14.3,
  "shape": [
    2,
    2
  ],
  "size": 4,
  "top": 0.0,
  "value": [
    [
      2.1,
      "a string"
    ],
    [
      "Mon, 22 Oct 2018 00:09:18 GMT",
      null
    ]
  ],
  "width": 102.0
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/range/<address>

Example response:

```
{
  "address": "$A$1:$B$2",
  "color": null,
  "column": 1,
  "column_width": 8.47,
  "count": 4,
  "current_region": "$A$1:$B$2",
  "formula": [
    [
      "=1+1.1",
      "a string"
    ],
    [
      "43395.0064583333",
      ""
    ]
  ],
  "formula_array": null,
  "height": 28.5,
  "last_cell": "$B$2",
  "left": 0.0,
  "name": null,
  "number_format": null,
  "row": 1,
  "row_height": 14.3,
  "shape": [
    2,
    2
  ],
  "size": 4,
  "top": 0.0,
  "value": [
    [
      2.1,
      "a string"
    ],
    [
      "Mon, 22 Oct 2018 00:09:18 GMT",
      null
    ]
  ],
  "width": 102.0
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/shapes

Example response:

```
{
  "shapes": [
    {
      "height": 211.0,
      "left": 0.0,
      "name": "Chart 1",
      "top": 0.0,
      "type": "chart",
      "width": 355.0
    },
    {
      "height": 100.0,
      "left": 0.0,
      "name": "Picture 3",
      "top": 0.0,
      "type": "picture",
      "width": 100.0
    }
  ]
}
```

GET /books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/shapes/<shape_name_or_ix>

Example response:

```
{
  "height": 211.0,
  "left": 0.0,
  "name": "Chart 1",
  "top": 0.0,
  "type": "chart",
  "width": 355.0
}
```

34.6.3 /apps

GET /apps

Example response:

```
{
  "apps": [
    {
      "books": [
        "Book1",
        "C:\\Users\\felix\\DEV\\xlwings\\scripts\\Book1.xlsx",

```

(continues on next page)

(continued from previous page)

```
        "Book4"
    ],
    "calculation": "automatic",
    "display_alerts": true,
    "pid": 1104,
    "screen_updating": true,
    "selection": "[Book1.xlsx]Sheet2!$A$1",
    "version": "16.0",
    "visible": true
  },
  {
    "books": [
      "Book2",
      "Book5"
    ],
    "calculation": "automatic",
    "display_alerts": true,
    "pid": 7920,
    "screen_updating": true,
    "selection": "[Book5]Sheet2!$A$1",
    "version": "16.0",
    "visible": true
  }
]
}
```

GET /apps/<pid>

Example response:

```
{
  "books": [
    "Book1",
    "C:\\Users\\felix\\DEV\\xlwings\\scripts\\Book1.xlsx",
    "Book4"
  ],
  "calculation": "automatic",
  "display_alerts": true,
  "pid": 1104,
  "screen_updating": true,
  "selection": "[Book1.xlsx]Sheet2!$A$1",
  "version": "16.0",
  "visible": true
}
```

GET /apps/<pid>/books

Example response:

```
{
  "books": [
    {
      "app": 1104,
      "fullname": "Book1",
      "name": "Book1",
      "names": [],
      "selection": "Sheet2!$A$1",
      "sheets": [
        "Sheet1"
      ]
    },
    {
      "app": 1104,
      "fullname": "C:\\Users\\felix\\DEV\\xlwings\\scripts\\Book1.xlsx",
      "name": "Book1.xlsx",
      "names": [
        "Sheet1!myname1",
        "myname2"
      ],
      "selection": "Sheet2!$A$1",
      "sheets": [
        "Sheet1",
        "Sheet2"
      ]
    },
    {
      "app": 1104,
      "fullname": "Book4",
      "name": "Book4",
      "names": [],
      "selection": "Sheet2!$A$1",
      "sheets": [
        "Sheet1"
      ]
    }
  ]
}
```

GET /apps/<pid>/books/<book_name_or_ix>

Example response:

```
{
  "app": 1104,
  "fullname": "C:\\Users\\felix\\DEV\\xlwings\\scripts\\Book1.xlsx",
```

(continues on next page)

(continued from previous page)

```
"name": "Book1.xlsx",
"names": [
  "Sheet1!myname1",
  "myname2"
],
"selection": "Sheet2!$A$1",
"sheets": [
  "Sheet1",
  "Sheet2"
]
}
```

GET /apps/<pid>/books/<book_name_or_ix>/names

Example response:

```
{
  "names": [
    {
      "name": "Sheet1!myname1",
      "refers_to": "=Sheet1!$B$2:$C$3"
    },
    {
      "name": "myname2",
      "refers_to": "=Sheet1!$A$1"
    }
  ]
}
```

GET /apps/<pid>/books/<book_name_or_ix>/names/<name>

Example response:

```
{
  "name": "myname2",
  "refers_to": "=Sheet1!$A$1"
}
```

GET /apps/<pid>/books/<book_name_or_ix>/names/<name>/range

Example response:

```
{
  "address": "$A$1",
  "color": null,
  "column": 1,
  "column_width": 8.47,
```

(continues on next page)

(continued from previous page)

```

"count": 1,
"current_region": "$A$1:$B$2",
"formula": "=1+1.1",
"formula_array": "=1+1,1",
"height": 14.25,
"last_cell": "$A$1",
"left": 0.0,
"name": "myname2",
"number_format": "General",
"row": 1,
"row_height": 14.3,
"shape": [
    1,
    1
],
"size": 1,
"top": 0.0,
"value": 2.1,
"width": 51.0
}

```

GET /apps/<pid>/books/<book_name_or_ix>/sheets

Example response:

```

{
  "sheets": [
    {
      "charts": [
        "Chart 1"
      ],
      "name": "Sheet1",
      "names": [
        "Sheet1!myname1"
      ],
      "pictures": [
        "Picture 3"
      ],
      "shapes": [
        "Chart 1",
        "Picture 3"
      ],
      "used_range": "$A$1:$B$2"
    },
    {
      "charts": [],

```

(continues on next page)

(continued from previous page)

```
    "name": "Sheet2",
    "names": [],
    "pictures": [],
    "shapes": [],
    "used_range": "$A$1"
  }
]
```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>

Example response:

```
{
  "charts": [
    "Chart 1"
  ],
  "name": "Sheet1",
  "names": [
    "Sheet1!myname1"
  ],
  "pictures": [
    "Picture 3"
  ],
  "shapes": [
    "Chart 1",
    "Picture 3"
  ],
  "used_range": "$A$1:$B$2"
}
```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/charts

Example response:

```
{
  "charts": [
    {
      "chart_type": "line",
      "height": 211.0,
      "left": 0.0,
      "name": "Chart 1",
      "top": 0.0,
      "width": 355.0
    }
  ]
}
```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/charts/
<chart_name_or_ix>

Example response:

```
{
  "chart_type": "line",
  "height": 211.0,
  "left": 0.0,
  "name": "Chart 1",
  "top": 0.0,
  "width": 355.0
}
```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/names

Example response:

```
{
  "names": [
    {
      "name": "Sheet1!myname1",
      "refers_to": "=Sheet1!$B$2:$C$3"
    }
  ]
}
```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/names/
<sheet_scope_name>

Example response:

```
{
  "name": "Sheet1!myname1",
  "refers_to": "=Sheet1!$B$2:$C$3"
}
```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/names/
<sheet_scope_name>/range

Example response:

```
{
  "address": "$B$2:$C$3",
  "color": null,
  "column": 2,
  "column_width": 8.47,
  "count": 4,
  "current_region": "$A$1:$B$2",

```

(continues on next page)

(continued from previous page)

```

"formula": [
  [
    "",
    ""
  ],
  [
    "",
    ""
  ]
],
"formula_array": "",
"height": 28.5,
"last_cell": "$C$3",
"left": 51.0,
"name": "Sheet1!myname1",
"number_format": "General",
"row": 2,
"row_height": 14.3,
"shape": [
  2,
  2
],
"size": 4,
"top": 14.25,
"value": [
  [
    null,
    null
  ],
  [
    null,
    null
  ]
],
"width": 102.0
}

```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/pictures

Example response:

```

{
  "pictures": [
    {
      "height": 100.0,
      "left": 0.0,

```

(continues on next page)

(continued from previous page)

```

    "name": "Picture 3",
    "top": 0.0,
    "width": 100.0
  }
]
}

```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/pictures/
<picture_name_or_ix>

Example response:

```

{
  "height": 100.0,
  "left": 0.0,
  "name": "Picture 3",
  "top": 0.0,
  "width": 100.0
}

```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/range

Example response:

```

{
  "address": "$A$1:$B$2",
  "color": null,
  "column": 1,
  "column_width": 8.47,
  "count": 4,
  "current_region": "$A$1:$B$2",
  "formula": [
    [
      "=1+1.1",
      "a string"
    ],
    [
      "43395.0064583333",
      ""
    ]
  ],
  "formula_array": null,
  "height": 28.5,
  "last_cell": "$B$2",
  "left": 0.0,
  "name": null,
  "number_format": null,

```

(continues on next page)

(continued from previous page)

```

"row": 1,
"row_height": 14.3,
"shape": [
  2,
  2
],
"size": 4,
"top": 0.0,
"value": [
  [
    2.1,
    "a string"
  ],
  [
    "Mon, 22 Oct 2018 00:09:18 GMT",
    null
  ]
],
"width": 102.0
}

```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/range/<address>

Example response:

```

{
  "address": "$A$1:$B$2",
  "color": null,
  "column": 1,
  "column_width": 8.47,
  "count": 4,
  "current_region": "$A$1:$B$2",
  "formula": [
    [
      "=1+1.1",
      "a string"
    ],
    [
      "43395.0064583333",
      ""
    ]
  ],
  "formula_array": null,
  "height": 28.5,
  "last_cell": "$B$2",
  "left": 0.0,

```

(continues on next page)

(continued from previous page)

```

"name": null,
"number_format": null,
"row": 1,
"row_height": 14.3,
"shape": [
    2,
    2
],
"size": 4,
"top": 0.0,
"value": [
    [
        2.1,
        "a string"
    ],
    [
        "Mon, 22 Oct 2018 00:09:18 GMT",
        null
    ]
],
"width": 102.0
}

```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/shapes

Example response:

```

{
  "shapes": [
    {
      "height": 211.0,
      "left": 0.0,
      "name": "Chart 1",
      "top": 0.0,
      "type": "chart",
      "width": 355.0
    },
    {
      "height": 100.0,
      "left": 0.0,
      "name": "Picture 3",
      "top": 0.0,
      "type": "picture",
      "width": 100.0
    }
  ]
}

```

(continues on next page)

(continued from previous page)

```
}
```

GET /apps/<pid>/books/<book_name_or_ix>/sheets/<sheet_name_or_ix>/shapes/
<shape_name_or_ix>

Example response:

```
{  
  "height": 211.0,  
  "left": 0.0,  
  "name": "Chart 1",  
  "top": 0.0,  
  "type": "chart",  
  "width": 355.0  
}
```

A

activate() (*xlwings.App* method), 224
 activate() (*xlwings.Book* method), 231
 activate() (*xlwings.Shape* method), 256
 activate() (*xlwings.Sheet* method), 237
 active (*xlwings.main.Apps* property), 222
 active (*xlwings.main.Books* property), 229
 active (*xlwings.main.Sheets* property), 236
 add() (*xlwings.main.Apps* method), 222
 add() (*xlwings.main.Books* method), 229
 add() (*xlwings.main.Charts* method), 257
 add() (*xlwings.main.Names* method), 263
 add() (*xlwings.main.Pictures* method), 260
 add() (*xlwings.main.Sheets* method), 236
 add() (*xlwings.main.Tables* method), 265
 add_hyperlink() (*xlwings.Range* method), 242
 address (*xlwings.Range* property), 242
 alert() (*xlwings.App* method), 224
 api (*xlwings.App* property), 224
 api (*xlwings.Book* property), 231
 api (*xlwings.Chart* property), 258
 api (*xlwings.main.Characters* property), 270
 api (*xlwings.main.Charts* property), 258
 api (*xlwings.main.Font* property), 269
 api (*xlwings.main.Names* property), 263
 api (*xlwings.main.Note* property), 265
 api (*xlwings.main.PageSetup* property), 236
 api (*xlwings.main.Pictures* property), 261
 api (*xlwings.main.Shapes* property), 255
 api (*xlwings.main.Table* property), 266
 api (*xlwings.Name* property), 264
 api (*xlwings.Picture* property), 262
 api (*xlwings.Range* property), 243
 api (*xlwings.Shape* property), 256
 api (*xlwings.Sheet* property), 237
 App (class in *xlwings*), 223
 app (*xlwings.Book* property), 231

Apps (class in *xlwings.main*), 222
 autofit() (*xlwings.Range* method), 243
 autofit() (*xlwings.RangeColumns* method), 255
 autofit() (*xlwings.RangeRows* method), 254
 autofit() (*xlwings.Sheet* method), 237

B

bold (*xlwings.main.Font* property), 269
 Book (class in *xlwings*), 230
 book (*xlwings.Sheet* property), 238
 Books (class in *xlwings.main*), 229
 books (*xlwings.App* property), 224

C

calculate() (*xlwings.App* method), 224
 calculation (*xlwings.App* property), 225
 caller() (*xlwings.Book* class method), 231
 cells (*xlwings.Sheet* property), 238
 Characters (class in *xlwings.main*), 270
 Chart (class in *xlwings*), 258
 chart_type (*xlwings.Chart* property), 258
 Charts (class in *xlwings.main*), 257
 charts (*xlwings.Sheet* property), 238
 clear() (*xlwings.Range* method), 243
 clear() (*xlwings.Sheet* method), 238
 clear_contents() (*xlwings.Range* method), 243
 clear_contents() (*xlwings.Sheet* method), 238
 clear_formats() (*xlwings.Range* method), 243
 clear_formats() (*xlwings.Sheet* method), 238
 close() (*xlwings.Book* method), 232
 color (*xlwings.main.Font* property), 269
 color (*xlwings.Range* property), 243
 column (*xlwings.Range* property), 244
 column_width (*xlwings.Range* property), 244
 columns (*xlwings.Range* property), 244
 copy() (*xlwings.Range* method), 244
 copy() (*xlwings.Sheet* method), 238
 copy_picture() (*xlwings.Range* method), 244

count (*xlwings.main.Apps* property), 222
count (*xlwings.main.Charts* property), 258
count (*xlwings.main.Names* property), 264
count (*xlwings.main.Pictures* property), 262
count (*xlwings.main.Shapes* property), 255
count (*xlwings.Range* property), 245
count (*xlwings.RangeColumns* property), 255
count (*xlwings.RangeRows* property), 254
current_region (*xlwings.Range* property), 245
cut_copy_mode (*xlwings.App* property), 225

D

data_body_range (*xlwings.main.Table* property), 266
delete() (*xlwings.Chart* method), 259
delete() (*xlwings.main.Note* method), 265
delete() (*xlwings.Name* method), 264
delete() (*xlwings.Picture* method), 262
delete() (*xlwings.Range* method), 245
delete() (*xlwings.Shape* method), 256
delete() (*xlwings.Sheet* method), 239
display_alerts (*xlwings.App* property), 225
display_name (*xlwings.main.Table* property), 267

E

enable_events (*xlwings.App* property), 225
end() (*xlwings.Range* method), 245
expand() (*xlwings.Range* method), 245

F

Font (class in *xlwings.main*), 269
font (*xlwings.main.Characters* property), 270
formula (*xlwings.Range* property), 246
formula2 (*xlwings.Range* property), 246
formula_array (*xlwings.Range* property), 246
fullname (*xlwings.Book* property), 232

G

get_address() (*xlwings.Range* method), 246

H

has_array (*xlwings.Range* property), 247
header_row_range (*xlwings.main.Table* property), 267
height (*xlwings.Chart* property), 259
height (*xlwings.Picture* property), 262
height (*xlwings.Range* property), 247
height (*xlwings.Shape* property), 256

hwnd (*xlwings.App* property), 225
hyperlink (*xlwings.Range* property), 247

I

index (*xlwings.Sheet* property), 239
insert() (*xlwings.Range* method), 248
insert_row_range (*xlwings.main.Table* property), 267
interactive (*xlwings.App* property), 225
italic (*xlwings.main.Font* property), 269

J

json() (*xlwings.Book* method), 232

K

keys() (*xlwings.main.Apps* method), 223
kill() (*xlwings.App* method), 225

L

last_cell (*xlwings.Range* property), 248
left (*xlwings.Chart* property), 259
left (*xlwings.Picture* property), 262
left (*xlwings.Range* property), 248
left (*xlwings.Shape* property), 256
load() (in module *xlwings*), 221
lock_aspect_ratio (*xlwings.Picture* property), 262

M

macro() (*xlwings.App* method), 225
macro() (*xlwings.Book* method), 232
merge() (*xlwings.Range* method), 248
merge_area (*xlwings.Range* property), 249
merge_cells (*xlwings.Range* property), 249
module
 xlwings, 221

N

Name (class in *xlwings*), 264
name (*xlwings.Book* property), 233
name (*xlwings.Chart* property), 259
name (*xlwings.main.Font* property), 269
name (*xlwings.main.Table* property), 267
name (*xlwings.Name* property), 264
name (*xlwings.Picture* property), 262
name (*xlwings.Range* property), 249
name (*xlwings.Shape* property), 256
name (*xlwings.Sheet* property), 239

Names (*class in xlwings.main*), 263
 names (*xlwings.Book property*), 233
 names (*xlwings.Sheet property*), 239
 Note (*class in xlwings.main*), 265
 note (*xlwings.Range property*), 249
 number_format (*xlwings.Range property*), 249

O

offset() (*xlwings.Range method*), 249
 open() (*xlwings.main.Books method*), 229
 options() (*xlwings.Range method*), 249

P

page_setup (*xlwings.Sheet property*), 239
 PageSetup (*class in xlwings.main*), 236
 parent (*xlwings.Chart property*), 259
 parent (*xlwings.main.Table property*), 267
 parent (*xlwings.Picture property*), 262
 parent (*xlwings.Shape property*), 256
 paste() (*xlwings.Range method*), 250
 path (*xlwings.App property*), 226
 Picture (*class in xlwings*), 262
 Pictures (*class in xlwings.main*), 260
 pictures (*xlwings.Sheet property*), 239
 pid (*xlwings.App property*), 226
 print_area (*xlwings.main.PageSetup property*), 236
 properties() (*xlwings.App method*), 226

Q

quit() (*xlwings.App method*), 227

R

Range (*class in xlwings*), 242
 range (*xlwings.main.Table property*), 267
 range() (*xlwings.App method*), 227
 range() (*xlwings.Sheet method*), 239
 RangeColumns (*class in xlwings*), 254
 RangeRows (*class in xlwings*), 254
 raw_value (*xlwings.Range property*), 251
 refers_to (*xlwings.Name property*), 264
 refers_to_range (*xlwings.Name property*), 264
 render_template() (*xlwings.App method*), 227
 render_template() (*xlwings.Book method*), 233
 render_template() (*xlwings.Sheet method*), 240
 resize() (*xlwings.main.Table method*), 267
 resize() (*xlwings.Range method*), 251
 row (*xlwings.Range property*), 251

row_height (*xlwings.Range property*), 251
 rows (*xlwings.Range property*), 251

S

save() (*xlwings.Book method*), 233
 scale_height() (*xlwings.Shape method*), 256
 scale_width() (*xlwings.Shape method*), 256
 screen_updating (*xlwings.App property*), 228
 select() (*xlwings.Range method*), 252
 select() (*xlwings.Sheet method*), 240
 selection (*xlwings.App property*), 228
 selection (*xlwings.Book property*), 234
 set_mock_caller() (*xlwings.Book method*), 234
 set_source_data() (*xlwings.Chart method*), 259
 Shape (*class in xlwings*), 255
 shape (*xlwings.Range property*), 252
 Shapes (*class in xlwings.main*), 255
 shapes (*xlwings.Sheet property*), 240
 Sheet (*class in xlwings*), 237
 sheet (*xlwings.Range property*), 252
 sheet_names (*xlwings.Book property*), 234
 Sheets (*class in xlwings.main*), 236
 sheets (*xlwings.Book property*), 234
 show_autofilter (*xlwings.main.Table property*), 267
 show_headers (*xlwings.main.Table property*), 267
 show_table_style_column_stripes (*xlwings.main.Table property*), 267
 show_table_style_first_column (*xlwings.main.Table property*), 267
 show_table_style_last_column (*xlwings.main.Table property*), 267
 show_table_style_row_stripes (*xlwings.main.Table property*), 267
 show_totals (*xlwings.main.Table property*), 267
 size (*xlwings.main.Font property*), 269
 size (*xlwings.Range property*), 252
 startup_path (*xlwings.App property*), 228
 status_bar (*xlwings.App property*), 228

T

Table (*class in xlwings.main*), 266
 table (*xlwings.Range property*), 252
 table_style (*xlwings.main.Table property*), 267
 Tables (*class in xlwings.main*), 265
 tables (*xlwings.Sheet property*), 240
 text (*xlwings.main.Characters property*), 270
 text (*xlwings.main.Note property*), 265

`text` (*xlwings.Shape* property), 257
`to_html()` (*xlwings.Sheet* method), 240
`to_pdf()` (*xlwings.Book* method), 234
`to_pdf()` (*xlwings.Chart* method), 259
`to_pdf()` (*xlwings.Range* method), 252
`to_pdf()` (*xlwings.Sheet* method), 240
`to_png()` (*xlwings.Chart* method), 259
`to_png()` (*xlwings.Range* method), 252
`top` (*xlwings.Chart* property), 260
`top` (*xlwings.Picture* property), 262
`top` (*xlwings.Range* property), 253
`top` (*xlwings.Shape* property), 257
`totals_row_range` (*xlwings.main.Table* property),
267
`type` (*xlwings.Shape* property), 257

U

`unmerge()` (*xlwings.Range* method), 253
`update()` (*xlwings.main.Table* method), 268
`update()` (*xlwings.Picture* method), 263
`used_range` (*xlwings.Sheet* property), 241

V

`value` (*xlwings.Range* property), 253
`version` (*xlwings.App* property), 228
`view()` (in module *xlwings*), 221
`visible` (*xlwings.App* property), 228
`visible` (*xlwings.Sheet* property), 241

W

`width` (*xlwings.Chart* property), 260
`width` (*xlwings.Picture* property), 263
`width` (*xlwings.Range* property), 253
`width` (*xlwings.Shape* property), 257
`wrap_text` (*xlwings.Range* property), 253

X

`xlwings`
 module, 221
`xlwings.arg()` (in module *xlwings*), 271
`xlwings.func()` (in module *xlwings*), 271
`xlwings.ret()` (in module *xlwings*), 271
`xlwings.sub()` (in module *xlwings*), 271